

People's Republic of Bangladesh
Ministry of Shipping
Ministry of Road Transport and Bridges
Chittagong Port Authority
Roads and Highways Department

Preparatory Survey
on the Matarbari Port Development
in People's Republic of Bangladesh

Final Report

December 2018

Japan International Cooperation Agency (JICA)
The Overseas Coastal Area Development Institute of Japan
Oriental Consultants Global Co., Ltd
Nippon Koei Co., Ltd
PADECO Co., Ltd

Exchange Rate (As of Apr, 2018)
1.00 USD = 82.891 BDT = 106.106 JPY

Contents

0.	Executive Summary	0-1
1.	Introduction	1-1
1.1	Purpose of Survey	1-1
1.2	Outline of Survey	1-1
1.3	Target Area	1-3
1.4	Survey Schedule.....	1-5
1.5	Major Meetings and Activities	1-6
2.	Port Development.....	2-1
2.1	Port Policy and Trend of Maritime Logistics	2-1
2.1.1	Port Policy Direction	2-1
2.1.2	Trend of Maritime Logistics	2-3
2.1.3	Relevant Port Development projects	2-8
2.2	Cargo Demand Forecast.....	2-14
2.2.1	Container Cargo Demand Forecast.....	2-14
2.2.2	Bulk Cargo Demand Forecast.....	2-18
2.3	Port Development Plan	2-19
2.3.1	Regional Development Plans and Other Related Projects.....	2-19
2.3.2	Requirement of Facilities	2-26
2.3.3	Prediction of Vessel Type and Size.....	2-27
2.3.4	Alternatives.....	2-29
2.3.5	Port Development Plan.....	2-31
2.4	Port Facility Plan.....	2-34
2.4.1	Mooring Facility	2-34
2.4.2	Yard and other Facilities.....	2-57
2.4.3	Cargo Handling Equipment	2-60
2.4.4	Channel, Basin and other Marine Facilities.....	2-70
2.4.5	Navigational Safety Aids	2-84
2.4.6	Security Facilities	2-96
2.5	Preliminary Design, Specification and Quantity	2-100
2.5.1	Mooring Facility	2-100
2.5.2	Yard and other Facilities, including Soil Improvement and Drainage.....	2-110
2.5.3	Cargo Handling Equipment	2-132
2.5.4	Channel, Basin and other Marine Facilities.....	2-141
2.5.5	Navigational Safety Aids	2-154
2.5.6	Security Facilities	2-167
2.	2-168

2.6.	Construction Plan.....	2-169
2.6.1.	Mooring Facility.....	2-169
2.6.2	Yard and other Facilities.....	2-171
2.6.3	Channel, Basin and other Marine Facilities, Soil Disposal	2-173
2.6.4.	Cargo Handling Equipment.....	2-180
2.6.5	Navigational Aids and Others.....	2-181
2.7	Preliminary Cost and Schedule	2-183
2.7.1	Procurement of Materials and Construction Equipment	2-183
2.7.2	Preliminary Cost.....	2-187
2.7.3	Demarcation between Matarbari coal fired power plant project and Port development project	2-189
2.7.4	Preliminary Schedule.....	2-196
2.7.5	Measures for Construction Safety	2-198
2.8	Maintenance and Management of Facilities.....	2-205
2.8.1	Channel and Basin.....	2-205
2.8.2	Offshore Disposal of Dredged Soil.....	2-222
2.8.3	Shoreline Deformation and Countermeasure	2-244
2.8.4	Beach Profile Survey	2-273
2.9	Port Management and Operation	2-276
2.9.1	Port Management.....	2-276
2.9.2	Port Operation	2-281
2.9.3	Port Promotion.....	2-283
2.10	Outline and Cost of Port Consulting	2-287
2.10.1	Packaging, Procurement, Standard and Major Facilities.....	2-287
2.10.2	Outline of Port Consulting Service.....	2-287
3.	ACCESS ROAD DEVELOPMENT	3-1
3.1	Present Situation of Road Transport Infrastructure.....	3-1
3.1.1	Present Road Network in Bangladesh	3-1
3.1.2	Existing Road Development Plans and Proposals.....	3-8
3.1.3	Existing Regional Development Plans and Proposals.....	3-18
3.2	Road Freight Transport Planning	3-20
3.2.1	Required Developments for Road Freight Transport.....	3-20
3.2.2	Port Access from National Highway	3-21
3.2.3	Traffic Demand Analysis	3-26
3.2.4	Improvement of National Highway.....	3-52
3.3	Natural Condition Survey	3-61
3.3.1	Topographic Survey.....	3-61
3.3.2	Geotechnical Investigation	3-64
3.3.3	Satellite Image and Digital Terrain Data	3-65
3.	ACCESS ROAD DEVELOPMENT	3-66

3.1	Present Situation of Road Transport Infrastructure.....	3-66
3.2	Road Freight Transport Planning	3-66
3.3	Natural Condition Survey	3-66
3.4	Preliminary Design.....	3-67
3.4.1	Highway Design	3-67
3.4.2	Bridge Design.....	3-88
3.4.3	Soft Ground Analysis and Design	3-110
3.4.4	Hydraulic and Hydrological Study.....	3-117
3.	ACCESS ROAD DEVELOPMENT	3-176
3.1	Present Situation of Road Transport Infrastructure.....	3-176
3.2	Road Freight Transport Planning	3-176
3.3	Natural Condition Survey	3-176
3.4	Preliminary Design.....	3-176
3.5	Construction Planning and Cost Estimates	3-177
3.5.1	Construction Planning	3-177
3.5.2	Cost Estimates	3-191
3.6	Implementation Plan	3-201
3.6.1	Implementation Strategy (Phased Construction).....	3-201
3.6.2	Scope of the Project.....	3-202
3.6.3	Justification for the Project Scope.....	3-211
3.6.4	Implementation Schedule	3-243
3.6.5	Implementation Structure	3-243
3.6.6	Consultancy Services.....	3-246
3.6.7	Operation and Maintenance Plan.....	3-249
4.	Environmental and Social Consideration.....	4-1
4.1	Outline of Project Components causing Environmental and Social Impact.....	4-1
4.1.1	Outline of Project Components causing Environmental and Social Impact.....	4-1
4.1.2	Adjacent Project.....	4-4
4.2	Baseline Data of the National and Socio-economic Environment.....	4-5
4.2.1	Natural Environment.....	4-5
4.2.2	Social Environment.....	4-13
4.3	Environmental and Social Consideration Laws and Institutions.....	4-23
4.3.1	Laws and Standards related to Environmental and Social Considerations.....	4-23
4.3.2	Relevant Organizations.....	4-38
4.3.3	Gender-related Laws and Policies.....	4-40
4.4	Analysis of the Alternatives (Including “without Project”).....	4-42
4.4.1	Port.....	4-42
4.4.2	Access Road	4-49
4.5	Cumulative Impact.....	4-61
4.5.1	Background.....	4-61

4.5.2	Concept of Cumulative Impact.....	4-61
4.5.3	The method of cumulative impact in this project.....	4-61
4.6	Scoping and TOR of Environmental and Social Consideration Survey.....	4-64
4.6.1	Scoping (Port).....	4-64
4.6.2	Scoping (Access Road).....	4-68
4.6.3	Survey TOR (Port).....	4-72
4.6.4	Survey TOR (Access Road).....	4-74
4.7	Environmental Impact Assessment.....	4-77
4.7.1	Result of Impact Assessment (Port).....	4-77
4.7.2	Result of Impact Assessment (Access Road).....	4-82
4.8	Results of Environmental and Social Consideration Survey (Including Anticipated Impacts).....	4-87
4.8.1	Port.....	4-87
4.8.2	Access road.....	4-139
4.8.3	Cumulative Impact.....	4-162
4.9	Environmental Management and Monitoring Plan (Including the implementation plan).....	4-171
4.9.1	Port.....	4-171
4.9.2	Access Road.....	4-174
4.10	Stakeholder Meetings.....	4-232
4.10.1	Stakeholder Meetings Required by Laws in Bangladesh.....	4-232
4.10.2	Stakeholder Meetings in the Project.....	4-232
4.10.3	Stakeholders Analysis.....	4-232
4.10.4	Result of Stakeholder Meetings.....	4-234
4.11	Land Acquisition and Resettlement.....	4-256
4.11.1	Requirement for Land Acquisition and Resettlement.....	4-256
4.11.2	Legal Framework for Land Acquisition and Resettlement.....	4-259
4.11.3	Scale and Scope of Land Acquisition and Resettlement.....	4-268
4.11.4	Compensation and Assistance Policy.....	4-304
4.11.5	Grievance Redress Mechanism.....	4-319
4.11.6	Institutional Arrangements.....	4-322
4.11.7	Implementation Schedule.....	4-324
4.11.8	Resettlement Budget and its Source.....	4-328
4.11.9	Monitoring and Evaluation.....	4-336
4.11.10	Public Consultations.....	4-338
5.	Economic and Financial Analysis.....	5-1
5.1.	Financial Analysis for Port Investment.....	5-1
5.1.1	Financial Situation of CPA.....	5-1
5.1.2	Financial Simulation Model.....	5-3
5.1.3	Financial Analysis of Port Investment.....	5-8
5.2.	Economic Analysis of Port and Road Investment.....	5-21

5.2.1	Preconditions	5-21
5.2.2	Benefit of the Port Project	5-22
5.2.3	Economic Analysis on Access Road Investment	5-23
5.2.4	EIRR of the Project	5-26
5.3.	Project Outcome Indicators	5-30
6.	Conclusions and Recommendation	6-1
6.1	Port Development Project	6-1
6.1.1	Cyclic Review on Cargo Demand and Port Planning.....	6-1
6.1.2	Coordination with related development plan in Moheshkhali.....	6-1
6.1.3	Close collaboration of Ultra Super Critical Coal Fired Power Generation Project	6-1
6.1.4	Siltation and Maintenance Dredging in Approach Channel and Basin	6-1
6.1.5	Port Management and Promotion	6-2
6.1.6	Utilization of Advanced Technologies of Japan and Technical Guidance.....	6-2
6.1.7	Navigation Safety	6-2
6.2	Project Risks and Adaptation Measures	6-3
6.	Conclusions and Recommendations.....	6-11
6.1	Port Development Project	6-11
6.2	Access Road Development Project	6-12
6.	Conclusion and Recommendation.....	6-13
6.3	Environmental and Social Considerations	6-14
6.3.1	Environmental Considerations (Port).....	6-14
6.3.2	Environmental Consideration (Access Road).....	6-15
6.3.3	Social Considerations	6-15

List of Figures

Figure 1.3-1 Target Area.....	1-3
Figure 1.3-2 Survey Area and Surrounding Situation	1-4
Figure 1.4-1 Actual Survey Schedule.....	1-5
Figure 2.1-1 River Ports and Railway ICDs around Dhaka	2-5
Figure 2.1-2 Desired Shape of Export Cargo Flows	2-7
Figure 2.1-3 General Layout Plan of BCD, Phase II (ADB Report).....	2-10
Figure 2.1-4: Approach Channel to Payra Port	2-13
Figure 2.2-1: Flowchart of container cargo forecast	2-14
Figure 2.2-2 Comparison of Base Case (2026 and 2041).....	2-17
Figure 2.2-3 Comparison between Payra and Matarbari for Each Scenario (2026).....	2-17
Figure 2.3-1 Moheshkhali Block Diagram.....	2-20
Figure 2.3-2 Preliminary Plan of Rail Route to Matarbari.....	2-21
Figure 2.3-3 Matarbari Ultra Super Critical Coal Fired Plant Layout.....	2-22
Figure 2.3-4 Pipelines from SPM and Delivery Pipeline to Chittagong	2-24
Figure 2.3-5 Options of Marine Facility for LPG by SK GAS	2-25
Figure 2.3-6 Alternative Plans in the Estuary of Kohelia River.....	2-30
Figure 2.3-7 Phase 1 of the First Stage Development	2-31
Figure 2.3-8 Phase 2 of the First Stage Development	2-32
Figure 2.3-9 Second Stage and Industrial Port Development	2-33
Figure 2.4-1 Ground plan of the port area and boring locations	2-37
Figure 2.4-2 Subsurface section (BH-7 ~ BH-11).....	2-39
Figure 2.4-3 Subsurface section (BH-12~BH-16).....	2-40
Figure 2.4-4 Subsurface section (BH-17~BH-19).....	2-41
Figure 2.4-5 Subsurface section (BH-7~BH-12~BH-17).....	2-41
Figure 2.4-6 Subsurface section (BH-8~BH-13~BH-18).....	2-42
Figure 2.4-7 Subsurface section (BH-9~BH-14~BH-19).....	2-42
Figure 2.4-8 Subsurface section (BH-10~BH-15).....	2-43
Figure 2.4-9 Subsurface section (BH-11~BH-16).....	2-43
Figure 2.4-10 Seismic Zone Coefficient of Bangladesh.....	2-44
Figure 2.4-11 General Layout Plan of Mooring Facilities and Water Area.....	2-50
Figure 2.4-12 Required Water Area for Berthing and Un-docking	2-50
Figure 2.4-13 Harbor Craft Basin.....	2-54
Figure 2.4-14 Steel Sheet Pile Quay and Inner Breakwater	2-55
Figure 2.4-15 Wave Dissipating Conc. Block Quay at Basin Slip	2-55
Figure 2.4-16 West end Revetment	2-56
Figure 2.4-17 East Revetment and future Expansion of Mooring Facilities (Phase 2)	2-56
Figure 2.4-18 Matarbari Port General Layout Plan.....	2-59

Figure 2.4-19	Terminal layout of each phase of the Matarbari Port development plan	2-60
Figure 2.4-20	Terminal layout (Phase 1).....	2-61
Figure 2.4-21	Sediment Mitigation Dike.....	2-70
Figure 2.4-22	Proposed layout plan of north and south side Dike structure for new port.....	2-72
Figure 2.4-23	Layout plan of channel and basin for new port	2-74
Figure 2.4-24	Experimental results of wave transmission coefficient for Rubble Mound type dike .	2-77
Figure 2.4-25	Wave height distribution.....	2-78
Figure 2.4-26	Wave height distribution.....	2-80
Figure 2.4-27	Example of wave height ratio distribution by Boussinesq method and location of evaluate point for harbor oscillation.....	2-83
Figure 2.4-28	Wave height ratio versus input wave height with respect to incident wave period	2-83
Figure 2.4-29	VTMS facilities in Chittagong Port.....	2-85
Figure 2.4-30	VTMS in Chittagong Port.....	2-85
Figure 2.4-31	Location of VTMS Facilities in Matarbari Port.....	2-86
Figure 2.4-32	Lighted Buoys, and Leading Lights.....	2-87
Figure 2.4-33	Location of Lighted Buoys, and Leading Lights in Matarbari Port.....	2-88
Figure 2.4-34	Tugboat at Chittagong Port.....	2-89
Figure 2.4-35	Pilot Boat at Chittagong Port.....	2-90
Figure 2.4-36	Location of Pilot Station at Chittagong Port.....	2-91
Figure 2.4-37	Survey Boat at Chittagong Port	2-92
Figure 2.4-38	Security boats at Chittagong Port	2-93
Figure 2.4-39	Some of Service Boats at Chittagong Port.....	2-94
Figure 2.4-40	Fences in Chittagong Port.....	2-96
Figure 2.4-41	Security Camera in Chittagong Port.....	2-96
Figure 2.4-42	Lights in Chittagong Port	2-97
Figure 2.4-43	Gate No.4 of Chittagong Port	2-97
Figure 2.4-44	Fire Station in Chittagong Port	2-97
Figure 2.4-45	Fences around Terminal.....	2-98
Figure 2.5-1	Layout Plan of Quay Piles, Struts and Ancillary (Fenders Mooting Bollards).....	2-101
Figure 2.5-2	Bending Moment Diagram	2-102
Figure 2.5-3	Wave Uplift and Wave Crest Hight.....	2-104
Figure 2.5-4	Typical Cross Section of Quay	2-105
Figure 2.5-5	Rubber Fender System.....	2-107
Figure 2.5-6	Mid-Level Mooring Point (Cleat) and Cat-walk	2-108
Figure 2.5-7	Soil Stratification (BH-7 ~ BH-11) along the Quay Center Line	2-109
Figure 2.5-8	Slope Protection and soil replacement under Quay Deck.....	2-109
Figure 2.5-9	Typical Section of Berth	2-110
Figure 2.5-10	Tentative slope after dredging and subsoil stratification	2-111
Figure 2.5-11	Tentative slope after dredging and subsoil stratification	2-112
Figure 2.5-12	Tentative slope after dredging and subsoil stratification	2-112

Figure 2.5-13	e vs log P relationship	2-117
Figure 2.5-14	Schematic distribution of layers with possibility of liquefaction	2-121
Figure 2.5-15	Typical section of Pavement and RTG Traveling PC Slab	2-123
Figure 2.5-16	Storm Drainage Plan.....	2-124
Figure 2.5-17	Schematic Water Supply System	2-125
Figure 2.5-18	Schematic Power Supply Diagram	2-128
Figure 2.5-19	Schematic Plan of Electric Power Supply and Yard Lighting	2-128
Figure 2.5-20	Schematic overview of Quayside Container Crane (QC).....	2-137
Figure 2.5-21	Location and type of seismic isolation device.....	2-137
Figure 2.5-22	Schematic overview of Multi-purpose Gantry Crane (MGC)	2-138
Figure 2.5-23	Schematic overview of Rubber Tyred Gantry Crane (RTG).....	2-140
Figure 2.5-24	Tide condition at the project site.....	2-143
Figure 2.5-25:	Location of the Wave Predicted Location.....	2-145
Figure 2.5-26	Designed cross section of Steel Pipe Pile wall for Training Dike	2-147
Figure 2.5-27	Typical cross section of the proposed Rubble Mound Dike	2-148
Figure 2.5-28	Location of Soil Survey for additional countermeasure works by MUSCCPP	2-149
Figure 2.5-29 (1)	Longitudinal soil profile along Training Dike	2-150
Figure 2.5-30 (1)	Cross section of Training Dike.....	2-151
Figure 2.5-31	Cross section of Extension part	2-153
Figure 2.5-32	Coverage Area of Radar.....	2-155
Figure 2.5-33	Preliminary Configuration of VTMS.....	2-155
Figure 2.5-34	Details around Terminals	2-156
Figure 2.5-35	Pillar-type Lighted Buoy	2-157
Figure 2.5-36	Description of Lateral Marks.....	2-158
Figure 2.5-37	Function of Leading Lights	2-158
Figure 2.5-38	Example of Beacon.....	2-159
Figure 2.5-39	Description of Leading Lines	2-160
Figure 2.5-40	Relationship between Size of Cargo Vessel and Power of Tugboat	2-162
Figure 2.5-41	Example of Azimuth Propeller	2-163
Figure 2.5-42	Example of 4,400PS Tugboat	2-164
Figure 2.5-43	Example of Pilot Boat.....	2-165
Figure 2.5-44	Example of Survey boat.....	2-166
Figure 2.5-45	Example of Cable Duct in a Port in Japan.....	2-167
Figure 2.6-1	Dredged volume of each area	2-173
Figure 2.6-2	Dredging Plants: SCD (left) and TSHD (right)	2-174
Figure 2.6-3	Dredging by CSD	2-175
Figure 2.6-4	Location of disposal area (left: on-shore) and (right: off-shore)	2-176
Figure 2.6-5	Off-shore dumping by CSD.....	2-176
Figure 2.6-6	Off-shore dumping by TSHD	2-176
Figure 2.6-7	Sample Picture of on-shore disposal method.....	2-177

Figure 2.6-8 Sample Picture of reclamation work.....	2-177
Figure 2.6-9 Sample Picture of sand barge	2-178
Figure 2.6-10 Sample Picture of stone work.....	2-178
Figure 2.6-11 Sample Picture of fabrication and installation of armor concrete block.....	2-179
Figure 2.6-12 Preliminary Installation Schedule of VTMS	2-181
Figure 2.6-13 Preliminary Installation Schedule of Service Boats	2-182
Figure 2.7-1 Sample Picture of Piling Barge.....	2-184
Figure 2.7-2 Sample Picture of Crane Barge.....	2-184
Figure 2.7-3 Sample Picture of Material Barge.....	2-185
Figure 2.7-4 Sample Picture of Excavator	2-185
Figure 2.7-5 Sample Picture of Dump Truck	2-185
Figure 2.7-6 Sample Picture of PVD Machine.....	2-186
Figure 2.7-7 Sample Picture of Dredger.....	2-186
Figure 2.7-8 Sample Picture of Crane	2-186
Figure 2.7-9 Training Dike and Breakwater.....	2-189
Figure 2.7-10 Dredging area and Project Allocation (1)	2-191
Figure 2.7-11 Dredging area and Project Allocation (2)	2-191
Figure 2.7-12 Trial Calculation results of Maintenance Dredging Cost for CPA.....	2-195
Figure 2.7-13 Outline of the overall implementation schedule	2-196
Figure 2.7-14 Preliminary Construction Schedule	2-197
Figure 2.8-1 Original layout plan of port for Matarbari Power Plant.....	2-205
Figure 2.8-2 Observed and Calculated Results of Cumulative Thickness at Monitoring Pocket with water depth of MSL -10m	2-207
Figure 2.8-3 Observed and Calculated Results of Cumulative Thickness at Monitoring Pocket with water depth of MSL -5m	2-207
Figure 2.8-4 Topographical Change from Apr. 2016 to Feb. 2017.....	2-208
Figure 2.8-5 Topographical Change from Feb. 2017 to Oct. 2017.....	2-208
Figure 2.8-6 Comparison of the observed and calculated results of monthly deposition thickness of Temporary Channel	2-209
Figure 2.8-7 Schematic figure of the channel and basin area and the separation of the part of the area for the presentation of the volume and thickness of deposition	2-210
Figure 2.8-8 Annual deposition volume of channel and basin for original port layout plan.....	2-211
Figure 2.8-9 Annual deposition thickness of channel and basin for original port layout plan.....	2-211
Figure 2.8-10 Annual deposition volume of channel and basin for countermeasure	2-212
Figure 2.8-11 Annual deposition thickness of channel and basin for countermeasure Case5	2-213
Figure 2.8-12 Locations, P1 to P5, of monitoring of oceanographic	2-214
Figure 2.8-13 Layout plan of Phase 2 (Left) and Areas for the calculation of the amount of total sedimentation volume for Phase2 (Right)	2-215
Figure 2.8-14 Calculated annual sedimentation volume	2-216
Figure 2.8-15 Calculated spatial average annual deposition thickness	2-216

Figure 2.8-16 Comparison of the observed and calculated results of monthly deposition thickness of Temporary Channel from Apr. 3, 2017 to June 18, 2017	2-219
Figure 2.8-17 Comparison of the observed and calculated results of monthly deposition thickness of Temporary Channel from Jun 18, 2017 to July 24, 2017	2-219
Figure 2.8-18 Comparison of the observed and calculated results of monthly deposition thickness of Temporary Channel from July 24, 2017 to Oct 13, 2017	2-220
Figure 2.8-19 Calculated annual sedimentation volume	2-221
Figure 2.8-16 Candidate site of dumping of dredged soil material near the project site.....	2-223
Figure 2.8-17 Work plan of the dredging and reclamation.....	2-224
Figure 2.8-18 Relation between sediment particle size and critical turbidity velocity	2-226
Figure 2.8-19 Simulated Area and Grid size (for Dredging work).....	2-231
Figure 2.8-20 Simulated Area and Grid size (for Dumping site)	2-232
Figure 2.8-21 Computation Area and the Tidal Condition Setting Method at the Boundary	2-233
Figure 2.8-22 Comparison of the simulated tide record by major 8 constituents and by M2 constituent	2-234
Figure 2.8-23 Location of Major Rivers.....	2-235
Figure 2.8-24 Monthly River Discharge from Ganges and Brahmaputra River	2-235
Figure 2.8-25 Rivers near the Project Site.....	2-236
Figure 2.8-26 Examples of Observed Vertical Profile of the Water Temperature and Salinity Data.....	2-237
Figure 2.8-27 SS diffusion by dumping (red box indicate dumping site : case1-2)	2-239
Figure 2.8-28 SS diffusion by dumping (red box indicate dumping site : case1-2)	2-240
Figure 2.8-29 SS diffusion by dredging works (case2-2)	2-241
Figure 2.8-30 SS diffusion by dredging works (case2-2)	2-242
Figure 2.8-31 Observed SS record near the site (Mar. 2017 to Apr. 2017)	2-243
Figure 2.8-32 Topographical condition before and after the construction of Port (Phase2)	2-245
Figure 2.8-33 Wave height change due to construction of Port (Phase2)	2-246
Figure 2.8-34 Depth-averaged tidal current change before and after construction of port (Phase2) (Dry Season: red indicate tidal current acceleration and blue indicate tidal current deceleration by construction of port)	2-247
Figure 2.8-35 Depth-averaged tidal current change before and after construction of port (Phase2) (Dry Season: red indicate tidal current acceleration and blue indicate tidal current deceleration by construction of port)	2-248
Figure 2.8-36 Data collected area map.....	2-249
Figure 2.8-37 (1) Collected Satellite Image data and divided section for following analysis.....	2-250
Figure 2.8-38 Sonadia Island coastline (3 Zone for detail consideration in Figure 1-16).....	2-253
Figure 2.8-39 Detail coastline change of Sonadia Island for each three zone.....	2-253
Figure 2.8-40 Chart data near Sonadia Island (edition of June 2009).....	2-254
Figure 2.8-41 Detail of the aerial photo of northern part of Sonadia coast.....	2-255
Figure 2.8-42 Chart data in front of Sonadia Island.....	2-255
Figure 2.8-43 Matarbari Island coastline (3 Zone for detail consideration in Figure 1-19).....	2-256

Figure 2.8-44 (1) Detail coastline change of Matarbari Island (Zone 1).....	2-257
Figure 2.8-45 Detail of the aerial photo of Zone 1	2-260
Figure 2.8-46 Chart data near Sonadia Island (edition of June 2009).....	2-260
Figure 2.8-47 Overall dominant longshore sand transport (yellow arrows) and assumed location of major supply of sand by on-off shore sand transport	2-261
Figure 2.8-48 Coordinate system for the numerical simulation model	2-262
Figure 2.8-49 Assumption to calculate the shoreline change	2-262
Figure 2.8-50 Schematic figure of longshore sand transport trapped by jetty	2-263
Figure 2.8-51 Cross-sectional distribution of longshore sediment transport.....	2-264
Figure 2.8-52 Beach profile survey data	2-264
Figure 2.8-53 Wave direction histogram for Rainy Season (May to September).....	2-265
Figure 2.8-54 Wave direction histogram for Dry Season (Oct. to Apr.).....	2-265
Figure 2.8-55 Selected section of shoreline where the effect of on-offshore sediment transport on shoreline changes are negligible and longshore sand transport at both end of the section is balanced	2-268
Figure 2.8-56 Calculated comparable shoreline after collecting the shoreline location by tide elevation difference.....	2-269
Figure 2.8-57 Comparison of shoreline changes for validity analysis (longshore distance from 4,000 to 6,000m are used for the analysis).....	2-271
Figure 2.8-58 Difference of the predicted future shoreline without the construction of port and that with construction of port	2-272
Figure 2.8-59 Beach Profile Survey Location and Result during Dry Season	2-273
Figure 2.8-59 Beach Profile Survey Location and Result during Monsoon Season	2-274
Figure 2.8-59 Comparison of Beach Profile between Dry (Red) and Monsoon (Blue) Season.....	2-275
Figure 2.9-1 Proposal of PIU of CPA.....	2-280
Figure 3.1-1 Bangladesh Road Network	3-2
Figure 3.1-2 Present Road Details of N1 & R170.....	3-3
Figure 3.1-3 Asian Highway Route Map	3-4
Figure 3.1-4 SASEC Economic Corridors	3-6
Figure 3.1-5 BIMSTEC Road Corridor in Bangladesh	3-7
Figure 3.1-6 On-going and Proposed Projects	3-17
Figure 3.1-7 Maheshkhali Block Diagram.....	3-18
Figure 3.1-8 Preliminary Plan of Rail Route to Matarbari	3-19
Figure 3.2-1 Alternative Route Options	3-22
Figure 3.2-2 Hierarchy of Roads.....	3-25
Figure 3.2-3 Possible Future Extension of Road in Maheshkhali	3-25
Figure 3.2-4 Traffic Survey Locations	3-27
Figure 3.2-5 Directional Traffic Count Locations.....	3-28
Figure 3.2-6 Vehicle Based Modal share of Mainstream Traffic at 3 Intersections (Weekday).....	3-28
Figure 3.2-7 Directional Traffic Flow at each Junction.....	3-29

Figure 3.2-8	Daily Traffic (including SMV) on R172 to and from Matarbari Direction	3-31
Figure 3.2-9	Modal Share of Daily Traffic Flow on R172 in 2017 (weekday).....	3-31
Figure 3.2-10	Zoning of the Study Area.....	3-32
Figure 3.2-11	Tentative Location & Traffic Volume on N1 (From Chittgong to Cox's bazar)	3-34
Figure 3.2-12	Flow of Estimation of Cargo Container Truck	3-35
Figure 3.2-13	Flow of Estimation of Bulk Container Truck	3-35
Figure 3.2-14	Flow of Estimation of Diverted Traffic	3-36
Figure 3.2-15	Flow of Estimation of Traffic Demand by Development Activities	3-36
Figure 3.2-16	GDP Growth Rate in Bangladesh (2005 - 2015)	3-37
Figure 3.2-17	Change of Vehicular Growth of Bangladesh from 2011 to 2015.....	3-38
Figure 3.2-18	Relation between GDP and Vehicle Registration Number	3-38
Figure 3.2-19	Change of Vehicle share for Daily Traffic Flow on Access Road (2026 ~ 2035).....	3-48
Figure 3.2-20	Change of Vehicle Share for Daily Traffic Flow on N1 (2026 ~ 2035).....	3-49
Figure 3.2-21	Peak Hour Traffic Flow of R172 and Access Road in 2026	3-50
Figure 3.2-22	Directional Traffic Diagram in 2026 at Intersecting Point with N1	3-51
Figure 3.2-23	Example of Improvement of N1	3-53
Figure 3.2-24	National Highway No.1 (Chittagong-Chakaria Section).....	3-55
Figure 3.2-25	Traffic Situation of N1 in Chakaria Town	3-57
Figure 3.2-26	Proposal for Chakaria Flyover.....	3-60
Figure 3.3-1	Location of Installed Benchmarks	3-62
Figure 3.3-2	Photograph of the Installed Bench Marks	3-63
Figure 3.3-3	Location of River Cross Section Surveys	3-63
Figure 3.3-4	Location of Boring Investigations	3-64
Figure 3.3-5	High-Resolution Satellite Image (40cm Resolution).....	3-65
Figure 3.3-6	High-Definition Digital Terrain Model (0.5 m DTM).....	3-65
Figure 3.4-1	Typical Cross Sections of Matarbari Port Access Road (Embankment Sections)	3-68
Figure 3.4-2	Typical Cross Sections of Matarbari Port Access Road (Bridge Sections).....	3-69
Figure 3.4-3	Typical Cross Sections of Service Road.....	3-69
Figure 3.4-4	Alternative Alignments for Route Option B	3-70
Figure 3.4-5	Clearance for Railway	3-71
Figure 3.4-6	Designed Road Alignment (1/3)	3-73
Figure 3.4-7	Designed Road Alignment (2/3)	3-74
Figure 3.4-8	Designed Road Alignment (3/3)	3-74
Figure 3.4-9	Intersection with Matarbari Port North-South Connector Road.....	3-75
Figure 3.4-10	Intersection with CPGCBL's Power Plant Access Road.....	3-76
Figure 3.4-11	Intersection with R172.....	3-77
Figure 3.4-12	Intersection with N1	3-78
Figure 3.4-13	Resilient Modulus (M_R).....	3-83
Figure 3.4-14	Designed Pavement Layers.....	3-86
Figure 3.4-15	Road Lighting Poles	3-87

Figure 3.4-16 Classification of Inland Waterways	3-89
Figure 3.4-17 Design Truck Load	3-90
Figure 3.4-18 Bangladesh Seismic Zone Map	3-91
Figure 3.4-19 Normalized Design Acceleration Response Spectrum	3-94
Figure 3.4-20 Cofferdam of the Bored Pile Plan.....	3-100
Figure 3.4-21 PC-I Girder Bridge for Short-Span Bridges	3-101
Figure 3.4-22 Pier Arrangement of Steel Narrow Box Girder Bridges	3-103
Figure 3.4-23 Pier Span of Steel Narrow Box Girder Bridges	3-103
Figure 3.4-24 Cross Section of Steel Narrow Box Girder Bridges	3-104
Figure 3.4-25 Bending Moment and Shear Force Diagram of Main Girder	3-104
Figure 3.4-26 Steel Type and Maximum Thickness of Main Girder Flange.....	3-105
Figure 3.4-27 Cross Sectional Shape of Pier and Foundation.....	3-105
Figure 3.4-28 Pier and Foundation Shape of Steel Narrow Girder Brodge.....	3-106
Figure 3.4-29 Typical Cross Section of PC-I Girder Bridge	3-107
Figure 3.4-30 Pier Shape of PC-I Girder Bridge.....	3-108
Figure 3.4-31 Geological Features at Project Site.....	3-110
Figure 3.4-32 Soil Profile of the Matarbari Port Access Road.....	3-111
Figure 3.4-33 Calculation Flowchart.....	3-112
Figure 3.4-34 Preloading Method Conventional with/without PVD.....	3-115
Figure 3.4-35 Sand Compaction Pile Method	3-115
Figure 3.4-36 Flood Types in Bangladesh.....	3-118
Figure 3.4-37 Location of Observed Stations Selected for Data Collection	3-121
Figure 3.4-38 Monthly Mean Temperature (Daily Maximum and Minimum).....	3-123
Figure 3.4-39 Monthly Mean Relative Humidity.....	3-123
Figure 3.4-40 Monthly Mean Sunshine Hours	3-124
Figure 3.4-41 Monthly Mean Wind Speed.....	3-125
Figure 3.4-42 Monthly Mean Rainfall.....	3-127
Figure 3.4-43 Daily Rainfall at Cox’s Bazar Station (1987-2016).....	3-128
Figure 3.4-44 Annual Fluctuation of Rainfall	3-128
Figure 3.4-45 IDF (Intensity-Duration-Frequency) Curve.....	3-131
Figure 3.4-46 River Profile of Matamuhuri River.....	3-132
Figure 3.4-47 Daily Water Level at SW204 Station (Matamuhuri River–30.2km from Rivermouth)	3-133
Figure 3.4-48 Daily Water Level at SW203 Station (Matamuhuri River–58.3km from Rivermouth)	3-133
Figure 3.4-49 Daily Water Level at SW200 Station (Maheshkhali Channel)	3-133
Figure 3.4-50 Water-Level Duration Curve at SW204 (Matamuhuri River)	3-134
Figure 3.4-51 Water-Level Duration Curve at SW203 (Matamuhuri River)	3-134
Figure 3.4-52 Water-Level Duration Curve at SW200 (Maheshkhali Channel)	3-134
Figure 3.4-53 Tide Chart Diagram at Matarbari Port.....	3-138

Figure 3.4-54	Prediction of Astronomical Tide at Matarbari Port.....	3-139
Figure 3.4-55	Related Catchment Area	3-140
Figure 3.4-56	River Bed Fluctuations at Matamuhuri River.....	3-142
Figure 3.4-57	Distribution Map of Probable Flood Level (100-year Return Period, for Reference)	3-144
Figure 3.4-58	Interviewed Locations and Interviewed Historical High Water Levels.....	3-145
Figure 3.4-59	Classification of Inland Waterways	3-150
Figure 3.4-60	Contour Line and Elevation Points of River and Sea Area.....	3-153
Figure 3.4-61	Detailed Terrain Model (2m mesh DEM).....	3-153
Figure 3.4-62	Unstructured and Structured Meshes on Calculation.....	3-153
Figure 3.4-63	Hydraulic Profile on Proposed Road Alignment (100 / 50 year Storm Surge only)	3-155
Figure 3.4-64	Results of 2-dimensional Pre-Analyses	3-156
Figure 3.4-65	Calculated Water-Levels each Case of Roughness Coefficient at SW200 Station .	3-157
Figure 3.4-66	Grain Size Distribution Curve for the Riverbed Materials	3-157
Figure 3.4-67	Setting Area for Roughness Coefficient	3-158
Figure 3.4-68	Relationship between Moving Speed and Affected Time.....	3-159
Figure 3.4-69	Affected Time of Storm Surge (Case of Input Condition).....	3-159
Figure 3.4-70	Water Level Variation by Cyclone Cases (Calculation Case 4-3).....	3-159
Figure 3.4-71	DEM used for the Case “with Project Road Embankment”	3-160
Figure 3.4-72	Hydraulic Profile on the Road Alignment	3-161
Figure 3.4-73	2-dimensional Hydraulic Analyses (1)	3-162
Figure 3.4-74	2-dimensional Hydraulic Analyses (2)	3-163
Figure 3.4-75	Maximum Water Surface Elevation Distribution with / without Road Embankment (Case 4-3, 100-years Storm Surge + 20-years Flood).....	3-164
Figure 3.4-76	Discharge Variation of Proposed Bridge Opening Portion at Maheshkhali Channel (with Road Embankment)	3-165
Figure 3.4-77	Maximum Shear Stress Distribution (50-year Storm Surge + 20-year Flood)	3-166
Figure 3.4-78	Maximum Flow Velocity Distribution (50-year Storm Surge + 20-year Flood)	3-166
Figure 3.4-79	Hydraulic Profile and Cross-Section (1).....	3-168
Figure 3.4-80	Hydraulic Profile and Cross-Section (2).....	3-169
Figure 3.4-81	Simple Schematic Representation of Scour at a Cylindrical Pier.....	3-170
Figure 3.5-1	Temporary Construction Yard.....	3-178
Figure 3.5-2	Example of Construction Procedure for Road Works.....	3-181
Figure 3.5-3	Temporary Works.....	3-182
Figure 3.5-4	Cast-in-place Concrete Piles.....	3-183
Figure 3.5-5	Steel Pipe Sheet Pile	3-183
Figure 3.5-6	Substructure	3-184
Figure 3.5-7	Erection of Steel Box Girders.....	3-184
Figure 3.5-8	Erection of PC-I Girders.....	3-185

Figure 3.6-1 Project Scope	3-202
Figure 3.6-2 Typical Cross Section (Embankment Section)	3-204
Figure 3.6-3 Typical Cross Section (Bridge Section).....	3-205
Figure 3.6-4 Soft Soil Improvement Methods.....	3-207
Figure 3.6-5 Water Surface Elevations at Different Flooding Situations (m)	3-208
Figure 3.6-6 Construction Contract Packages	3-209
Figure 3.6-7 Mouza Map at Project Site	3-213
Figure 3.6-8 Revised Alignment of the Project Road.....	3-214
Figure 3.6-9 Photos of Design Controls	3-214
Figure 3.6-10 Design Control against CPGCBL’s Power Line	3-214
Figure 3.6-11 Long-Span Bridge.....	3-216
Figure 3.6-12 Long-Span Bridge.....	3-216
Figure 3.6-13 Comparison of Bridge Construction Costs over BIWTA’s Class II Waterway.....	3-217
Figure 3.6-14 Comparison of PC Box Girder Bridge and Steel Narrow Box Girder Bridge.....	3-218
Figure 3.6-15 Comparison of Construction Period	3-221
Figure 3.6-16 Example of Steel Bridges in Coastal Areas of Japan.....	3-222
Figure 3.6-17 Extent of Salt Damage in Japan.....	3-223
Figure 3.6-18 Road Structural Types.....	3-225
Figure 3.6-19 Cost Comparison of Road Structural Types (BDT billion/km)	3-226
Figure 3.6-20 Image of Land Reclamation in Matarbari and Maheshkhali	3-227
Figure 3.6-21 Current and Future Land Use at the Project Site	3-228
Figure 3.6-22 Estimated Construction Cost for Road Works (BDT million).....	3-229
Figure 3.6-23 Method for Establishment of Unit Prices	3-230
Figure 3.6-24 Estimated Cost for PC-I Girder Bridges per Sq. m.....	3-233
Figure 3.6-25 Estimated Cost for Steel Box Girder Bridges per Sq. m.....	3-233
Figure 3.6-26 Estimated Cost for Steel-I Girder Bridges per Sq. m.....	3-233
Figure 3.6-27 Estimated Construction Cost (BDT million)	3-234
Figure 3.6-28 Slope Gradient Options	3-235
Figure 3.6-29 Embankment Construction Concepts	3-237
Figure 3.6-30 Embankment Slope Options	3-239
Figure 3.6-31 Clearance for Railway	3-241
Figure 3.6-32 Comparison of Rail Crossing Types	3-241
Figure 3.6-33 Rail Crossing with the Proposed Rail Spur Line to Matarbari Port.....	3-242
Figure 3.6-34 Steps Involved in Approval Process of Investment Projects	3-243
Figure 3.6-35 Implementation Structure (RHD)	3-244
Figure 3.6-36 Organizational Structure of RHD	3-245
Figure 3.6-37 Organization Structure of MORTB.....	3-245
Figure 3.6-38 Classification of deterioration Mechanism	3-251
Figure 3.6-39 Major Repairing Measures	3-251
Figure 3.6-40 Road Condition of RHD Road Network.....	3-252

Figure 4.1-1 Project Location (port).....	4-2
Figure 4.1-2 Project Location (access road).....	4-3
Figure 4.1-3 Location of the Project and the Adjacent Project	4-4
Figure 4.2-1 Monthly maximum and minimum Temperatures (Source: BMD 2013).....	4-6
Figure 4.2-2 Trend of annual maximum and minimum Temperature (Source: BMD 2013).....	4-6
Figure 4.2-3 Average monthly maximum and minimum Rainfall (1977-2012).....	4-7
Figure 4.2-4 Trend of annual maximum and minimum Rainfall.....	4-7
Figure 4.2-5 Average of monthly maximum and minimum humidity (1985-2013).....	4-8
Figure 4.2-6 Land use patterns of the Moheshkhali Upazila.....	4-9
Figure 4.2-7 Comparative Position of ECA and WS.....	4-13
Figure 4.2-8 Map of Cox’s Bazar and Project Area	4-15
Figure 4.2-9 Unions in Moheshkhali and Chakaria Upazila, Project Affected Unions.....	4-16
Figure 4.3-1 Process image to acquire Environmental Clearance Certificate in Bangladesh	4-32
Figure 4.3-2 Organizational Setup of DOE.....	4-39
Figure 4.4-1 Plans of Four Options	4-43
Figure 4.4-2 The location for Dredge Soil Ocean Dumping (A common place for four Options)	4-44
Figure 4.4-3 Road Network in Bangladesh.....	4-49
Figure 4.5-1 Location of the Project and the Adjacent Project	4-63
Figure 4.8-1 sampling points of air quality survey.....	4-88
Figure 4.8-2 Sampling points of the sea water quality survey	4-90
Figure 4.8-3 Sampling point of the surface water quality survey	4-92
Figure 4.8-4 Sampling point of the ground water quality survey.....	4-96
Figure 4.8-5 Noise Level Monitoring of the Port Area	4-97
Figure 4.8-6 Location of Vibration Level Data	4-98
Figure 4.8-7 Sampling point of the sea bottom sediment survey	4-99
Figure 4.8-8 Water system around the planned site.....	4-101
Figure 4.8-9 Typology	4-103
Figure 4.8-10 Project Site and St. Martins Island.....	4-104
Figure 4.8-11 Map of Sonadia Ecollogically Critical Area(ECA)	4-106
Figure 4.8-12 Map of Fasiakhali Wildlife Sanctuary	4-107
Figure 4.8-13 Map of Medhakachapia National Park	4-108
Figure 4.8-14 Marine Organizm Sampling Points.....	4-110
Figure 4.8-15 Sampling points of fish and nekton	4-112
Figure 4.8-16 Salt Cultivation by using river water in the dry season in Moheshkhali	4-130
Figure 4.8-17 Location of the Project Site and Cultural Heritage.....	4-135
Figure 4.8-18 Adinath Temple in Moheshkhali.....	4-135
Figure 4.8-19 Temple of the Rakhain in Moheshkhali.....	4-135
Figure 4.8-20 sampling points of air quality survey.....	4-139
Figure 4.8-21 Sampling points of the surface water quality survey.....	4-140
Figure 4.8-22 Sampling points of the ground water quality survey	4-142

Figure 4.8-23 Noise Level Monitoring of the Access Road Project.....	4-144
Figure 4.8-24 Location of Vibration Level Data	4-146
Figure 4.8-25 Reserved area near the project site	4-147
Figure 4.8-26 Mangrove Forest in the Project Area	4-148
Figure 4.8-27 Study Area of Terrestrial Wildlife (Flora & Fauna).....	4-149
Figure 4.8-28 Plant Examples in the area.....	4-150
Figure 4.8-29 Tree Examples from the area	4-151
Figure 4.8-30 Bird Examples from the area	4-152
Figure 4.8-31 Comparison of Abundance of Phytoplankton (surface water).....	4-152
Figure 4.8-32 Comparison of Abundance of Zooplankton (surface water).....	4-154
Figure 4.8-33 Comparison of the Benthos abundance	4-154
Figure 4.8-34 Location of the Project Site and Fishing Ground	4-167
Figure 4.8-35 Shrimp Processing Company in Cox Bazar (Cox Bazar Seafood).....	4-170
Figure 4.8-36 Interview with the Company	4-170
Figure 4.8-37 Location Map of Both Projects.....	4-171
Figure 4.9-1 Implementation structure of Environmental Management and Monitoring Plan of the port during construction phase.....	4-172
Figure 4.9-2 Implementation structure of Environmental Management and Monitoring Plan of the port during operation phase	4-173
Figure 4.9-3 Environmental Management and Monitoring Implementation Structure of the access road during Operation phase	4-174
Figure 4.9-4 Environmental Management and Monitoring Implementation Structure in Operation phase for the access road.....	4-175
Figure 4.10-1 SHMs for Port.....	4-237
Figure 4.10-2 SHMs for Access Road.....	4-243
Figure 4.10-3 2nd SHMs for Port and its Access Road.....	4-252
Figure 4.10-4 Supplementary Community Consultation (Access Road)	4-255
Figure 4.11-1 Typical Cross-section of Embankment Section	4-257
Figure 4.11-2 Typical Cross-section of Bridge Section.....	4-258
Figure 4.11-3 Grievance Redress Mechanism.....	4-320
Figure 4.11-4 Institutional Arrangements.....	4-323
Figure 4.11-5 Land Acquisition Process in ARIPA2017	4-325
Figure 4.11-6 1st Public Consultation (for port)	4-341
Figure 4.11-7 Public Consultation for Access Road.....	4-347
Figure 4.11-8 2nd Public Consultations for Port and its Access Road.....	4-355
Figure 4.11-9 Supplemental Community Consultation (Access Road).....	4-358
Figure 4.11-10 Consultation Meeting for Compensation Policy.....	4-362
Figure 4.11-11 FGDs	4-363
Figure 4.11-12 Focus Group Discussion	4-366

List of Tables

Table 1.5-1 List of Hearing Survey regarding Environmental and Social Consideration	1-7
Table 2.1-1 Vessel deployment of the container services calling at Chittagong Port.....	2-3
Table 2.1-2 Deadweight and Number of Callings by Port / Ship Type (2016).....	2-4
Table 2.1-3 Coastal Shipping Fleet (as of April 2018).....	2-6
Table 2.1-4 Container Throughput of Pangaon ICT	2-6
Table 2.1-5 BCT Cargo Throughput and Berth Requirements (ADB Report).....	2-8
Table 2.1-6 BCT Container Throughput and Berth Requirements (CPA Plan).....	2-8
Table 2.1-7 BCT Berth Requirements for Multi-Purpose Terminal (CPA Plan)	2-9
Table 2.1-8: Cost Estimation for Payra Port and Industrial Area Development.....	2-12
Table 2.2-1 Results of MICS (Base Case).....	2-15
Table 2.2-2 Simulation Conditions for Base Case.....	2-15
Table 2.2-3 Simulation Conditions for Scenarios (for 2026)	2-16
Table 2.2-4 Results of MICS for Scenarios (for 2026).....	2-16
Table 2.2-5 Future Cargo Volume for Each Scenario.....	2-16
Table 2.3-1 Matarbari Ultra Super Critical Coal Fired Plant Working Schedule	2-23
Table 2.3-2 Marginal Laden TEUs Required for an Extra Calling by Size.....	2-27
Table 2.3-3 Laden Throughputs Assumed to Receive an Extra Calling by Size	2-27
Table 2.3-4 Concept and outline of Alternative Port Development Plans	2-30
Table 2.3-5 Phase 1 of the First Stage Matarbari Port Development	2-31
Table 2.3-6 Phase 2 of the First Stage Matarbari Port Development	2-32
Table 2.4-1 Joint probability of assumed extreme Water Level	2-35
Table 2.4-2 Objective Ships Dimensions	2-35
Table 2.4-3 Distribution of Clay layer.....	2-37
Table 2.4-4 Soil properties for group A,B and C.....	2-38
Table 2.4-5 Required Berth Dimension	2-49
Table 2.4-6 Comparison of Structural Type of Quay.....	2-52
Table 2.4-7 Comparison of Pile Type Quay	2-53
Table 2.4-8 Harbor Service Crafts.....	2-54
Table 2.4-9 Inspection Facilities of Customs and CPA.....	2-58
Table 2.4-10 Cargoes of Multi-Purpose Terminal	2-58
Table 2.4-11 Container handling volume in Matarbari Port (Demand Forecast) (1/2)	2-62
Table 2.4-12 Container handling volume in Matarbari Port (Demand Forecast) (2/2)	2-62
Table 2.4-13 Cargo handling volume in Matarbari Port (Demand Forecast).....	2-63
Table 2.4-14 Required functions of cargo handling equipment	2-64
Table 2.4-15 Proposed north and south side Dike structure and responsible organization	2-73
Table 2.4-16 Results of working rate of port unloading and loading operation.....	2-75

Table 2.4-17 Joint Frequency distribution of wave height and Wave direction in front of Matarbari Port entrance at MSL-15m (CDL-12.3m)	2-76
Table 2.4-18 Wave reduction ratio by Training Dike and Sand Protection Dike	2-76
Table 2.4-19 Maximum wave reduction ratio at berth location for extreme storm surge condition ..	2-79
Table 2.4-20 Maximum wave reduction ratio at berth location for extreme storm surge condition ..	2-81
Table 2.4-21 Considered offshore wave conditions for harbor oscillation analysis	2-82
Table 2.4-22 Components of VTMS at Chittagong Port	2-84
Table 2.4-23 List of Tugboats at Chittagong Port	2-89
Table 2.4-24 List of Pilot Boats.....	2-90
Table 2.4-25 List of Survey Boats.....	2-92
Table 2.4-26 List of Survey Equipment	2-93
Table 2.4-27 List of Security Boats.....	2-93
Table 2.4-28 List of Other Boats	2-94
Table 2.4-29 Main features of ISPS code	2-98
Table 2.5-1 Sub-Soil Conditions of Quay	2-101
Table 2.5-2 Joint Probabilities and Uplift Forces	2-104
Table 2.5-3 Berthing Energy	2-106
Table 2.5-4 Recommended Fenders and Rated Performance.....	2-106
Table 2.5-5 Mooring Bollards	2-107
Table 2.5-6 Legends of soil and strengths	2-110
Table 2.5-7 N vs Relative density of sand.....	2-111
Table 2.5-8 Consistency of clay vs N & qu.....	2-111
Table 2.5-9 Sand and sil/clay layers with N along berth.....	2-114
Table 2.5-10 Distribution of classified clay into three Groups.....	2-115
Table 2.5-11 Soil properties clay in the yard area	2-116
Table 2.5-12 Comparisons with Pz and Pc.....	2-118
Table 2.5-13 Computed final settlements at boring locations	2-119
Table 2.5-14 Countermeasure Technique against Liquefaction.....	2-122
Table 2.5-15 Estimated Fresh Water Demand.....	2-125
Table 2.5-16 Sewerage System Volume Estimation	2-126
Table 2.5-17 Power Demand Unit Load.....	2-126
Table 2.5-18 Power Load Estimation	2-127
Table 2.5-19 Terminal Building.....	2-129
Table 2.5-20 Administration Office Building.....	2-130
Table 2.5-21 Major Port Terminal Facilities and relevant Quantities.....	2-131
Table 2.5-22 Breakdown of cargo handling equipment at the time of opening Matarbari port	2-133
Table 2.5-23 Cargo handling equipment and other related equipment.....	2-134
Table 2.5-24 Equipment of cargo handling equipment corresponding to handled quantity	2-135
Table 2.5-25 Main specifications of Quayside Container Crane (QC)C.....	2-136
Table 2.5-26 Main specifications of Multi-purpose Gantry Crane (MGC).....	2-138

Table 2.5-27 Main specifications of Rubber Tyred Gantry Crane (RTG)	2-139
Table 2.5-28: Typical Side Slopes for Various Soil for Underwater Slopes.....	2-142
Table 2.5-29: Results of Slope Stability Analysis along the Channel and Basin.....	2-143
Table 2.5-30 Storm Surge Height at Southern Side of Matarbari Area	2-144
Table 2.5-31: Offshore Significant Design Waves with Return Period of 50 Years	2-145
Table 2.5-32 Tide conditions for the structural design of breakwater.....	2-145
Table 2.5-33 Design wave height at the breakwater.....	2-146
Table 2.5-34 Design soil parameters	2-151
Table 2.5-35 Quantities of volume of the structures	2-153
Table 2.5-36 Preliminary Specification of VTMS at Matarbari Port	2-154
Table 2.5-37 Preliminary Specification of Pillar-type Lighted Buoys	2-157
Table 2.5-38 Preliminary Specification of Leading Lights	2-159
Table 2.5-39 Preliminary Specification of Beacon.....	2-160
Table 2.5-40 Wind Resistance and Necessary Power of Tugboat	2-161
Table 2.5-41 Preliminary Specification of Tugboat at Matarbari Port	2-163
Table 2.5-42 Preliminary Specification of Pilot Boat at Matarbari Port	2-164
Table 2.5-43 Preliminary Specification of Survey Boat at Matarbari Port.....	2-166
Table 2.5-44 Preliminary Specification of CCTV at Matarbari Port.....	2-167
Table 2.5-45 Preliminary Specification of Gate Control System at Matarbari Port.....	2-168
Table 2.6-1 Summary of Terminal Buildings and Utilities.....	2-172
Table 2.6-2 Work Schedule of Cargo Handling Equipment	2-180
Table 2.7-1 Availability of Materials.....	2-183
Table 2.7-2 Availability of Construction Equipment.....	2-184
Table 2.7-3 Preliminary Cost.....	2-187
Table 2.7-4 Preliminary Cost of Equipment.....	2-188
Table 2.7-5 Allocation Plan of Initial Investment for Training Dike and Breakwater (Draft)	2-190
Table 2.7-6 Dredging Volume and Project Allocation (Draft)	2-192
Table 2.7-7 Trial Calculations of Maintenance Dredging Cost	2-193
Table 2.7-8 Safety Risk Analysis Table (Sample)	2-198
Table 2.7-9 Activity of Safety Management System.....	2-199
Table 2.7-10 Important Facilities for which special attention is required	2-199
Table 2.7-11 Safety Facilities	2-200
Table 2.8-1 Combination of the countermeasure structure.....	2-212
Table 2.8-2 Calculated amount of sedimentation	2-217
Table 2.8-3 Predicted results of channel and basin sedimentation for different length of northern Training Dike of port of MUSCCPP	2-217
Table 2.8-4 Predicted results of channel and basin sedimentation for New Port	2-218
Table 2.8-5 Calculated amount of sedimentation volume	2-221
Table 2.8-5 Planned dredged method and expected maximum daily dredging volume	2-224
Table 2.8-6 Study cases for the SS diffusion prediction.....	2-224

Table 2.8-7 Representative Soil Particle Size and Settling Velocity of Considered Material for Turbidity Diffusion.....	2-225
Table 2.8-8 Employed Basic Unit of Turbidity Source.....	2-226
Table 2.8-9 Employed amount of SS loading at the source.....	2-228
Table 2.8-10 Employed amount of SS loading at the source with and without contamination prevention membrane.....	2-229
Table 2.8-11 Turbidity source conditions and its model for dredging and dumping works.....	2-230
Table 2.8-12 Tidal Amplitude and Phases to determine the Boundary Conditions.....	2-233
Table 2.8-13 Average uniform wind conditions over the sea.....	2-234
Table 2.8-14 Collected Satellite Image data.....	2-249
Table 2.8-15 Energy average wave with wave direction SSW (Dry Season).....	2-266
Table 2.8-16 Energy average wave with wave direction SW (Dry Season).....	2-266
Table 2.8-17 Energy average wave with wave direction SSW (Rainy Season).....	2-266
Table 2.8-18 Energy average wave with wave direction SW (Rainy Season).....	2-266
Table 2.8-19 Parametric validity analysis by changing the empirical constants of K1 and K2.....	2-270
Table 2.9-1 Budget of CPA.....	2-278
Table 2.9-2 Members of the Interim PIU and their Responsibilities.....	2-279
Table 2.9-3 Current Role Allotment between CPA and Private at Chittagong Port.....	2-281
Table 2.9-4 Proposal on Technical Training for CPA Staff.....	2-282
Table 2.10-1 Safety Facilities.....	2-289
Table 3.1-1 Total Road Network in Bangladesh.....	3-1
Table 3.1-2 Growth in RHD Road Network.....	3-3
Table 3.1-3 Road Widths of Other Roads in the Region.....	3-4
Table 3.1-4 Challenges for Improving International Economic Corridors.....	3-5
Table 3.1-5 Strategic Policy for National Land Transport.....	3-9
Table 3.1-6 Road Sector Policy.....	3-12
Table 3.1-7 Master Plan Priority Projects.....	3-14
Table 3.1-8 Types of Encroachments and Possible Solutions.....	3-15
Table 3.2-1 Comparison of Route Options.....	3-24
Table 3.2-2 Vehicle Classification for Traffic Survey.....	3-26
Table 3.2-3 PCU Conversion Factors.....	3-27
Table 3.2-4 24-Hour Traffic Count Data at Intersection A1.....	3-30
Table 3.2-5 24-Hour Traffic Count Data at Intersection A2.....	3-30
Table 3.2-6 24-Hour Traffic Count Data at Intersection A3.....	3-30
Table 3.2-7 Zone Coding for OD Survey.....	3-32
Table 3.2-8 Traffic Count Data on National Highway 1 (Near Chakaria).....	3-33
Table 3.2-9 Traffic Count Data on National Highway 1.....	3-33
Table 3.2-10 Real GDP (Base year: 2005).....	3-37
Table 3.2-11 Cumulative Registered Number of Vehicles in Bangladesh from 2011 to 2015.....	3-38
Table 3.2-12 Parameters of the Vehicle Registration Number Forecasting Model.....	3-39

Table 3.2-13 Forecast of Future Vehicle Registration (in thousands)	3-39
Table 3.2-14 Yearly Growth Rate of Registered Vehicles	3-39
Table 3.2-15 Estimated Number of Container Cargo of Matarbari Port (Thousand TEU)	3-40
Table 3.2-16 Total Traffic Volume related with Cargo Container	3-41
Table 3.2-17 Estimation of Multipurpose Berth (Thousand Tons).....	3-41
Table 3.2-18 Traffic Volume of Multipurpose Berth	3-42
Table 3.2-19 Total Induced Traffic from the Port.....	3-43
Table 3.2-20 Future Peak Hour Traffic Flow from the Port	3-43
Table 3.2-21 Estimated Diverted Traffic from the Existing Road to the New Access Road.....	3-44
Table 3.2-22 Future Development Activities in Matarbari Region	3-44
Table 3.2-23 Number of Working Days in Power Plant.....	3-45
Table 3.2-24 Possible Number of Staff in Power Plant & Others	3-45
Table 3.2-25 Number of Daily Commuting Trips to Power Plant & Others	3-46
Table 3.2-26 Number of Business Trips to the Power Plant & Others	3-46
Table 3.2-27 Number of Daily Vehicular Trips to Power Plant & Others	3-46
Table 3.2-28 Potential Container Truck Trips from Economic Zones.....	3-47
Table 3.2-29 Estimated Daily Traffic for the Access Road	3-48
Table 3.2-30 Forecast of Daily Traffic Flow on N1 (Chakaria Area).....	3-49
Table 3.2-31 Forecast of Daily Induced Traffic from the Access Road	3-49
Table 3.2-32 Estimated Combined Daily Traffic Flow on N1 (Chakaria Area).....	3-49
Table 3.2-33 Future Traffic Forecast on R172	3-50
Table 3.2-34 Estimated Peak Hour Traffic (PCU/hour) at Intersection with SMV	3-51
Table 3.2-35 Estimated Peak Hour Traffic (PCU/hour) at Intersection without SMV.....	3-51
Table 3.2-36 Alternative Options for Improvement of N1	3-54
Table 3.2-37 Calculated Average Travel Time between Chittagong and Chakaria during Peak Period	3-54
Table 3.2-38 Rough Cost Estimates for Improvements (Case 2)	3-56
Table 3.2-39 Rough Cost Estimates for Improvements (Case 3)	3-56
Table 3.2-40 Rough Cost Estimates for Improvements (Case 4)	3-56
Table 3.2-41 Rough Benefit Estimates for Different Cases compared to Case 1 (Do Nothing)	3-56
Table 3.2-42 Effectiveness of Improvements	3-56
Table 3.2-43 Comparison of Improvement Method for N1 at Chakaria	3-58
Table 3.2-44 Comparison of Bridge Type for Chakaria Flyover	3-59
Table 3.3-1 RTK-GNSS Static Observation Points of Survey of Bangladesh (SoB).....	3-61
Table 3.3-2 RTK-GNSS Static Observation Results of CP & TP Pillar	3-62
Table 3.3-3 Check Result of Accuracy of DTM.....	3-66
Table 3.4-1 Geometric Design Conditions	3-67
Table 3.4-2 Comparison of Alternative Alignments for Route Option B.....	3-72
Table 3.4-3 Minimum Length at Intersection Area	3-76
Table 3.4-4 Minimum Length of Interchange Ramp Terminal (60 km/h).....	3-77

Table 3.4-5	Comparison of Traffic Saturation Rate at N1 Intersection.....	3-78
Table 3.4-6	Minimum Length at Intersection Area	3-78
Table 3.4-7	Comparison of Pavement Types.....	3-79
Table 3.4-8	Pavement Design Conditions	3-81
Table 3.4-9	Future Traffic Demand and ESAL 18-kip (Port Access Road).....	3-82
Table 3.4-10	Future Traffic Demand and ESAL 18-kip (N1).....	3-82
Table 3.4-11	Future Traffic Demand and ESAL 18-kip (Other Intersecting Roads).....	3-82
Table 3.4-12	Calculated Design ESAL (W_{18}).....	3-83
Table 3.4-13	Calculated Thickness of Surface Layer.....	3-84
Table 3.4-14	Calculated Thickness of Asphalt Treated Base Course Layer.....	3-84
Table 3.4-15	Calculated Thickness of Crushed Aggregate Base Course Layer	3-85
Table 3.4-16	Calculated Thickness of Granular Aggregate Subbase Course Layer.....	3-85
Table 3.4-17	Calculated Thickness of Pavement Layers for Access Road.....	3-86
Table 3.4-18	Calculated Thickness of Pavement Layers for N1	3-86
Table 3.4-19	Calculated Thickness of Pavement Layers for Other Intersecting Roads	3-86
Table 3.4-20	Navigation Waterways Limitation.....	3-88
Table 3.4-21	Unit Weight of Bridge Materials for Dead Load Calculation.....	3-90
Table 3.4-22	Lane Load Specifications for Girder and Substructure Design.....	3-90
Table 3.4-23	Site Class for Soil Profile	3-92
Table 3.4-24	Site Dependent Soil Factor and Other Parameters	3-93
Table 3.4-25	Response Modifications Factor R (AASHTO LRFD)	3-94
Table 3.4-26	Strength Requirements of Concrete for Bridges	3-95
Table 3.4-27	Nominal Stress of Reinforcing Steel Bars for Bridges.....	3-95
Table 3.4-28	Nominal Stress of Pre-stressing Steel.....	3-95
Table 3.4-29	Nominal Stress of Steel	3-95
Table 3.4-30	Applicable Bridge Span for Bridge Types (Experience in Japan).....	3-97
Table 3.4-31	Comparison of Bridge Type for BIWTA's Class II Waterway	3-98
Table 3.4-32	Comparison of Foundation Type for Long-Span Bridges	3-99
Table 3.4-33	List of Bridge	3-102
Table 3.4-34	Approximate Quantity of Steel Narrow Girder Bridge	3-105
Table 3.4-35	Approximate Quantity of Steel Narrow Girder Bridge	3-108
Table 3.4-36	Number of Piles of PC-I Girder Bridge.....	3-109
Table 3.4-37	Design Criteria for Soft Soil Improvement	3-112
Table 3.4-38	Project Section	3-113
Table 3.4-39	Comparison of Soft Soil Improvement method	3-113
Table 3.4-40	Comparison of Construction Time and Cost.....	3-114
Table 3.4-41	Recommended Filling Rate.....	3-114
Table 3.4-42	Summary of Soft Soil Improvement method	3-116
Table 3.4-43	Freeboard Allowances for Bridge.....	3-119
Table 3.4-44	Collected Data and Surveyed Items	3-122

Table 3.4-45	Past Maximum Wind Speed at Surrounding Stations.....	3-125
Table 3.4-46	List of Major Cyclonic Storms from 1960 to 2017	3-126
Table 3.4-47	Monthly Mean Rainfall	3-127
Table 3.4-48	Annual Mean Rainy Days (more than 10 mm/day).....	3-129
Table 3.4-49	Probable 24-hour Rainfall at 4 Stations.....	3-130
Table 3.4-50	Rainfall Intensity for each Duration at Cox's Bazar	3-131
Table 3.4-51	Typical Water Level of SW204 (Matamuhuri River, m PWD)	3-135
Table 3.4-52	Typical Water Level of SW203 (Matamuhuri River, m PWD)	3-136
Table 3.4-53	Typical Water Level of SW200 (Maheshkhali Channel).....	3-137
Table 3.4-54	Tidal Harmonic Constants at Matarbari Port.....	3-138
Table 3.4-55	Probable Storm Surge Height at Matarbari Port.....	3-139
Table 3.4-56	Estimation of Height of Land Development at Matarbari Port	3-139
Table 3.4-57	Related Catchment Area.....	3-141
Table 3.4-58	Probable Flood Discharge at SW 203	3-143
Table 3.4-59	Probable Flood Levels at 9 Stations	3-144
Table 3.4-60	Design Water Levels	3-145
Table 3.4-61	Interview Survey Results (1/4).....	3-146
Table 3.4-62	Interview Survey Results (2/4).....	3-147
Table 3.4-63	Interview Survey Results (3/4).....	3-148
Table 3.4-64	Interview Survey Results (4/4).....	3-149
Table 3.4-65	Fairway Limitation in Bangladesh	3-150
Table 3.4-66	Topographic Data used for Hydraulic Analyses.....	3-151
Table 3.4-67	Calculation Cases	3-154
Table 3.4-68	Permissible Shear Stress of Fill Material (N/m ²)	3-166
Table 3.4-69	Locations Requiring Slope Protection (Shear Stress > 30 N/m ²).....	3-167
Table 3.4-70	Locations Requiring Slope Protection (Velocity > 1.8m/s).....	3-167
Table 3.4-71	Dimension-based Comparison of Hydraulic Models for Scour Estimation.....	3-171
Table 3.4-72	Estimated Scour Depth at Kohelia River (No.1+423).....	3-171
Table 3.4-73	Estimated Scour Depth at Maheshkhali Channel Bridge (No.11+227).....	3-172
Table 3.4-74	Estimated Scour Depth at old Matamuhuri River Tributary Bridge (No.14+270)...	3-172
Table 3.4-75	Estimated Scour Depth at old Matamuhuri River Bridge (No.16+625).....	3-173
Table 3.4-76	Estimated Scour Depth at Matamuhuri River Bridge (No.18+730).....	3-173
Table 3.4-77	Estimated Scour Depth at Fasiakhali Khal Bridge (No.22+760)	3-173
Table 3.4-78	Estimated Scour Depth at Fasiakhali Khal Bridge (No.23+470)	3-173
Table 3.4-79	Estimated Scour Depth at Mangla River Bridge (No.24+475)).....	3-173
Table 3.5-1	Material Procurement.....	3-177
Table 3.5-2	Required Area for Temporary Construction Yard (ha)	3-178
Table 3.5-3	Operation Rate	3-185
Table 3.5-4	Road Works	3-186
Table 3.5-5	Sub structure Works (Cast-in-place Concrete Piles)	3-186

Table 3.5-6 Sub structure works (Steel pipe sheet piles).....	3-187
Table 3.5-7 Super structure works (PC-I girders)	3-187
Table 3.5-8 Super structure works (Steel-I girders)	3-187
Table 3.5-9 Super structure works (Steel narrow box girders).....	3-188
Table 3.5-10 Construction Schedule for Road Works	3-189
Table 3.5-11 Construction Schedule for Bridge Works	3-190
Table 3.5-12 Estimated Construction Cost.....	3-192
Table 3.5-13 Estimated Construction Cost for Embankment Sections per km	3-192
Table 3.5-14 Estimated Construction Cost for Bridge Sections per sq.m	3-192
Table 3.5-15 Total Estimated Construction Cost.....	3-193
Table 3.5-16 Construction Cost of Matarbari Port Access Road.....	3-194
Table 3.5-17 Construction Cost of Matarbari Port North-South Connector Road	3-195
Table 3.5-18 Construction Cost of Service Road	3-195
Table 3.5-19 Construction Cost of National Highway No.1	3-196
Table 3.5-20 Construction Cost of Other Intersecting Roads.....	3-196
Table 3.5-21 Construction Cost of Bridges No. 1-4.....	3-197
Table 3.5-22 Construction Cost of Bridges No. 5-8.....	3-198
Table 3.5-23 Construction Cost of Bridges No. 9-12.....	3-199
Table 3.5-24 Construction Cost of Bridges No. 13-17	3-200
Table 3.6-1 List of Intersecting Roads/Railways.....	3-203
Table 3.6-2 List of Bridges.....	3-203
Table 3.6-3 Construction Cost of Each Package	3-210
Table 3.6-4 RHD's Observations/ Comments on the Draft Final Report.....	3-211
Table 3.6-5 Request from Local Stakeholders.....	3-212
Table 3.6-6 Designed Bridge Types	3-215
Table 3.6-7 Applicable Bridge Span for Bridge Types.....	3-215
Table 3.6-8 Comparison of Bridge Construction Costs over BIWTA's Class II Waterway	3-219
Table 3.6-9 Comparison of Bridge Construction Period over BIWTA's Class II Waterway.....	3-220
Table 3.6-10 Possible Bridges to be Steel I Girder Type.....	3-221
Table 3.6-11 Minimum Required Cover Thickness against Salt Damage (mm).....	3-223
Table 3.6-12 Typical Protection Measures against Rusting/ Corrosion	3-224
Table 3.6-13 Comparison of Road Structural Types.....	3-226
Table 3.6-14 Possible Section for Viaduct.....	3-228
Table 3.6-15 Estimated Construction Cost per km (Phase 1).....	3-229
Table 3.6-16 Comparison of Unit Rates.....	3-231
Table 3.6-17 Review of Estimated Construction Cost for Bridges	3-232
Table 3.6-18 Review of Estimated Construction Cost (BDT million)	3-234
Table 3.6-19 Comparison of Slope Gradient.....	3-236
Table 3.6-20 Embankment Construction Concepts	3-238
Table 3.6-21 Comparison of Embankment Slope.....	3-240

Table 3.6-22	Necessary Input for Consultancy Services.....	3-246
Table 3.6-23	Cost Breakdown for the Consulting Services.....	3-248
Table 3.6-24	Overall Maintenance Needs for RHD Road Network.....	3-252
Table 3.6-25	Estimated Maintenance Cost for the Project Road (30 Years)	3-253
Table 4.1-1	Outline of Port Facilities	4-1
Table 4.1-2	Outline of access road	4-3
Table 4.2-1	Administered Agency and Law of ECA.....	4-10
Table 4.2-2	Rare Species found in Sonadia ECA.....	4-12
Table 4.2-3	Project Affected Unions and Mouzas.....	4-14
Table 4.2-4	Demographic Data of the Project Area (in 2011).....	4-17
Table 4.2-5	Religious Belief of the Project Area (in 2011)	4-18
Table 4.2-6	Ethnic Minorities of the Project Area (in 2011).....	4-19
Table 4.2-7	Distribution of Population aged 7 years and above by Literacy, Sex (in 2011)	4-20
Table 4.2-8	Distribution of Population aged 3-14 years by Age groups, School attendance	4-20
Table 4.2-9	Industry of the Project Area (in 2011).....	4-21
Table 4.2-10	Average Monthly Income of the household Income (in 2017).....	4-21
Table 4.2-11	Households below Poverty Line (in 2010).....	4-21
Table 4.2-12	Percentage Distribution of Households by Type of Structure and Housing Tenancy Status (in 2011).....	4-22
Table 4.2-13	Percentage Distribution of Households by Toilet Facility, Source of Drinking Water and Electricity Connection (in 2011)	4-23
Table 4.3-1	Project Relevant International Treaties and Conventions	4-31
Table 4.3-2	Gaps between Relevant Regulations in Bangladesh and JICA Guidelines considering Environmental Assessment (EA).....	4-33
Table 4.4-1	Outline of Four Options	4-42
Table 4.4-2	Analysis of Options.....	4-45
Table 4.4-3	Overview of Alternatives (Step 1).....	4-50
Table 4.4-4	Comparison of Alternatives and the Evaluation (Step 1)	4-52
Table 4.4-5	Overview of Alternatives (Step 2).....	4-55
Table 4.4-6	Comparison of Alternatives and the Evaluation (Step 2)	4-58
Table 4.6-1	Scoping Matrix (port).....	4-64
Table 4.6-2	Scoping Matrix (Access Road)	4-68
Table 4.6-3	Survey TOR (port)	4-72
Table 4.6-4	Survey TOR (access road).....	4-75
Table 4.7-1	Result of Impact Assessment (Port)	4-77
Table 4.7-2	Result of Impact Assessment (Access Road)	4-82
Table 4.8-1	Results of air quality survey.....	4-88
Table 4.8-2	Estimated CO2 emissions of the proposed port project	4-89
Table 4.8-3	Results of the seawater.....	4-91
Table 4.8-4	Results of the surface water quality survey.....	4-93

Table 4.8-5 Soil properties for group A,B and C.....	4-94
Table 4.8-6 Representative Soil Particle Size and Settling Velocity of Considered Material for Turbidity Diffusion	4-95
Table 4.8-7 Results of the ground water quality survey	4-96
Table 4.8-8 Noise Level data of the Study Area.....	4-97
Table 4.8-9 Description of Analysis:	4-98
Table 4.8-10 Results of Sea bottom Sediment Survey (Heavy Metals) of the project study area	4-100
Table 4.8-11 Protected and Significant Areas Located within the Study Area	4-104
Table 4.8-12 Inventory of Fish Species in different zones of the study area.....	4-113
Table 4.8-13 Fish Species Survey in Dhalghata (Gona) & Badarkhali Gona)	4-114
Table 4.8-14 List of Crab in the Study Area.....	4-115
Table 4.8-15 List of Shell in the Study Area	4-115
Table 4.8-16 List of Terrestrial Organisms.....	4-116
Table 4.8-17 List of Insects	4-119
Table 4.8-18 List of reptiles	4-121
Table 4.8-19 List of Birds.....	4-123
Table 4.8-20 Summary of Resettlement and Land Acquisition.....	4-129
Table 4.8-21 Average Household Income and the Volume of Fish Catches of Fisherman.....	4-131
Table 4.8-22 Employment of the Project Affected Persons.....	4-132
Table 4.8-23 Household Income for Each Occupation (Tk per month)	4-132
Table 4.8-24 Social Infrastructures which can be Affected by the Project.....	4-133
Table 4.8-25 Concened Households of Dhalghata public Graveyard.....	4-133
Table 4.8-26 Gender-wise Education Level of the Project Affected Persons.....	4-136
Table 4.8-27 Gender-wise Occupation of the Project Affected Persons.....	4-137
Table 4.8-28 The Percentage and Number of Child Labor (2013).....	4-138
Table 4.8-29 Vaccination Rate by Age of 23 Months.....	4-138
Table 4.8-30 Results of air quality survey.....	4-140
Table 4.8-31 Results of the surface water quality survey.....	4-141
Table 4.8-32 Results of the ground water quality survey	4-143
Table 4.8-33 Noise Level data of the Study Area.....	4-145
Table 4.8-34 Description of Analysis:	4-146
Table 4.8-35 Summary of Resettlement and Land Acquisition.....	4-155
Table 4.8-36 Employment of the Project Affected Persons.....	4-157
Table 4.8-37 Household Income for Each Occupation (Tk per month)	4-157
Table 4.8-38 Social infrastructures near the Project Site.....	4-158
Table 4.8-39 Gender-wise Education Level of the Project Affected Persons.....	4-160
Table 4.8-40 The Percentage and Number of Child Labor (2013).....	4-161
Table 4.8-41 Vaccination Rate by Age of 23 Months.....	4-161
Table 4.8-42 Results of Interviews.....	4-164
Table 4.8-43 Comparison of income and catch before and after Construction of the Adjacent Project	

(Survey in 2018).....	4-167
Table 4.8-44 Project Affected Union and Salt and Shrimp Farm in the Project Area	4-169
Table 4.9-1 Environmental Management Plan (Port).....	4-176
Table 4.9-2 Environmental Management Plan (Access Road).....	4-190
Table 4.9-3 Environmental Monitoring Plan of the Project (Port).....	4-204
Table 4.9-4 Environmental Monitoring Plan of the Project (Road)	4-221
Table 4.10-1 Schedule of Stakeholder Meetings.....	4-232
Table 4.10-2 List of Stakeholders.....	4-232
Table 4.10-3 Participants of SHM.....	4-234
Table 4.10-4 Remarkable comments, questions and their responses.....	4-236
Table 4.10-5 Participants of SHMs	4-238
Table 4.10-6 Remarkable comments, questions and their responses.....	4-239
Table 4.10-7 Participants of SHMs	4-244
Table 4.10-8 Remarkable comments, questions and their responses.....	4-244
Table 4.10-9 Participants of SHMs	4-253
Table 4.10-10 Remarkable Comments, Suggestions and Correspondences.....	4-253
Table 4.11-1 Project Components Incurring Land Acquisition and Resettlement.....	4-256
Table 4.11-2 Gaps between Law in Bangladesh and JICA Guidelines regarding Involuntary Resettlement	4-262
Table 4.11-3 Scale and Scope of Land Acquisition and Resettlement by the Project	4-268
Table 4.11-4 Summary of the Survey.....	4-270
Table 4.11-5 Type of House Structure and Value of the Affected Structure	4-271
Table 4.11-6 Ownership of Residential Structures	4-271
Table 4.11-7 Ownership of Commercial Structures	4-271
Table 4.11-8 Land System.....	4-272
Table 4.11-9 Size wise Affected Land in the Area	4-272
Table 4.11-10 Loss of Trees	4-272
Table 4.11-11 PAH's Location Wise Affected Trees	4-273
Table 4.11-12 Union/Mouza-wise HHs subject to the Survey	4-273
Table 4.11-13 Age Distribution of Household Member	4-273
Table 4.11-14 Educational Level of the Project Affected Persons	4-274
Table 4.11-15 Gender-wise Education Level of the Project Affected Persons.....	4-274
Table 4.11-16 Number of Employed Members in PAHs.....	4-275
Table 4.11-17 Union-wise Occupation Pattern of the PAPs.....	4-276
Table 4.11-18 Gender-wise Occupation Pattern of PAPs	4-277
Table 4.11-19 PAHs under Shrimp Cultivation	4-277
Table 4.11-20 Union-wise Monthly Household Income	4-278
Table 4.11-21 Access to Electricity	4-278
Table 4.11-22 Types of Toilet.....	4-278
Table 4.11-23 Vulnerability.....	4-279

Table 4.11-24 Occupation Pattern of Non Titled PAHs.....	4-279
Table 4.11-25 Income Range of Non-titled Sharecropper and Employee PAHs.....	4-280
Table 4.11-26 Education Level of Non-titled Sharecropper and Employee PAHs.....	4-280
Table 4.11-27 Summary of the Survey.....	4-281
Table 4.11-28 Classification of Residential and Commercial Structures	4-282
Table 4.11-29 Ownership of Residential Structures	4-282
Table 4.11-30 Ownership of commercial Structures	4-283
Table 4.11-31 Other Affected Structures	4-283
Table 4.11-32 Land System.....	4-283
Table 4.11-33 Affected Trees by Category.....	4-284
Table 4.11-34 Affected Trees by Households.....	4-286
Table 4.11-35 Union/Mouza-wise HHs subject to the Survey	4-298
Table 4.11-36 Distribution of Household Members by Age.....	4-298
Table 4.11-37 Education Level of the Project Affected Persons	4-299
Table 4.11-38 Gender-wise Education Level of the Project Affected Persons.....	4-299
Table 4.11-39 Number of Employed Members in PAHs.....	4-300
Table 4.11-40 Union-wise Occupation Pattern of the PAPs.....	4-301
Table 4.11-41 Union-wise monthly household income.....	4-302
Table 4.11-42 Access to Electricity	4-302
Table 4.11-43 Types of Toilet.....	4-303
Table 4.11-44 Vulnerability.....	4-303
Table 4.11-45 Occupation Pattern of Non Titled Share croppers and Employees.....	4-304
Table 4.11-46 Income Range of Non-titled Sharecroppers and Employees.....	4-304
Table 4.11-47 Education Level of Non-titled Share cropper and Employee PAHs.....	4-304
Table 4.11-48 Outline of the interview on Income Restoration Program.....	4-306
Table 4.11-49 Livelihood Restoration Priorities	4-307
Table 4.11-50 Vulnerables Eligible for Livelihood Restoration Assistance	4-308
Table 4.11-51 Livelihood Restoration Priorities	4-309
Table 4.11-52 Preference for Compensation Policy (Port).....	4-312
Table 4.11-53 Plan Examined for Providing Alternative Land	4-313
Table 4.11-54 Preference for Compensation Policy (Access Road).....	4-314
Table 4.11-55 Entitlement Matrix	4-315
Table 4.11-56 Resettlement Schedule	4-327
Table 4.11-57 Type of House and Commercial Structure.....	4-328
Table 4.11-58 Land Price by Category.....	4-329
Table 4.11-59 Tree Loss in the Affected Area	4-329
Table 4.11-60 R&R Budget (port).....	4-330
Table 4.11-61 Replacement Cost of Structures	4-331
Table 4.11-62 Other Affected Structures and their Squire Meters.....	4-332
Table 4.11-63 Replacement Cost Survey of Land	4-332

Table 4.11-64 Summary of Tree Loss by Category	4-333
Table 4.11-65 R&R Budget.....	4-335
Table 4.11-66 Schedule of Public Consultations.....	4-338
Table 4.11-67 Participants of Public Consultations.....	4-339
Table 4.11-68 Remarkable Comments, Suggestions and Correspondences	4-340
Table 4.11-69 Participants of Public Consultations.....	4-342
Table 4.11-70 Remarkable Comments, Suggestions and Correspondences	4-343
Table 4.11-71 Participants of Public Consultations.....	4-348
Table 4.11-72 Remarkable Comments, Suggestions and Correspondences	4-349
Table 4.11-73 Participants of Public Consultations.....	4-356
Table 4.11-74 Remarkable Comments, Suggestions and Correspondences	4-356
Table 4.11-75 Participants of Public Consultations.....	4-359
Table 4.11-76 Remarkable comments, questions and their responses.....	4-359
Table 4.11-77 Participants of Public Consultations.....	4-360
Table 4.11-78 Remarkable comments, questions and their responses.....	4-360
Table 4.11-79 Outline of FGDs (Port)	4-363
Table 4.11-80 Outline of FGDs (Access Road)	4-364
Table 5.1-1 Profit and Loss of CPA (2012/13 - 2016/17).....	5-1
Table 5.1-2 Balance Sheet of CPA (2011/12 - 2015/16).....	5-2
Table 5.1-3 Financial Performance Indicators.....	5-3
Table 5.1-4 Contents of Profit Loss Statement in the Simulation Model.....	5-4
Table 5.1-5 Contents of Cash Flow Statement	5-5
Table 5.1-6 Contents of Balance Sheet.....	5-5
Table 5.1-7 Revenues from container cargo handling and storage per a model ship	5-6
Table 5.1-8 Revenue from Ship Entry.....	5-7
Table 5.1-9 Operating Cost.....	5-8
Table 5.1-10 Port Construction Cost	5-9
Table 5.1-11 Comparison of Port Dues and Charges.....	5-10
Table 5.1-12 FIRR of the Port Project.....	5-12
Table 5.1-13 FIRR of Basic Cases (Phase 1)	5-13
Table 5.1-14 FIRR of Additional Case 1 (Private Terminals and Phase 1)	5-13
Table 5.1-15 FIRR of Additional Case 2 (Phase 1 and 2 and Private Terminals)	5-14
Table 5.1-16 Financial Simulation (Profit and Loss)	5-15
Table 5.1-17 Financial Simulation (Cash Flow and Balance Sheet)	5-17
Table 5.2-1 Trade Statistics of Bangladesh and Standard Conversion Factor (SCF)	5-22
Table 5.2-2 Maritime Transportation Cost Savings per Box (Container).....	5-22
Table 5.2-3 Maritime Transportation Cost Savings (General/Bulk Cargo).....	5-23
Table 5.2-4 Estimation of Traffic to/from Matarbari Port.....	5-24
Table 5.2-5 Travel Time Cost and Running Cost	5-25
Table 5.2-6 Estimated Cost for the Access Road (Two Lanes)	5-26

Table 5.2-7	Cost and Benefits of the Port Project	5-27
Table 5.2-8	Cost and Benefits of the Road Project.....	5-28
Table 5.2-9	EIRR of the Port and Road Project	5-29
Table 5.3-1	Indicators for Operation Performance and Effectiveness.....	5-31
Table 5.3-2	Indicators for Operation Performance and Effectiveness.....	5-31
