

DRAFT REPORT

Environmental & Social Impact Assessment (ESIA) of Proposed 450 MW Wind and Solar Hybrid Project at Jaisalmer and Barmer Districts in Rajasthan

JULY 2020



Prepared for:

Lenders and SBE Renewables Ten Pvt. Ltd.

Prepared by:

Arcadis India Private Limited

CONTACTS

DR BIPAL JANA
Principal Consultant

bipal.jana@arcadis.com

Arcadis India Private Limited

3rd Floor, Tower B
Logix Techno Park, Sector 127,
Noida-201304, India

QUALITY ASSURANCE

Issue Number /Status	Date	Prepared By	Technical Review & Authorised by
001-Draft V.01	June 2020	Mousumi Mondal Chhavi Ankita	Dr. Bipal Jana
002- Draft V.02	July 2020	Mousumi Mondal Chhavi Ankita Santu Gorai Bonhisikha Banerjee	Dr. Bipal Jana

Confidentiality:

This report is strictly confidential and is to be used exclusively by its investors and SBE and not be shared with any other party without prior written permission from Arcadis. Reproduction of any part of the report may attract legal action.

Disclaimer:

Information contained in this report is based on the observations during survey and interview with stakeholders. The interpretation of data and judgment is based on the professional experience and represent professional opinion of the interpreter.

CONTENTS

Executive Summary	1
1.0 Introduction	10
1.1. Background.....	10
1.2. Location of the Site	10
1.3. Salient Features of Project	11
1.4. Key Permitting and Compliance Status	12
1.5. Purpose of ESIA Study.....	13
1.5.1. Approach and Methodology of the ESIA Study	13
1.5.2. Limitations	14
1.5.3. ESIA Team.....	14
2. Project Description	15
2.1. Present Status of Project.....	15
2.2. Site Suitability and Justification of Project.....	18
2.3. Environmental and Social Settings	19
2.4. Resource Requirement	20
2.4.1. Land Scenario/ Status of land.....	20
2.4.2. Water Requirement.....	21
2.4.3. Manpower Requirement.....	21
2.4.4. Wastewater Treatment and Disposal System.....	21
2.4.5. Logistic Arrangement	22
2.4.6. Implementation Schedule for the Project.....	22
3. Applicable Regulations, Guidelines and Standards.....	24
3.1. National Regulations	24
3.2. Environmental and Social Performance Standards of the International Finance Corporation.....	30
3.3. Categorization of Projects	41
3.3.1. Categorization of Projects as per IFC guideline	41
3.4. World Bank Group's EHS Guidelines and applicable sector guidelines	41
3.5. Equator Principles	44
4. Description of Environment	46
4.1. Study Area	46
4.2. Baseline Conditions	46
4.2.1. Climate and Meteorological Conditions	46
Topography	50
4.2.3. Land use Analysis	52
4.2.4. Drainage.....	52
4.2.5. Hydrogeology	53
4.2.6. Ground Water Resources	55
4.2.7. Seismic Hazard	58
4.2.8. Wind Hazard	59

4.2.9. Flood Hazard.....	60
4.3. Environmental Monitoring	61
4.3.1. Ambient Air Quality	61
4.3.2. Ambient Noise Quality.....	63
4.3.3. Surface water Quality.....	65
4.3.4. Groundwater Quality	67
4.3. Ecological Environment.....	71
4.3.4. Methodologies for Ecological Surveys.....	71
4.3.5. Habitat Survey.....	72
4.3.6. Primary Survey.....	77
4.4. Socio-Economic Environment	85
4.4.4. Objective	85
4.4.5. Methodology.....	86
4.4.6. Demographic Profile.....	86
4.4.7. Schedule Caste and Schedule Tribes (SC/ST)	89
4.4.8. Literacy in the Study Area	90
4.4.9. Workers and Occupation	91
4.4.10. Wages	93
4.4.11. Livelihood Resource.....	93
4.4.12. Livestock	93
4.4.13. Local Employment and Migration.....	94
4.4.14. Gender Empowerment Status.....	94
4.4.15. BPL Families & Vulnerabilities	94
4.4.16. Land Holding Pattern	94
4.4.17. Irrigation	95
4.4.18. Amenities & Infrastructure.....	95
4.4.19. Common Property Resources (CPR).....	98
4.4.20. Archaeological Site	99
4.4.21. Community & Institutional Consultation:	99
4.4.22. Needs Gap Assessment for CSR Initiatives	104
5. Analysis of Alternatives.....	106
5.1. Current or No Project Scenario.....	106
5.2. Energy Security	106
5.3. Alternate Methods of Power Generation	106
5.3.1. Alternate Routes for Transmission Lines	108
5.4. Site suitability and justification for the project	108
5.5. Conclusion	108
6. Environmental & Social Impact Assessment.....	109
6.1. Approach & Methodology	109
6.1.1. Significance Evaluation Matrix	109
6.2. Impacts on Physical Environment	112
6.2.1. Air Quality.....	112

6.2.2.	Soil Quality	112
6.2.3.	Noise Quality	113
6.2.4.	Alteration of Natural Drainage Pattern	119
6.2.5.	Water Resources	120
6.2.6.	Solid/ Hazardous Waste Disposal.....	120
6.2.7.	Impact on Land and Land use	121
6.2.8.	Impact on Local Ecology	122
6.2.9.	Socio - economic Impact.....	129
6.2.10.	Health and Safety Impact.....	132
6.3.	Cumulative Impacts	140
6.4.	Conclusion	141
7.	Environmental & Social Management Plan.....	142
7.1.	Training of Personnel & Contractors.....	142
7.2.	Monitoring	143
7.3.	Documentation & Record Keeping	143
7.4.	Environmental Monitoring Plan	163
7.5.	Environmental Management Plans	163
7.5.1.	Emergency Preparedness and Response Plan	163
7.5.2.	Community Liaison Plan	166
7.5.3.	Waste Management Plan.....	167
7.5.4.	Storm Water Management Plan.....	167
7.5.5.	Community Property Resource	168
7.5.6.	Occupation Health and Safety Management Plan.....	168
7.5.7.	Grievance Redressal Mechanism (GRM)	170
7.5.8.	Community Development Plan under CSR	170
7.5.9.	Road Safety and Traffic Management Plan.....	171
7.5.10.	Ecological Management Plan	173
7.5.11.	Stakeholder Engagement Plan (SEP).....	174
7.5.12.	Provisions for ESMP Implementation	178
8.	Conclusion and RECOMMENDATION	179
8.1.	Impacts Assessment	180
8.2.	Level of compliance and gap with Applicable IFC Standards	182

LIST OF TABLES

Table-1: Salient Features of Project	11
Table 2: Status of Permits and Approvals	12
Table 3: Technical Features of Project.....	15
Table 4: Water Requirement During Construction and Operation Phase.....	21
Table 5: Applicable Environmental, Health, Safety and Social Regulations	25
Table 6: IFC's Environmental and Social Performance Standards	30
Table 7: World Bank Group's EHS Guidelines and applicable sector guidelines	42
Table 8: Compliance to Equator Principles	44
Table 9: Climate Data for Barmer (1901-2000).....	47
Table 10: Climate Data for Jaisalmer (1901-2000).....	47
Table 11: Ambient Air Quality Monitoring Results.....	61
Table 12: Noise Quality Monitoring Results	63
Table 13: Surface water Analysis Results	65
Table 14: Groundwater Analysis Results.....	67
Table 15: List of Trees Reported in the Project Area.....	78
Table 16: List of Fauna reported in the Project Area.....	79
Table 17: List of Recorded Birds	79
Table 18: Project Location.....	86
Table 19: Socio- Economic profile of the Barmer District.....	86
Table 20: List of Villages within the Project Area	87
Table 21: Demographic Profile of the Project Area.....	88
Table 22: Study Area SC & ST Percentage	89
Table 23: Study Area Literacy Scenario.....	90
Table 4-16: Study Area working Scenario.....	91
Table 25: Categorization of workers.....	92
Table 26: Minimum Wages for Labourers (INR)	93
Table 27: Telephonic Consultation with Stakeholders	100
Table 28: Stakeholders Consultation Contact details	100
Table 29: Key Needs/Gaps Identified	104
Table 30: Advantages and Disadvantages of various non-renewable and renewable energy	106
Table 31: Screening Criteria for Environmental and Social Impact Assessment.....	109
Table 32: Impact Significance Matrix	109
Table 33: Aspect Impact Matrix for Construction and Operation Phase	111
Table 34: Noise modelling results	116
Table 35: Details of Plantation Recommended for Greenbelt.....	127
Table 36: Shadow Flicker Sensitivity	135
Table 37: Shadow Flickering Modelling Results Detailing the Shadow Hours Received at the Receptors wrt to the Nearest WTG Locations	137
Table 38: Overall Project Risk Assessment.....	140
Table 38: Environment Management Plan	144

Table-39: Environment Monitoring Program	163
Table 40: Stakeholder Engagement Strategy	176
Table 41: Impact Assessment Summary	180
Table 42: Environmental and Social Action plan	182

LIST OF FIGURES

Figure 1-1: Project Location Map.....	11
Figure 2-1: Satellite Imagery (Google Map) Showing the Project Site	16
Figure 2-2: Accessibility of the Project Site	17
Figure 4-1: Monthly mean rainfall distribution of Barmer	47
Figure 4-2: Monthly mean rainfall distribution of Jaisalmer	48
Figure 4-3: Indian Solar Resources	49
Figure 4-4: Topography of the Project Site.....	50
Figure 4-5: Digital Elevation Map	51
Figure 4-6: Land Use Map.....	52
Figure 4-7: Drainage Map.....	53
Figure 4-8: Hydrogeology Map of Barmer district.....	54
Figure 4-9: Hydrogeology Map of Jaisalmer district.....	55
Figure 4-10: Depth to water level during pre-monsoon -Barmer	56
Figure 4-11: Depth to water level during post-monsoon -Barmer	56
Figure 4-12: Depth to water level during pre-monsoon -Jaisalmer	57
Figure 4-13: Depth to water level during post-monsoon -Jaisalmer	57
Figure 4-14: Seismic Map	58
Figure 4-15: Wind Hazard Map	59
Figure 4-16: Flood Hazard Map	60
Figure 4-17: AAQ Monitoring Results Graphical Interpretation	62
Figure 4-18: ANQ Monitoring Results Graphical Interpretation	64
Figure 4-19: Environmental Quality Monitoring Location Map.....	70
Figure 4-20: Map showing presence of no hotspots and sightings around the project area	72
Figure 4-21: Location of project area on the Biogeographic Zones.	73
Figure 4-22: Important Land use features in the study area.....	74
Figure 4-23: Forest Office of Jaisalmer	76
Desert National Park	Error! Bookmark not defined.
Figure 4-26: Birds observed at Project site.	82
Figure 4-27: Population Distribution in the study Area.....	89
Figure 4-28: SC & ST Population in the Study Area.....	90
Figure 4-29: Literacy in the Study Area.....	91
Figure 4-30: Status of working population in the Study Area.....	92
Figure 4-31: Medical facility Available at Villages.....	95
Figure 4-32: Educational Facility at study area	96
Figure 4-36: Stakeholder consultations at project study area.....	101

Figure 6-1: types of transmission lines.....126

APPENDIX

APPENDIX A: WTG Profiling188
APPENDIX B: ILO Guidelines232
APPENDIX C: Sample Questionnaire for community consultation.....233
APPENDIX D: Attendance Sheet of Stakeholders Consultation.....236
APPENDIX E: Summary of Stakeholders Consultation.....240
APPENDIX F: Draft LAND LEASE copy (BARmer/ Jaisalmer)249
APPENDIX G: Shadow flicker modelling.....251
APPENDIX H: Noise Modelling.....257

LIST OF ABBREVIATIONS

AC	Alternative Current
AWC	Anganwadi Centre
BPL	Below Poverty Line
CGWB	Central Ground Water Board
CSR	Corporate Social Responsibility
CTE	Consent to Establish
CTO	Consent to Operate
CFE	Consent for Establish
DC	Direct Current
DNP	Desert National Park
E&S	Environmental and Social Risk
EIA	Environment Impact Assessment
EPFI	Equator Principles Financial Institutions
ESIA	Environment and Social Impact Assessment
ESMP	Environmental Social Management Plan
FI	Financial Institutions
GRM	Grievance Redressal Mechanism
GW	Ground Water
IFC	International Finance Corporation
ICDS	Integrated Child Development Scheme
ILO	International Labour Organization
IUCN	International Union for Conservation of Nature
IPP	Independent Power Producer
Lpcd	Litre per capita per day
KLD	Kilo Litre per day
RSPDCL	Rajasthan Solar Power Development Corporation Limited
RSPCB	Rajasthan State Pollution Control Board
Km	Kilo meter
LA	Livelihood Assessment
LIA	Livelihood Impact Assessment
m	Meter
m bgl	Meter below ground level
MNRE	Ministry of New and Renewable Energy
MOEFCC	Ministry of Environment, Forest and Climate Change
NTPC	National Thermal Power Corporation
PAP	Project Affected People
PCB	Pollution Control Board
PUC	Pollution under control certificate
PS	Performance Standard

R & R	Rehabilitation & Resettlements
RF	Reserved Forest
SHG	Self Help Group
WPA	Wildlife Protection Act
SBM	Swachch Bharat Mission
SOP	Standard Operation Procedures
SCADA	Supervisory Control and Data Acquisition
SPCB	State Pollution Control Board

EXECUTIVE SUMMARY

Background SBE Renewables Ten Private Limited (Bidding Entity) has won the project through reverse auction conducted by SECI on 5 Dec 2018 under the RFS floated by SECI on 22 June 2018 for setting up ISTS connected Solar Wind Hybrid Power Projects. SBE Renewables Ten Projects Pvt Ltd (“SBE Ten Projects”) [100% step-down subsidiary of SBE Renewables Ten and Project SPV] has been created with the purpose of setting up a 450 MW ac Solar Wind Hybrid power generation facility in Jaisalmer district, Rajasthan. SBE Renewables Ten Projects Pvt Ltd, a SoftBank Group (‘Group’) company, is a wholly owned step-down subsidiary of SB Energy Holdings Limited (“SBEHL”).

The LOA was awarded for the project on 25 Jan 2019 with a tariff of INR 2.67/kWh. Power Purchase Agreements was executed on 31st of December 2019 for the off take of the entire power produced from the Project with SECI (rated ICRA AA+) for a period of 25 years. For 450 MW project (105.3 MW Wind and 420 MW ac Solar (55% DC oversizing)) SECI has issued two LOAs of 150 MW and 300 MW and separate PPAs has been already executed for respective LOAs.

Considering this is an ISTS project, the Project Company shall be responsible for the land acquisition and grid connectivity. The PGCIL Sub-Station location has been identified at Fatehgarh, Jaisalmer district, Rajasthan.

Arcadis India Private Limited (hereafter referred as Arcadis) was appointed as lenders advisor to undertake an Environmental and Social Impact Assessment (ESIA) study of Hybrid power project in accordance with IFC’s Performance Standards, Equator principles, World Bank Group’s EHS Guidelines and applicable sector guidelines and national environmental laws and regulations.

The site visit for the ESIA study has been undertaken to assess any potential impacts (both negative and positive) that may arise from the construction, operation and decommissioning of the hybrid wind-solar plant. The goal of the ESIA is to enhance sustainability of vital ecosystem, to improve or restore ecosystem health and biodiversity. The Environmental and Social Impact Assessment (ESIA) study for the project has been undertaken in accordance with the scope of work assigned to Arcadis. This ESIA report is based on International Finance Corporation’s (IFC) Performance Standards (PS) on Social and Environmental Sustainability, 2012, World Bank Group’s EHS Guidelines and Indian environmental standards. Environment, Health and Safety Guidelines, Equator Principles; Relevant ILO conventions covering labour standards. The study will also assess the sustainability of the project w.r.t the local and national regulations relevant to the project.

Project Overview

The proposed 450 MW Hybrid Project will be falling on the government land parcel measuring approximately 840 Ha for Solar and 260 Ha for Wind. Land will be allotted to SBE on sub lease basis. The project is in pre-construction stage. Since this is entirely Revenue Land, SBE is required to make an application to RRECL which then recommends for allotment of the said project land to District Collector for allotment. After obtaining necessary NOCs and approvals from relevant govt. departments allotment order is issued by District collector and lease deed is signed. Landowner is Govt. of Rajasthan and application has been made to RRECL for allotment of land. No Sales Deed applicable.

The land parcels in the project area is unused, fallow, and barren. Site is mostly barren, no vegetation and have undulating to flat terrain at most of the locations with very few hillocks. Most of the locations are accessible through internal village road or kutchra road. NH 15 is passing through the site. Few water bodies are located near WTG location SBE-65, though they are seasonal/ rain-fed.

PPA has been signed between SBE Renewables Ten Projects Private Limited and Solar Energy Corporation of India Limited on 31st day of December 2019 for 450 MW power plant.

Applicable IFC's Performance Standards	<p>The following IFC's performance standards (PS) are applicable for this project:</p> <ul style="list-style-type: none">• PS 1: Assessment and Management of Environmental and Social Risks and Impacts,• PS 2: Labour and Working Conditions,• PS 3: Resource Efficiency & Pollution Prevention,• PS 4: Community Health, Safety and Security.• PS 6: Biodiversity Conservation and Sustainable Management of Living Natural Resources, <p>The following IFC's performance standards are not applicable for this project:</p> <ul style="list-style-type: none">• PS 5: Land Acquisition and Involuntary Resettlement,• PS 7: Indigenous People• PS 8: Cultural Heritage
---	--

PS1: Social and Environmental Assessment and Management Systems	<p>The project will have environmental and social impacts due to generation of onsite air emissions, noise, domestic wastes from site office and rest rooms, and generation of hazardous wastes from the construction site. SBE has developed Environmental & Social Management System (ESMS) which needs to be followed and implemented to manage the risks associated with its operations. This ESIA report includes evaluation of project specific environment and social risks arising from the project activities along with recommended mitigation measures. SBE should also appoint qualified E&S personnel with appropriate responsibility to implement/ oversee/ monitor the ESMS.</p> <p>Hence, PS1 is applicable.</p>
--	---

PS2: Labour and Working Conditions	<p>Labourers would be involved during construction and operation phase. As reported about 2900 labourers are estimated to be deployed in the peak construction phase.</p> <p>The contractor's workforce will comprise of skilled, semi-skilled and unskilled labours, which may be sourced from the nearby village settlements depending on their skills and capabilities. There is a huge potential for employment of migrant labours on site. The details of the labour engagement during construction phase are given below:</p> <p>Solar: Appx. 2500 Nos.</p> <p>Wind: Kintech to deploys approx. 350 Nos (No woman labours) Employment: Sub Contractor labours, GE to deploy upto ~30-40 Nos.</p> <p>Solar: Appx. 500 may be migrant labour</p> <p>Wind: Appx. 250 migrant labour</p> <p>Solar: Labour accommodation shall be constructed at Site after EPC contractor is mobilised</p> <p>In the operational phase, approximately 15-20 labourers are expected to be deployed onsite by SBE and EPC shall deploy approx. 200 including security guards, operation and maintenance staff.</p> <p>Wind: Dove Resources Private Limited will deploy as per site requirements.</p> <p>Labour camps will be constructed within the periphery of Site for solar project and for wind project arrangement will be made in nearby Villages /Town.</p> <p>Hence, PS 2 is applicable.</p>
---	--

PS3: Resource Efficiency & Pollution Prevention

The project involves use of resources like land and water. Improper handling of broken and damage solar panel may result in soil contamination. Improper handling of spent oil may lead to contamination of soil and ground water.

Though topsoil is very limited in the area, wherever exists Topsoil management is required during site levelling. Construction activities may lead to air and noise emission which needs to be managed. Broken / damaged solar panels may result in contamination of soil and ground water. The project would involve clearing of ground vegetation along with construction and demolition waste.

Robotic cleaning techniques will be used for cleaning of solar module. Water will be required only for domestic purpose. Diesel/ transformer oil/ spent oil may contaminate soil and water.

Hence, PS3 is applicable.

PS4: Community Health, Safety and Security

During construction phase the project envisages influx of labourers from nearby villages and these migrant labourers are expected to interact with community hence there is a possibility of conflict between migrant labourers and local community. Company and contractors will ensure proper stakeholder consultations, grievance redressal mechanism, communication to workers and other stakeholders to avoid any conflict between migrant labour and local community.

Shadow flicker and noise emission during wind turbine operation may impact community health and safety but majority of the receptors are found to be rest house structures with temporary usage (Pump house, resting shade, Agricultural storage , during agricultural work) hence the impact is expected to be moderate.

In India, there are no specific guidelines for wind power project on noise levels. As per IFC's General EHS Guidelines: Environmental, Noise Management, noise impacts should not result in a maximum increase in background levels of 3 dB(A) at the nearest receptor location off-site. Estimated noise generated during operation phase was calculated using Windpro software. The increment in ambient noise level due to WTG operations is anticipated to increase up to a range of 1.7 to 3.8 dB(A), in night-time for the permanent Structures such as SBE 39(1), SBE65_R1, SBE65_R2, SBE65_R3. during the operational phase of the project.

Heavy vehicles would use the existing village roads. Several staff will remain involved during the operation period. The generated electrical energy will be transmitted through high voltage power line, thereby exposing the staff and community to electrical injury cannot be ignored.

Construction of boundary wall may result in restriction of access/ increased distances from common property. Interaction of community with project staff especially security staff would occur.

Thus, PS 4 is applicable.

PS5: Land Acquisition and Involuntary Resettlement

A total of 1100 Ha. of government land will be procured for the proposed 450 MW Hybrid power Project. Out of that, 840 Ha. of government land will be leased for Solar from Rewari village of Seo taluk in Jaisalmer district and 260 Ha for Wind project in 6 villages of Sam block in Barmer District. The government revenue land will be allotted to SBE on lease basis.

As reported during consultation with SBE, land aggregator and people from project impacted villages, land lease will not result in any economic or physical displacement and no adverse impact envisaged for the proposed project.

Therefore, PS 5 is not applicable

PS 6: Biodiversity Conservation and Sustainable

Desert National Park is located at approximately 30 km towards west from the proposed project site which could be depicted as ecological sensitive area. The

Management of Living Natural Resources

nearby area within 10 km radius of the proposed project site is mainly dominated by open scrubby vegetation, stony wasteland, and few grazing lands.

The project area comprises of non-forest wastelands and fallow lands. It is sparsely covered by shrubs and thorny bushes. There are no plantations or orchards. There was no sighting of any known rare, endangered, or ecologically significant animal and plant species as reported during consultation with Forest Official, Desert National Park (DNP). Chinkaras, Nilgais were observed during site visit. Raptors like Egyptian Vulture, Himalayan Griffon, Tawny Eagle and Eastern Imperial Eagle have been reported around the project site as mentioned in the Late Winter Season Final Report - Bird surveys at the proposed hybrid project sites in Rewari and Devaka, Rajasthan by Bombay Natural History Society (BNHS) 4th May 2020. As reported in the Late Winter Season Final Report by Bombay Natural History Society (BNHS) 4th May 2020, during surveys, Great Indian Bustard *Ardeotis nigriceps* was not seen. While two unconfirmed sightings of GIB were reported by local people in year 2017–18 at Negarda (26.280847°, 71.143286°) and in between Khyala and Rewari (26.469018°, 71.052508°) which are westernmost part of the study area. Footprints and feathers of migratory bird MacQueen's Bustard *Chlamydotis macqueenii* (or Asian Houbara) were seen at the Rasla area. A detailed avifaunal study is being conducted by Bombay Natural History Society around the project site to understand the avian diversity of the area and assessing if there are any occurrences of Great India Bustard. Water birds include Ruff, Northern Shoveler, Mallard, Little Ringed Plover etc. Ground dwelling or low flying birds like Indian Peafowl, Shrikes, Drongo, Barbets, Indian Rollers, Grey Partridge, Jungle Bush Quail, Painted Sandgrouse have also been reported. All these raptors are found flying above 30-100 meters from above the ground. The rest of the birds found flying about 20-25 meters above the ground. As far as this project is concerned, in terms of the wind turbine model (considering the hub height and blade length) , birds fly above 60m to 120 m height from the ground can be considered vulnerable to get hit by the wind turbines because of flying within the “Probable Collision Risk Zone” of a WTG. The possibility of mortality of raptors due to collision with the WTGs cannot be dismissed during the operation phase.

The overall impact on ecology is envisaged to be **moderate**.

Therefore PS 6 is applicable for the project.

PS 7: Indigenous Peoples

No impact on tribal community has been envisaged as the project development will be on government land.

Hence, PS 7 is not applicable

PS8: Cultural Heritage

There is no designated archaeological or cultural heritage site within 10 Km radius of the study area village.

During site visit of Arcadis team, no notified Cultural Heritage site is recorded within the vicinity of the project. However, wind sites traverse through a number of religious common properties such as temples, mosques which though not of archaeological significance but nevertheless are significant to the local community. Kapuria math (temple) is located 15 km (approx.) from solar site

Hence, PS 8 is not applicable.

Key impacts during construction phase

Impact on water body: Few Surface water (seasonal/ rain-fed) exists near some WTG locations. Therefore, moderate impact on existing drainage is envisaged and this impact is limited to construction phase only.

Impact on air quality: Generation of fugitive dust due to movement of project vehicles, transportation of fine material (if not covered) and emission from diesel generators and vehicles. Impact will be limited to the construction phase only.

Water resources: As reported to Arcadis, water will be sourced from safe authorized sources through vendor and supplied by tanker during construction phase and will be under the scope of the EPC Contractor. Drinking water requirement during the construction phase will be met via local tankers/ approved vendors. As per the categorization by CGWB the Blocks where the project sites are located falls under over exploited category. Hence, impact on the ground water is anticipated to be High.

Conflict between migrant and local community: During construction phase the project envisages influx of labourers from nearby villages and migrant labourers, these labours are expected to interact with community, there is a possibility of confrontation between migrant labourers and local community.

Traffic Load: The project site is connected to the National Highway (NH-15). The selected land for WTGs is adjacent to the NH-15. This will be used for movement of trailer trucks carrying the equipment and materials. This movement is expected to result in increase in ambient noise levels. However, this increase is short term during construction stage only.

Impact on Ecology:

There will be minimal clearing of vegetation during the construction phase. As per the consultations with local villagers and Forest Official of Desert National Park (DNP) no critically endangered wild species observed in the area. However, animals like Nilgai, Chinkara, Desert Hare have been observed around the site and could be impacted during the construction phase due to the contact movement of vehicles carrying raw materials. Therefore, the impact on ecology is envisaged to be Moderate.

Key impacts during operation phase

Soil & ground water contamination: Improper handling of broken/ damaged solar panels spent oil may result in contamination of soil and ground water. Diesel/ transformer oil/ spent oil may contaminate soil and water.

Water resources: In operational phase water will not be required for panel cleaning as robotic cleaning is proposed throughout the project life cycle. The water requirement would be approximately 9.9 KLD during operation phase for domestic use. Water will be required for domestic purposes by the operations staff. Considering the distribution of impact in within the site, long duration with moderate intensity, significance of impact is assessed as **Low**.

Occupational health and safety of workers: Accidents like electrocution, short circuits may lead to occupational health and safety issues, for which proper training to workers need to be given to combat the same as well as it needs to be further ensured that the workers wear appropriate PPE's according to their nature of work involved.

Social Welfare: Locals may get dissatisfied due to influx of migrant labour. To reduce dissatisfaction among local people regarding the project activity, maximum job opportunity should be provided to the locals on priority during construction phase. Besides, a community development plan along with a grievance redressal mechanism should be followed. It should be ensured that a complaint register is maintained onsite so that any complaints from the stakeholders, locals or labors can be registered, investigated, and timely resolved.

Ecology & Biodiversity: It is generally reported that maximum avian deaths are caused due to collision with transmission lines & WTG blades, hence the project proponent will be using bird diverters at 20ms at closer to the Transmission line or sensitive locations that are observed as per the Avifaunal Study conducted by Bombay Natural history Society, painting the WTG blades and other necessary steps as per standard guidelines. Any dead animals/carcass shall be removed in time from the site so that it does not attract movement of raptors near to the WTGs. While planning project transmission lines, feasibility should be checked for avoiding water bodies crossings. This can be considered for water bodies that could be important

when they turn into suitable habitats. Towers be regularly checked to avoid any nesting in any suitable gaps or platforms. Flash lamps on the WTGs should be installed to reduce the collision risks during nights. Vehicular movements during operation phase are to be set up with speed limits to avoid road kills. All due to the possible avifaunal collision risk the impact on ecology is envisaged to be **moderate**.

Community Health and Safety: Impact may be envisaged due to electromagnetic fields, noise, shadow flicker and accidental blade throw. But with appropriate mitigation measures, the same can be minimized.

Noise: Wind turbines produce noise through a number of different mechanisms, which can be roughly grouped into mechanical and aerodynamic sources. Wind turbines noise could impact on annoyance, sleep and health of the residents at close proximity to the wind turbines. Reconnaissance survey highlighted majority of the receptors to be rest house structures with temporary usage (seasonal usage, Pump house, resting shade as shelter during agricultural work).

- Estimated noise generated during operation phase was calculated using Windpro software. These ambient noise levels at village level were observed to be within permissible limits specified for Residential area as per Noise Pollution (Regulation and Control) Rules, 2000 (without project), However the increment in ambient noise level due to WTG operations is anticipated to increase up to a range of 1.7 to 3.8 dB(A), in night time during the operational phase of the project.
- Out of 7 Identified receptors SBE_11_R1 and SBE 18 (1) are temporary structures and SBE05_R1 is found to be Government office hence very limited mobility expected during day time and hence it is interpreted that there will no impact to these receptors during operation phase of the project.
- However, for permanent Structures such as SBE 39(1), SBE65_R1, SBE65_R2, SBE65_R3 following mitigation measures suggested in this report shall be followed.

Shadow flicker impact: Shadow Flicker Modelling results show that out of 7 identified receptors 3 receptors will receive shadow for more than 30 hours per year from 10 WTGs. However, majority of the receptors identified during site survey are Temporary use structures (Pump house, resting shade, Agricultural storage) located within 300 m radius of WTG's. The modelling results is provided in **Appendix. G**.

WTG profiling of all locations was undertaken based on Ground truthing during the site visit. Site visit was undertaken to understand the status of receptors, from this study. However as per the WTG profiling carried out on site by SBE and Arcadis, two receptors found to be sensitive SBE 5 R1 and SBE 65 R3 as it is a permanent structure (Government office cum control building, Residential House). SBE_11_R1 are found to be temporary use (cattle shade). Impacting WTGs with status of receptors are provided in respective sections in the report.

Blade Throw: A failure of the rotor blade can result in the "throwing" of a rotor blade, or part thereof, which may affect public safety which are mainly because of mechanical failures. The overall risk of blade throw is extremely low with regular maintenance.

Key Mitigation Measures

Appropriate mitigation measures have been planned and recommended in the ESIA report. These measures will minimise the impacts on air, water, soil, noise quality, solid and liquid effluent waste, ecology and socio-economic conditions. The activities of the project during both construction and operation phase will help in improving the socioeconomic condition of the surrounding area.

Construction Phase

- Proper water sprinkling of road should be undertaken to reduce the fugitive
-

emissions during transportation.

- Wind turbines should be designed in accordance with the international acoustic design standards.
- Grievance Redressal mechanism should be followed by SBE and its sub-contractors. It should be ensured that a complaint register is maintained onsite so that any complaints from the locals or labours can be registered, investigated and timely resolved.
- Proper PPE's viz. gloves, glasses, helmet and shoes should be worn by workers/labours while handling solar panels as well as during other activity during construction phase.
- It should be ensured that the accommodation provided to the migrant workers should meet national and international standards laid down by ILO, IFC. Basic amenities such as electricity, potable drinking water, waste disposal, health & sanitation facility and kitchen to be provided.
- Integral noise shielding to be used where practicable and fixed noise sources to be acoustically treated by using for example silencers, acoustic louvers and enclosures.
- Strict prohibition shall be implemented on trapping, hunting or injuring wildlife within subcontractors and shall bring a penalty clause under contractual agreements.
- Camp and kitchen waste shall be collected in a manner that it does not attract wild animals.
- Temporary barriers/fencing shall be installed on excavated areas.
- The speed limit of the heavy vehicles should be maintained.
- All the vehicle should have valid PUC certificate.
- Hazardous materials such as waste oil, used oil should be stored at designated locations in enclosed structures over impermeable surface.
- Hazardous Waste authorization as per Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 should be obtained
- NOC for ground water abstraction should be obtained in the event developer/project proponent install bore well for ground water abstraction to meet water requirement for the project activity.
- Complaint register should be maintained onsite to receive complaints from locals and workers

Operational Phase:

- Sourcing of water from approved vendors should be considered by EPC contractor.
- Implement the recommended complaint resolution procedure (Grievance Redress Mechanism) to assure that any complaints regarding noise and shadow flickering or any other issue related to project activity is not left unnoticed. The complaints should be registered, investigated, and timely resolved.
- To minimize "Lake effect", visual frightening techniques may be considered to frighten any bird trying to land on panels and prevent birds from landing.
- Use of curtains, higher fencing and planting trees can be explored at locations which will get impacted due to shadow flicker.

- Rainwater harvesting structures/ water conservation structures should be used to meet the operational water needs
- Hazardous waste viz. waste oil used oil, used grease, wastes or residues containing oil, empty barrels/ containers/ liners wastes or residues Containing oil etc. will be collected and stored in paved and enclosed area with secondary containment and subsequently sold to authorized recyclers/ Transfer storage disposal facility (TSDF) in compliance with RSPCB norms.
- Vehicular movements during construction phase are to be set up with speed limits to avoid road kills.
- Bird diverter should be installed in transmission line which the client will be complying with respect to the sensitive areas as suggested by the study undertaken by Bombay Natural History Society (BNHS)
- Painting the tip of the blades for better visibility
- Towers be regularly checked to avoid any nesting in any suitable gaps or platforms.
- Flash lamps on the WTGs should be installed to reduce the collision risks during nights.
- If any nests of ground dwelling birds/ reptiles are found the Forest Department is to be notified so that the eggs of reptiles/ birds don't get displaced.
- Implement the recommended complaint resolution procedure (Grievance Redress Mechanism) to assure that any complaints regarding noise and shadow flickering or any other issue related to project activity is not left unnoticed. The complaints should be registered, investigated, and timely resolved.
- Visibility enhancement objects such as marker balls, bird deterrents, or diverters can be installed along the transmission line specially wherever recommended by BNHS to avoid bird collision.
- The tip of blades should be painted to increase visibility and avoid collision

Decommissioning Phase:

- Decommissioning consists of the removal of facility components, the management of excess materials and waste and the restoration of Project Location lands and waters, as applicable to facilitate the anticipated future use of the land.
- This Decommissioning Plan should be done to assist the project proponent in fulfilling regulatory requirements as mandated by government agencies for the decommissioning of the Project.
- The project proponent will adhere to the decommissioning requirements provided in their decommissioning report and will ensure that the project location is restored to a condition appropriate for its future use.
- Decommissioning of the project and any ancillary equipment can be conducted in such a manner as to ensure that there will be no significant negative environmental effects.

Conclusion and Recommendation

The Hybrid power project is not likely to have significant adverse environmental impacts that are sensitive, diverse or unprecedented. It is envisaged to have moderate impact due to issues related to community safety during the construction period, insignificant impact due to generation of dust and fugitive emissions and minor impact on resource utilization like land and socio-economic conditions of

project area villages. There is no impact on cultural resources in the study area. The impacts anticipated during the operation phase is fugitive emissions from movement of project vehicles within the site (air environment), impact on soil due to storage and spillage of hazardous wastes used oil and transformer oil (land environment) as well as use of ground water (if any) resources during operation phase, which can be mitigated by adopting suggested mitigation measures. Considering the short duration, localized distribution and low intensity, noise and shadow flicker impact has been assessed as **Low** significance and can be controlled with the recommended mitigation measures.

There could be possible avifaunal collision risk during the operation phase of the project. All mitigations for avoiding the same are to be implemented. Therefore, the impact on ecology is envisaged to be moderate.

The ESIA study based on the conclusion drawn from the IFC performance standards, Equator Principles and World Bank Group's EHS Guidelines and applicable sector guidelines with respect to the intensity of impacts due to project activities on environment, resources, biodiversity, labours and community, the project is categorized as **Category B** (as per IFCs categorization of projects). This specifies that this project is expected to have limited adverse environment and social impacts, which can be mitigated by adopting suitable mitigating measures

This Executive Summary should be read in conjunction with the full report and reflects an assessment of the site based on information received by Arcadis at the time of reporting.

1.0 INTRODUCTION

1.1. Background

SBE Renewables Ten Pvt. Ltd. is developing the proposed 450 MW Hybrid Power Project on a total of 1100 Ha. of government land will be procured. Out of that, 840 Ha. of government land will be leased for Solar from Rewari village of Seo taluk in Jaisalmer district and 260 Ha for Wind project in 6 villages of Sam block in Barmer District. The government revenue land will be allotted to SBE on sublease basis. Presently, the project is in pre-construction phase and will be developed by SBE in government land parcels.

Arcadis India Private Limited (hereafter referred as Arcadis) was appointed as lenders advisor to undertake an Environmental and Social Impact Assessment (ESIA) study and Environmental & Social Due Diligence of the project as per the standard TOR shared by IFC through SBE.

As reported, land lease has not resulted in any economic or physical displacement and no resettlement is envisaged for the proposed project.

As per Indian solar radiation map of India Rajasthan state receives good amount of solar radiation. Rajasthan receives around 5.5 - 6 kWh/sq. m/day which is potentially adequate for the installation of the PV plant.


SBE is yet to finalise the Engineering, procurement, and construction (Hereafter known as EPC) contractor for development of this proposed project. EPC contractor will be responsible for installation of solar panels, WTG structures, construction of transformers in existing pooling substation and laying of transmission line. Post construction, operation, and maintenance (O&M) contractor will be responsible for long term operation and maintenance of the site.

This ESIA report has been prepared based on Site visit baseline survey, desktop survey, documentation review, consultation with stakeholders and in accordance with International Finance Corporation's (IFC) Performance Standards (PS) on Environmental and Social Sustainability, 2012; Environment, Health and Safety Guidelines of World Bank Group, Equator Principles; Relevant ILO conventions covering labour standards. The study has also assessed the requirement of the project with respect to the local and national regulations relevant to the project

1.2. Location of the Site

The site is of a total of 1100 Ha. of government land will be procured for the proposed 450 MW Hybrid power Project. Out of that, 840 Ha. of government land will be leased for Solar from Rewari village of Seo taluk in Jaisalmer district and 260 Ha for Wind project in 6 villages of Sam block in Barmer District. The location map is depicted in **Figure 1-1**.

Figure 1-1: Project Location Map



1.3. Salient Features of Project

The salient features of the project are summaries in Table-1.

Table-1: Salient Features of Project

S. N.	Salient Features	450 MW hybrid wind-solar project
1.	Project Owner	SBE Renewables Ten Pvt. Ltd.
2.	Project Capacity	450 MW
3.	Location of Site	Villages of Devka and Rewari from Sam taluk of Jaisalmer and villages Mati ka Gol, Bherupura, Hadwa, Manihari, Junejo ki dhani from Sheo taluk of Barmer
4.	Taluka	Fatehgarh
5.	District	Jaisalmer & Barmer
6.	State	Rajasthan
7.	Project Coordinates	Latitude: 26.3404 Longitude: 71.1779
8.	Nearest Town	Dedha (17 km to Sam)
9.	Nearest Railway Station	Jaisalmer railway Station
10.	Nearest Airport	Jaisalmer Airport
11.	Total Land Area	1100 Ha
12.	Type of land	Government Land
13.	Type of Land use (10 km radius from site)	Barren land

14.	Present status of the project/project phase	Pre-construction
15.	Power evacuation	Separate 220/33kV substation for solar and wind, connecting to PSS at 220kV, transmission from PSS to GSS at Voltage of 220 kV
16.	Location of PSS	26°42'29.26"N, 71°16'27.33"E
17.	Transmission Line Length	50 km (from Solar PSS to PGCIL GSS) approx..
18.	Grid Sub-station	PGCIL 220 kV ISTS Fatehgarh II Substation
19.	Mode of Implementation	EPC (Engineering, Procurement and Construction)
20.	Solar PV Technology	Poly crystalline solar PV
21.	Project Life	30 years (based on Land Sub Lease Agreement) & PPA with SECI is for 25 years
22.	Connectivity Approval from PGCIL	Stage 1 and 2 approval received, and LTA agreement signed on 27 May 2020

1.4. Key Permits and Compliance Status

The project is at pre-construction stage. The required permits and approvals for the construction and operation of the project are summarized below **Table 2**

Table 2: Status of Permits and Approvals

S. N	Permits/Approvals	Status	Remarks (if any)
1	Consent to Establish from Rajasthan Pollution Control Board (RSPCB) under Water (Prevention & Control of Pollution) Act, 1974 and the Air (Prevention & Control of Pollution) Act. 1981	Not Applicable	As per CPCB notification No. B-29012/ESS(CPA)/2015-16; dated March 07, 2016 Hybrid power project falls in White category and therefore white category industries do not require to obtain consent of the board, an intimation to the RSPCB shall suffice (APPENDIX A).
2	Hazardous Waste authorization as per Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016	Not Applicable	Solar and wind projects are exempted from purview of Hazardous Waste authorization as per Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016
3	NOC from Village Panchayat	Need to be obtained	NOC from Gram Panchayat will be obtained after Lease Agreement is signed with GoR.
4	Factory License under factories act 1948	Need to be obtained after Commissioning of the Project	With reference to the factories act 1948, the same is applicable because this hybrid plant generating, transforming, or transmitting electrical energy and more than 10 workers are employed/working at site.
5	Power Purchase agreement	Available	PPA is signed between SBE and SECI Limited on 31 st day of December 2019

4	Approval for extraction of ground water	If required needs to be obtained	Central Ground Water Board (CWGB) approval for extraction of groundwater requires to be obtained in case project proponent intends to install bore wells/dug wells for ground water extraction during construction and operation phase.
6	Land Lease	In process	SB Energy will procure land through Rajasthan government land lease Policy.

1.5. Purpose of ESIA Study

The main purpose of the ESIA study is to identify, evaluate and manage environmental and social impacts that may arise due to implementation and operation of the project. The document has been made to comply with the requirements of IFC's Performance Standards, World Bank Group's EHS Guidelines and applicable sector guidelines, as well as applicable local and national regulations. The objectives of ESIA study are:

- To identify and establish the baseline environmental and socioeconomic conditions, to analyse the environmental and social risk and impacts of the project and its associated components (facilities like transmission line, access road etc.)
- Review of the land sale process to assess any legacy or current/existing issues (like informal settlers, livelihood dependence, other usage etc.) on the purchased/ leased land through suitable survey using acceptable socioeconomic tools. This will help in assessing the impact of the project on the community/ villagers.
- Socio-economic survey involving consultation with local community, stakeholders, Land sellers, to identify the needs and problems of community with respect to the project activities.
- To suggest appropriate safeguards for the associated environmental and social risk, which may not lead to project investment and activities at risk.
- Shadow flickering and noise assessment and study of impact of flickering and noise on the nearby structures.

1.5.1. Approach and Methodology of the ESIA Study

The approach and methodology applied for undertaking the environmental and social impact assessment study is as provided.

- Desktop review of project related documents
- Reconnaissance survey to understand site specific issues
- Discussion with the local community in the project influenced villages to understand their perception of the project and identification of key issues.
- Baseline noise level, air, water, soil, ecology, and biodiversity data collection of the site through primary surveys and secondary data source surveys.
- Identification of environmental and social risks associated with the project (including associated facilities) during construction, operation, and decommissioning stage.
- Preparation of an environmental and social management action plan (with timelines & responsibilities) & Environmental monitoring plan to manage these risk and impact.

1.5.2. Limitations

The study is based on observation recorded during site reconnaissance survey, the project planning information and document provided by the project proponent/ Client, stakeholder consultation and desktop review. Any meaningful change in the activities at a later stage may result in variation of outcomes. Presented information and fact has been analyzed and inferences have been drawn through professional judgement. Baseline environmental monitoring has been conducted. As the project is in preconstruction stage, contractors and other details have not been finalised. Hence the resource requirements have been taken as approximation and based on assumptions given by the client.

WTG profiling is carried out via baseline survey, desktop review and Site photographs, videos provided by client.

During Arcadis team visit to the site, land procurement/allotment was under progress and therefore, apparently, land parcels were not demarcated and reportedly the same will be undertaken after allotment by revenue department to SBE. Hence, Arcadis team has to rely upon site representative of SBE to understand the site area. During site visit, the site was greenfield and no activity was noticed in identified land parcels.

Consultation with stakeholders was carried out together with SBE site representative and same is provided in **Appendix D** recorded through photographic evidence.

1.5.3. ESIA Team

Arcadis mobilized a diverse team of multidisciplinary experts for conducting the ESIA study. A number of these experts are accredited professionals by Quality Council of India to conduct regulatory EIA. Combination of these experts have provided consultancy services to over 100 no's each of solar & wind power projects across India with over 14000 MW installed capacity. The experts have been continuously working with funding agency and understand the modalities and procedures of evaluating and addressing environment and social risk associated with large scale investment.

For the purpose of conducting this ESIA study, professionals involved are Ms. Mousumi Mondal and Ms. Ankita Chhavi as main experts. Representatives of SBE accompanied Arcadis professionals Santu Gorai and Bonhisikha Banerjee during site visit and will be referred to as the 'site representative' in the report.

2. PROJECT DESCRIPTION

The proposed project is under pre-construction stage during this ESIA study. As reported by site representative of SBE, the construction works yet to be started and expected to be commissioned in Q3 2020.

The technical features of project are depicted in **Table 3** and satellite imagery of the project site is shown in **Figure 2-1**.

Table 3: Technical Features of Project

Particulars		450 MW hybrid solar-wind project at Jaisalmer
Project Capacity		450 MW
Solar Technology	PV	Poly crystalline solar PV
Inverter		To be among reputed Tier 1 inverter suppliers, SB Energy in past has procured inverters from Sungrow and Kehua
Module Make		To be among Bloomberg Tier 1 module suppliers, SB Energy in past has procured modules from Trina, Risen, ZnShine, Jinergy and Suntech
Robotics System	Cleaning	SB Energy plants deploy 100% waterless cleaning systems, in past SB Energy has procured robotics based waterless cleaning system from Eccopia and Sol-Bright
EPC Contractor		To be among Tier 1 EPC contractors (under process of appointment). SB Energy in past projects has worked with Sterling & Wilson, Mahindra Susten, Tata Solar and L&T
O&M Contractor		Third party Tier 1 O&M contractor to be appointed closer to commissioning of the project – in past SB Energy has appointed Sterling & Wilson
Wind OEM		SBE is in discussions with both Vestas and Suzlon and they have not yet finalised the OEM supplier Further, Wind OEM supplier will be responsible for installation of WTGs For civil foundation work, they have appointed Kintech who's scope will include land acquisition, civil work, transmission line construction, sub-station, internal roads, approvals etc.
Wind Contractor for Land/ BoP/Evacuation		Kintech Synergy (Agreement with Kintech has been signed in Feb 2020) Kintech to be responsible for land acquisition, permits, civil works, Liasoning and construction of evacuation infrastructure.

Source: Details provided by SBE

2.1. Present Status of Project

The project is under pre-construction phase and land identification & land procurement process is going on.

Figure 2-1: Satellite Imagery (Google Map) Showing the Project Site





Figure 2-2: Accessibility of the Project Site



2.2. Site Suitability and Justification of Project

Following analysis describes the site suitability for a Solar PV power plant development, these analyses includes

- **Solar radiation at the site:** Average annual solar radiation at the proposed site at horizontal surface is 5.5 - 6 (Meteonorm) which is potentially adequate for the installation of the PV plant. The power generated will also help to cut out the dependency on the coal to generate the electricity. It is anticipated that grid outage and transmission losses will be considerably low, and this will help to optimize the electricity feed in the grid.
- **Topography:** The project site is spread across an open area with the land being flat with mild undulation.
- **Substation proximity:** Separate 220/33kV substation for solar and wind, connecting to PSS at 220kV, transmission from PSS to GSS at Voltage of 220 kV. The Grid Sub-station (GSS) is PGCIL 220 kV ISTS Fatehgarh II Substation which is approximately 50 km from Solar Site. Application to Connectivity Approval from PGCIL is under process.
- **Clean Technology:** CPCB has categorised Hybrid power projects under White category which pertains to those industrial sectors which are practically non-polluting and having Pollution Index score up to 20.
- **Accessibility:** The site is located about 17 km from Dedha Town. Site is accessible through various internal village roads and NH-15. Jaisalmer railway station (47 KM) are reachable nearest railway stations. The accessibility map is depicted in **Figure 2-2**.
- **Geological and soil conditions:** As per CGWB report (western region Jaipur, 2013 edition), Barmer district forms part of Great Thar Desert of Rajasthan. In this arid region, there are sand dunes, alluvial areas dotted with few hillocks and hill chains scattered in the area. In the eastern part of the district, the area between Bilara and Barmer is covered by alluvium deposited due to fluvial action of Luni river system. The eastern part of the district exhibits gentle undulating topography interrupted by small ridges of hard rocks. Soils of the district have been classified as follows a) Red desertic soils b) Desert soils c) Sand dunes d) Lithosols and regosols of hills.

Jaisalmer district is a part of the 'Great Thar Desert'. The terrain around Jaisalmer town, within a radius of about 60 km is stony and rocky. The area is barren, undulating with its famous sand dunes. There are no rivers worth the name in the area nor are there any perennial streams in the area. Soils of the district are classified as follows a) Desert soil b) Sand dunes c) Red desertic soil d) Saline soil of depressions. Small nallas are purely seasonal and ephemeral with the result that there is lack of effective discharge in the event of heavy precipitation.

- Soils of the district are classified as follows: Desert soil: Desert soil area is occupied by alluvium and wind-blown sand, yellowish brown, sandy to sandy loam, loose, structure less, well drained with high permeability occurring in major part of the district.

Sand dunes: These are non-calcareous soils, sandy to loamy sand, loose, structure less and well drained. These occupy northern, western, southwestern, north-eastern parts of the district.

Red desertic soil: These are pale brown to reddish brown soils, structure less, loose, and well drained. Texture varies from sandy loam to sandy clay loam. These soils occur in eastern, central and south-eastern parts of the district.

Saline soil of depressions: This type of soil is found in salt lakes. They are dark grey to pale brown, heavy soils with water table very near to the surface and are distinctly saline.

- At the time of site visit, habitation near to Site was absent. Also, through site photographs, google earth imageries and desk-based study it is learnt that site is devoid of any habitation.
- No obstacle in the form of trees, buildings exists in the vicinity that could lead to near shading
- The location well addresses the significant land availability, connectivity and accessibility, meteorology and favourable global solar irradiance, shadow free area and required infrastructure.

2.3. Environmental and Social Settings

The key physical features of the project site have been described below:

- Project site is spread across an open area with mild undulation
- The project will be carried out in Reevadi village of Seo taluk in Jaisalmer district and in 6 villages (Mati Ka gol, Manihari, Harwa, Junejon ki Basti, Bhairapura and Deoka) of Sam block in Barmer District. comprising of 1100 ha.
- There are no shading elements such as mountains or huge trees available on the site.
- No large-scale industries located in and around immediate vicinity of the project area.
- There are no such temporary or permanent structures observed within the site. However, there are presence of huts for location SBE 11, 40, 68. For location SBE7, small waterbody is present in nearby low-lying area.
- The land parcel has mild undulation and hence small amount of excavation and levelling of land would be carried out.
- The entire region is reportedly drought prone. No major/large scale water bodies/lakes are located within 10 km from project area.

SBE in process of finalizing various contractors for the project (EPC, modules, inverters, robotics suppliers), as per the primary project information shared by SBE following details are mentioned.

PV Modules: From the technology assessment poly crystalline solar PV technologies have been optimized at the location of Solar park. Using the TIER-1 manufacturers of the key components following models have been chosen for energy yield estimation and project design. SB Energy in past has procured modules from Trina, Risen, ZnShine, Jinery and Suntech. Project developers may choose the technology/ supplier/ manufacturer etc. using their own techno-commercial approach at the project implementation stage.

Inverter: From the technology assessment section the central inverters with outdoor arrangements have been optimized for the location of Solar Park. The outdoor inverters may effectively reduce the project implementation duration and cost. Project developers can take the decision of inverter selection at the implementation stage; however, in order to carry out the energy yield estimation it is proposed to use Tier 1 inverter suppliers, SB Energy in past has procured inverters from Sungrow and Kehua.

SCADA: The PV power plant will be monitored through the SCADA system. This will enable monitoring the status of inverters to gather information on energy generation. Periodic reports of the plant's performance will be provided by the monitoring system. A suitable display system can also be installed suitably in the plant to access live data on the performance of the solar system. Remote data access will be provided through secured gateway connectivity. The status of all breakers shall also be monitored.

Power Evacuation: Separate 220/33kV substation for solar and wind, connecting to PSS at 220kV, transmission from PSS to GSS at Voltage of 220 kV. The Grid Sub-station (GSS) is PGCIL 220 kV ISTS

Fatehgarh II Substation which is approximately 50 km from Solar Site. Application to Connectivity Approval from PGCIL is under process.

2.4. Resource Requirement

2.4.1. Land Scenario/ Status of land

The proposed 450 MW Hybrid Power Project is located on government land parcels measuring approximately 1100 Ha. Of which 840 Ha. of proposed land will be leased for Solar from Reevadi village of Seo taluk in Jaisalmer district and 260 Ha. for Wind project in 6 villages (Mati Ka gol, Manihari, Harwa, Junejon ki Basti, Bhairapura and Deoka) of Sam block in Barmer District.

SBE has engaged Kintech private limited in land procurement, boundary wall and transmission line etc. During Arcadis team visit to the site, land procurement/allotment was under progress and therefore, apparently, land parcels were not demarcated and reportedly the same will be undertaken after allotment by revenue department to SBE. Hence, Arcadis team has to rely upon site representative of SBE to understand the site area. During site visit, the site was greenfield, and no activity was noticed in identified land parcels.

The solar & wind site are proposed in government revenue land parcels. As reported, these land parcels are government declared waste land as per revenue record. Solar site is located contiguous land and wind is scattered locations. Land parcels is being procured for long term lease basis 30 years & extendable by another 10 year

Specifically, for solar site, it was observed the existence of private land parcel which was almost centrally located adjacent to the identified revenue land. This private land was demarcated by pillar & likely to be procured to enhance the project capacity (as reported). For wind site, cluster of households (near Juejo ki Dhani village) exists at an approximate distance of 140m from WTG location SBE65. SBE officials have been informed about the same, and are looking into it.

As reported by revenue official, there are no government declared grazing area/land is planned for this project and none of such land exists within the immediate vicinity of the proposed project and agricultural activities is not permitted in government notified revenue land, however, in surrounding areas, limited agricultural activities based on rainfall were observed in private land.

Based on the visual observation during site visit of Arcadis team and people's consultation, land parcels were devoid of settlements, hence, there is no such evidence of physical and economic displacement and resettlement witnessed for this project. However, as the land parcels for the project (for both wind & solar) are yet to be demarcated, existence of private land parcel (in solar site) and vicinity of village settlement, land allotment/ procurement may result in economic displacement. Hence, after allotment of land and its subsequent demarcation, further study should be undertaken to ensure the need of Resettlement Action Plan (in case of physical and economic displacement) and Livelihood Restoration Plan (in case of economic displacement).

Since this is entirely Revenue Land, SBE is required to make an application to RRECL which then recommends for allotment of the said project land to District Collector for allotment. After obtaining necessary NOCs and approvals from relevant govt. departments, allotment order is issued by District collector and lease deed is signed. At present, owner is Govt. of Rajasthan and Application has been made to RREC for allotment of land.

Lease Rent @ 5% of DLC for 30 Years with an increase of 5% every two years and one-time Land Cost @ 100% of DLC applicable at the time of allotment.

No conversion is required as land will be allotted by Govt. of Rajasthan for specific purpose of establishment of Solar/Wind Energy Project. However, for valuation purpose present rate of DLC is Rs.3,31,000/-Ha for Solar and Rs.2,81,000/-Ha for Wind

Land leased for the project is contiguous and the topography of the project site is largely plain in an open vast area with mild undulations. Based on site observation, the land in the project area was unused, fallow and barren. Also, the land is rocky and barren in nature. The agriculture in the area is majorly dependent on rain and a large portion of the land remains barren most part of the year.

2.4.2. Water Requirement

During the project construction phase, water is required for preparing RCC foundations for module mounting structures, building control room and security rooms, and domestic purpose such as drinking and washing by the construction workers and staff. During operations, robotic cleaning techniques will be used for cleaning of solar panels. Water will be required for domestic purposes by the operations staff. The indicative estimated quantities of water required during the construction and operation phases are presented below **Table 4**

Table 4: Water Requirement During Construction and Operation Phase

Phase	Activity	Max. Consumption
Construction	Civil works water requirement (53 WTG @ 60KLD/WTG)	3180 KLD
	Domestic use – drinking (during peak construction phase) considering 2900 persons @ 110 lpcd	319 KLD
Operation	Domestic use – considering 150 operation and maintenance (O&M) site personals and security guards @ 45 lpcd	6.75 KLD

As reported by SBE, construction phase water need will be sourced through vendor and supplied by tanker and for operation phase it may be sourced through approved/ authorized water tanker vendors. Drinking water requirement during the construction & operation phase will be met via local tankers/ approved/ authorized vendors.

2.4.3. Manpower Requirement

As reported, approximately 2900 labours are estimated to be deployed in the peak construction phase for the foundation structural work, fencing, cleaning and erection of mounting structure. The contractor workforce will comprise of both skilled and unskilled labors. Majority workers will be sourced from the nearby villages depending on their skills and capabilities.

In the operational phase, a total of 150 personnel (approximate) expected to be required onsite including security guards, operation and maintenance officer and site engineers for O&M activities.

2.4.4. Wastewater Treatment and Disposal System

During the construction phase, the wastewater or sewage from site office toilets will be disposed in a septic tank. Proper storm water channels would be constructed along the periphery of the project site for draining of site run off. The domestic wastewater would be managed through septic tanks followed by soak pit.

2.4.5. Logistic Arrangement

Labour Camp: The project is in pre-construction phase and land identification & land procurement process is under process. SBE will engage the contractor for construction purpose. Unskilled labors will be hired locally, and the technical work will be undertaken by the skilled personnel who will stay in rented accommodation nearby to the site area village. As reported by SBE, labour accommodation for solar plant shall be constructed at site after EPC contractor will be mobilized and labour camps will be constructed within the periphery of Site. And for wind project, it is constructed in nearby villages/towns.


Project Vehicles: Project vehicles such as water tanker, tractors, JCB, and cars will be engaged to support various activities during construction phase and further efforts will be made to hire vehicles from local community.

2.4.6. Implementation Schedule for the Project

The proposed project is expected to be commissioned in Q3 of 2020 as reported by site representative of SBE.

Organizational Structure

Organizational structure at project level, represent communication and working relationship at project level. At project level, implementation of management plans and corrective actions are the responsibilities of EHS specialist. In construction and operational phase, site EHS specialist will supervise the third party EHS engineer performance to implement the management action plans in coordination with site manager. On the performance and completion status, site EHS reports to Head EHS.



Social, Health, Environment and Safety Management System (SHES) Committee:

SHES committee is formed at corporate level to review the performance of project on environmental, health, safety and social aspects. Regular updating of SHES is the responsibility of SHES committee in addition to support the top management to achieve the goals as committed in the Policy. SHES committee is formed consisting of one member from HR, Finance, Project and Quality Health, Safety and Environment (QHSE) departments. The QHSE Head is the SHES coordinator for implementing this SHES and will need to interface with several other departments to ensure smooth and efficient functioning of the SHES. SBE employees will be responsible for compliance with EHS regulations and requirements in their work areas.

Key responsibilities are as follows:

- Work in conformance to organizational policies for environmental and social performance
- Understand the SHES
- Complete training on environment, health, safety and social aspect according to work area
- Reporting Environment, Health, Social and Safety (EHSS) related issues & incidents in respective area.
- Ensure fulfilment of requirement of SBE 's ESMS through contractors by providing them training and information on E&S management system (if required) and making necessary provision in their agreement.

Given the footprint of the project will be limited to the sites and their immediate vicinity and the range of stakeholders' dependent on the project site for various usages, SBE should ensure that its hired contractors deploys a social officer or site In-charge to manage social (including labor and community) issues.

3. APPLICABLE REGULATIONS, GUIDELINES AND STANDARDS

This section describes regulations, statutory guidelines and obligatory standards that are applicable to the social and environmental performance of the project.

3.1. National Regulations

In India the Ministry of Environment, Forests and Climate Change (MoEF&CC) is the apex administrative body for (i) regulating and ensuring environmental protection; (ii) formulating the environmental policy framework in the country; (iii) undertaking conservation & survey of flora, fauna, forests and wildlife; and (iv) planning, promotion, co-ordination and overseeing the implementation of environmental and forestry programmes. Several laws have been framed for protection of environment and for Occupational Health & Safety in India by the Central Government. The relevant regulation pertaining to the project activity has been discussed as under. The compliance to all environmental, health, safety and social regulation have been presented in **Table 5**.

Table 5: Applicable Environmental, Health, Safety and Social Regulations

S.N.	National Environment, Health & Safety Regulation	Agency Responsible	Requirement	Applicability /Remarks
1.	The Air (Prevention & Control of Pollution) Act 1981	Rajasthan state Pollution Control Board (RSPCB)	With reference to the CPCB modified direction No. B-29012/ESS(CPA)/2015-16; dated March 07, 2016 Hybrid power project falls in White category and it is mentioned in the notification that there shall be no necessity of obtaining the Consent to Operate” for White category of industries. An intimation to concerned SPCB / PCC shall suffice.	<i>Not Applicable but RSPCB should be informed and SBE will ensure the same</i>
2.	The Water (Prevention & Control of Pollution) Act 1974	RSPCB	With reference to the CPCB modified direction No. B-29012/ESS(CPA)/2015-16; dated March 07, 2016 Hybrid power project falls in White category and it is mentioned in the notification that there shall be no necessity of obtaining the Consent to Operate” for White category of industries. An intimation to concerned SPCB / PCC shall suffice.	<i>RSPCB needs to be informed and SBE should ensure the same.</i>
3.	Guidelines/Criteria for evaluation of proposals/requests for ground water abstraction (With effect from 16.11.2015)	Central Ground Water Authority	As per the Central Ground Water Authority (CGWA), Guidelines/Criteria for evaluation of proposals/requests for ground water abstraction (With effect from 16.11.2015). This guidelines for abstraction of ground water in Notified/Non-Notified areas needs to be followed. Developer contractors needs to take NOC from CGWA.	<i>Applicable This stands applicable in the event developer/project proponent install bore well for ground water abstraction to meet water requirement for construction and operational phase.</i>
4.	Forests (Conservation) Act, 1980 and Rules 1981	Forest Department	The Forest Conservation Act and Rules mandate projects requiring diversion of forest land for non-forest purposes to seek Forest Clearance from the Ministry of Environment and Forests and Climate Change (MoEF&CC)	<i>Not Applicable As reported, no forest land is involved for the development of this project.</i>
5.	Environmental Impact Assessment (EIA) Notification 2006 & MoEF&CC Office Memorandum dated 30 th June'11.	MoEF&CC	The EIA Notification 2006 and thereafter the MoEF&CC Office Memorandum dated, 13 th May 2011 exempts Hybrid power project from obtaining prior Environmental Clearance from the regulatory authorities. But, under the provision of MoEF&CC office memorandum dated 30 th June 2011, requisite permission is required to be obtained from competent authority for water and land usage.	<i>Not Applicable. Hybrid power projects (wind & solar) are not covered under the 2006 EIA notification and therefore, exempt from EIA process for obtaining environmental clearance.</i>

S.N.	National Environment, Health & Safety Regulation	Agency Responsible	Requirement	Applicability /Remarks
6	Environment (Protection) Seventh Amendment Rules 2009	CPCB	Ambient air quality monitoring should be carried out and the concentration limits for the air quality parameters should be in compliance with NAAQS 2009. Activities in the project especially during construction should not result in exceeding National Ambient Air Quality Standards (NAAQS) for ambient concentrations of air pollutants (such as particulate matter). If violation of the Rules takes place, then the penalty will be decided based on the parent Air Act 1981.	<i>Applicable during construction phase and during operation phase</i>
7	Noise (Regulation and Control) Rules 2000 amended in 2010	RSPCB	The Rules stipulate ambient noise limits during daytime and night-time for industrial, commercial, residential and ecologically sensitive areas. The rules apply both during the construction and operation of the project. Violation of the standards for assessing the noise quality due to the project will lead to penalty as under the EPA Act 1986.	<i>Applicable during construction phase and during operation phase Installation of solar panels, construction activities may generate significant amount of noise. During operation phase noise generation is expected from inverter room.</i>
8	Hazardous Waste (Management, Handling and Trans-boundary Movement) Rules 2008 Hazardous and Other Wastes (Management and Transboundary Movement) Amendment Rules, 2016.	RSPCB	These Rules outline the responsibilities of the generator, transporter and recycler/re-processor of the hazardous wastes for handling and management in a manner that is safe and environmentally sound. Project proponent need to obtain consent from State Pollution Control Board for generation and storage of hazardous waste like transformer oil, etc. irrespective of quantity of waste. As per the law the occupier and the operator of the facility should be liable to pay financial penalties as levied for any violation of the provisions under these rules by the State Pollution Control Board with the prior approval of the Central Pollution Control Board.	<i>The operation phase of the project will result in generation of some quantities of hazardous waste, mostly in the form of waste/used oil released from transformer. In this regard, with reference to the stated rule, transformer oil and their tank bottom sludges is defined as used oil and included in schedule I of list of processes generating hazardous wastes. During the construction DG sets will be used for the civil work. As per the site protocols, oil for DG sets is stored in containers. The operation phase of the project will result in generation of some quantities of hazardous waste, mostly in the form of waste/used oil released from transformer as well as broken solar panels. SBE needs to tie-up with any CPCB/ SPCB authorised hazardous waste recycler who has obtained consent/authorization for storage of transformer waste oil. All the hazardous waste generated due to the project should be stored and disposed as per the requirements of Hazardous and Other Wastes (Management and Transboundary Movement) Amendment Rules, 2016. i.e., on a paved surface in a designated area with</i>

S.N.	National Environment, Health & Safety Regulation	Agency Responsible	Requirement	Applicability /Remarks
				<p><i>adequate secondary containment, with adequate labelling and before it is disposed to an PCBA approved vendor.</i></p> <p><i>Broken solar panels are recommended to be disposed through an authorised vendor.</i></p>
9	Wildlife (Protection) Act 1972, Wildlife (protection) Amendment Act 2002 and 2003 amendment.	Chief Conservator Wildlife, NBWL/State Forest Department and MoEF&CC	<p>The Act provides for the protection of wild animals, birds and plants; and for matters connected therewith or ancillary or incidental there to.</p> <p>The application of the Order of the Honourable Supreme Court in WP 460 of 2004 dated 04.12.2006 in the matter of Goa Foundation v. Union of India and other wherein the Honourable Supreme Court has directed that all projects which require environmental clearance and are located within the distance of 10Km of National Park and Sanctuaries must be placed before the standing Committee of the National Board for Wildlife constituted under the Wildlife (Protection) Act, 1972.</p>	<i>Not applicable.</i>
1	The Water Prevention and Control of Pollution), Cess Act, 1977 including Rules 1978 and 1991	Rajasthan State Pollution Control Board	This Act provides for levy and collection of Cess on water consumed and water pollution caused. It also covers specifications on affixing of meters, furnishing of returns, assessment of Cess, interest payable for delay in payment of Cess and penalties for non-payment of Cess within the specified time. Industries consuming water less than 10m ³ /day have been exempted from levy of Cess provided they are not generating hazardous wastes.	<p><i>Applicable during construction and operation phase.</i></p> <p><i>The water demand for construction phase shall be fulfilled through tankers by approved vendors. Project proponent must ensure treatment of Wastewater (if any) due to proposed project activities before disposal.</i></p>
1	Environment (Protection) Second Amendment Rules 2002	MoEF&CC	The DG sets installed during construction should comply with maximum permissible noise levels and noise control measures for diesel generators up to 1000 KVA capacity as specified in the Act.	<i>The power requirement during construction phase shall be met through DG sets, which will adhere to prescribed CPCB noise level limits and noise control measures.</i>
1	The Building and Other Construction Workers' (Regulation of Employment and Conditions of Service) Act 1996	Ministry of Labour and Employment	This Act provides for safety, health and welfare measures of buildings and construction workers in every establishment which employs or employed during the preceding year ten or more such workers. These measures include fixing hours for normal working day, weekly paid rest day, wages for overtime, provision of basic welfare amenities like drinking water, latrines,	<p><i>Applicable during construction phase</i></p> <p><i>Project proponent will ensure through its contractors that basic amenities are provided to the labourers. Project proponent through its contractors should also ensure all vendors employed should have valid labour license. Compensation to workers (own and vendors)</i></p>

S.N.	National Environment, Health & Safety Regulation	Agency Responsible	Requirement	Applicability /Remarks
			urinals, crèches, first aid, canteens and temporary living quarters within or near the work site. This Act also requires application of the following: Building or other construction workers' (regulation and Employment Conditions of Service) Central Rules 1998 & Workman's compensation Act, 1923 to buildings and other construction workers. These will be followed by contractor & developer during construction and operation phase.	<p><i>should not be below daily wage rate as specified by Government. Muster roll must be maintained. Employee ID card must be issued (own and vendors). Safety, health and welfare measures of building and construction workers as mentioned in the act needs to be complied with.</i></p> <p><i>Failure to comply results in financial penalty /imprisonment of the principal employer along with vendor and closure of project</i></p>
1	Central Electricity Authority (Safety Requirements for Operation, Construction and Maintenance of Electric Plants and Electrical Lines) Regulations 2008, (CET)	Min. of Power, Central Electricity Authority	The Act is applicable for the Wind - Solar Hybrid Power Project as the plant is going to be having electrical appliances and facilities installed for grid connected power generation. As per the act, all equipment's and system installed should comply with the provision of the statute, regulations and safety codes.	<p><i>Applicable both during construction and operation phase</i></p> <p><i>Project proponent under provisions of the CET regulations ensure that the health and safety requirements and provisions for transmission lines specified under the rules are complied.</i></p>
1	Workmen's Compensation Act, 1923 & Rules 1924	Labour Welfare Board, Rajasthan	The Act requires if personal injury is caused to a workman by accident arising out of and in the course of his employment, his employer should be liable to pay compensation in accordance with the provisions of this Act.	<p><i>Applicable during construction and operation phase.</i></p> <p><i>Project proponent should ensure through its contractors in case of any accident/ injury/ loss of life the workmen should be paid a minimum compensation as calculated under this act both during construction and operation phase of the project. The reporting of accidents needs to be done in prescribed forms as per the act and the incident / accident register needs to be maintained accordingly. The Act also gives a framework for calculating amount of compensation and wages.</i></p>
1	The Contract Labour (Regulation and Abolition) Rules, 1971 Contract Labour (Regulation and Abolition), 1973	Labour Welfare Board, Rajasthan	The Contract Labour (Regulations & Abolition) Act, 1970 requires every principal employer of an establishment to make an application to the registering officer in the prescribed manner for registering the establishment. The Act and its Rules apply to every establishment in which 20 or more workmen are employed on any day on the preceding 12 months as contract labour and to every contractor who employs or who employed	<p><i>Applicable during construction and operation phase.</i></p> <p><i>All vendors employed including contractors should have valid labour license. Compensation to contract workers (own and vendors) should not be below daily wage rate as specified by Government of India. Muster roll must be maintained. Employee ID card must be issued (own and vendors). Safety, health and welfare measures of</i></p>

S.N.	National Environment, Health & Safety Regulation	Agency Responsible	Requirement	Applicability /Remarks
			on any day preceding 12months, 20 or more workmen. It does not apply to establishments where the work performed is of intermittent or seasonal nature. An establishment wherein work is of intermittent nature will be covered by the Act and Rules if the work performed is more than 120 days in a year, and where work is of a seasonal nature if work is performed more than 60 days in a year.	<i>building and construction workers as mentioned in the act needs to be complied with. Failure to comply results in financial penalty.</i> <i>SBE through its contractors should also ensure that conditions like hours of work, fixation of wages and other essential amenities in respect of contract labour are provided and in compliance with the standards.</i>
1	Minimum Wages Act, 1948	Labour Welfare Board, Rajasthan	This Act provide for fixing minimum rates of wages in certain employments and requires the employer to provide to every worker engaged in a scheduled employment to be paid wages at a rate not less than the minimum rate of wages fixed by such notification for that class of employees in that employment without any deductions except as may be authorized within such time and subject to such conditions as may be prescribed.	<i>Applicable during construction and operation phase</i>
1	Factory License under factories act 1948	Central Government	With reference to the factories act 1948, the same is applicable because this solar plant generating, transforming or transmitting electrical energy and more than 10 workers are employed/working at site.	<i>Applicable.</i> <i>SBE should obtain the same for this project during Project Commissioning.</i>
1	The Child Labour (Prohibition and Regulation) Act, 1986	Labour Welfare Board, Rajasthan	The Act prohibits employment of children in certain occupation and processes. The Act also specifies conditions of work for children, if permitted to work.	<i>SBE should ensure that no child labour is engaged at site for construction or operation works either directly or by the sub-contractors. SBE should include a clause in the subcontractor agreements prohibiting employment of child labour.</i>
1	Companies Act, 2013	SBE	According to Schedule 135 sub -section 1, the companies meeting the threshold criteria (Minimum net worth of rupees 500 Crore, Turnover up to "1000 Crore" and having a net profit of at least '5 crore') specified should spend in every financial year, at least 2% of the average net profits of the Company made during the three immediately preceding financial years in pursuance of CSR policy.	<i>The project will need to comply with the requirement as stated in the law.</i>

3.2. Environmental and Social Performance Standards of the International Finance Corporation

The International Finance Corporation (IFC) has laid down a set of eight Performance Standards (PS) and project developers need to comply with applicable PS while establishing the project in the event the project is financed by IFC or multinational funding institution. The provisions of the Performance Standards relevant to the Hybrid power projects are summarized below:

Table 6: IFC’s Environmental and Social Performance Standards

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
<p>Performance Standard (PS) - 1 Assessment and Management of Environmental and Social Risks and Impacts</p>	<p>Conduct an Environmental and Social Impact Assessment (ESIA) of the project, appropriate to the nature of the project’s environmental and social risks and potential impacts.</p> <hr/> <p>Establish Environmental and Social Management Plans commensurate with the findings of the ESIA and consultation with affected communities</p>	<p>Arcadis has been appointed as lenders advisor to undertake ESIA study to identify the environment and social risks that may arise due to the Hybrid power project and recommend mitigation measures for the same as provided in Chapter 6.</p> <p>The PS 1 is applicable to projects with environment and/or social risks and/or impacts. The project is a Hybrid power project and will have environmental and social impacts resulting generation of noise, construction activities etc.</p> <p>PS 1 is therefore applicable for the project.</p> <hr/> <p>An Environmental and Social Management Plan has been prepared and incorporated in Chapter 7 of the ESIA report taking into consideration the potential social and environmental impacts or risks already identified & assessed in ESIA.</p>	<p>SBE has developed an Environmental and Social Management System at the corporate level as well as adhere to the environment and social management plan recommended for its wind-solar hybrid project at the ground level. SBE is required to fulfil the following requirements:</p> <ul style="list-style-type: none"> • Environmental and social action plan. • Identification of risks and impacts. • Management program. • Organizational capacity and competency. • Training for security and safety workers. • Emergency preparedness and response. • Stakeholder engagement/ grievance redressal; and • Monitoring, reporting and review.

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
	<p>Establish Action Plans where specific mitigation measures and actions are required for the project to comply with applicable laws, regulations and the requirements of these Performance Standards</p>	<p>An ESMP has been prepared and incorporated in Chapter 7 of the ESIA report for implementation of mitigation measures in compliance with the statutory requirements and Performance Standards.</p>	
	<p>Provide organizational capacity and contractor / employee training to enable project to achieve continuous environmental and social performance</p>	<p>Organizational structure with roles and responsibilities of the team within the organization is defined in Chapter 2.</p>	
	<p>Establish and maintain a timely process of community engagement, including a grievance mechanism, focusing on disclosure of information and consultation with local communities affected by project risks or adverse impacts that is free from external manipulation, interference or coercion to ensure relevant and understandable access to project information.</p>	<p>This should aim to inform the community project related adverse impacts or risks. The grievance redressal mechanism has been developed and presented in SI. No 6.7.7. Also, SBE's Grievance Redressal Mechanism (GRM) is in place which is recommended for implementation in this project.</p>	
	<p>Establish procedures to monitor and measure the effectiveness of the environmental and social management program, including internal reporting of the program's effectiveness to the project's senior management, disclosure of Action Plans (including material changes to such Plans) to affected communities, and external reporting to affected communities on the results of Action Plans, commensurate with the concerns of the affected communities</p>	<p>System of monitoring with periodic audits will be established at all the six study area villages.</p>	
<p>PS 2: Labour and Working Conditions</p>		<p>The PS 2 applies to workers directly engaged by the client (direct workers), workers</p>	<p>SBE should ensure that adequate facilities and amenities are provided in the labour accommodation for construction workers including: adequate living/sleeping</p>

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
	<p>Establishment of a Human Resources Policy consistent with the requirements of this Standard that informs employees of their rights under national labour and employment laws</p>	<p>engaged through third parties (contracted workers), as well as workers engaged by the client's primary suppliers (supply chain workers).</p> <p>The project involves employment of 2900 nos. direct and contracted workers during construction and 350-375 no's during operation phases. Locals will be hired to carry out unskilled work.</p> <p>PS 2 is therefore applicable for the project.</p>	<p>facilities and space per person; potable water that meets national standards and standards as laid down by ILO; toilets, washing and cleaning facilities; canteen/mess or fuel for cooking; locker/storage facilities; and facilities for management and disposal of garbage, sewage and other waste. The company will periodically review and monitor the condition of the labour accommodation. The worker accommodation standards as laid down by ILO is presented in the below sections.</p> <p>The company, as a part of oversight procedures will need regular monitoring of compliance to the aforesaid guidelines/requirements and ensure that these are met at all the project sites. Internal audits and follow up on corrective actions will also need to be undertaken to assess efficacy of the oversight system at all the said project sites.</p> <hr/> <p>SBE has HR policies at the corporate level. SBE should inform their employees their rights under national labour and employment laws.</p> <p>The company will need to communicate with the contractors on its SHES system and HR policies.</p> <p>As per the PS 2 requirements, SBE will ensure access to grievance mechanisms, health & safety, benefits and welfare provisions etc. to all workers. Provision of trainings and capacity building support will have to be provided to the contractors. The company, as a part of the contractor oversight procedures will need regular monitoring of compliance to the aforesaid guidelines/requirements and ensure that these are met. Internal audits and follow up on corrective actions will also need to be undertaken to assess efficacy of the oversight system. SBE will also require the developer to ensure usage of relevant personal protective equipment, implement work permit and incident/accident recording/reporting systems etc.).</p>

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
	Document and communicate to all employees' conditions and terms of employment.	Applicable during construction and operation phase	<p>SBE would engage labourer through its contractors, however the same should be supervised so that the engagement of workers is in accordance to applicable rules and regulations.</p> <p>SBE and their contractor will ensure adequate provisions of facilities such as access to clean water, sanitary facilities and other necessary facilities at the labour accommodation and construction sites.</p>
	Practice non-discrimination and equal opportunity in making employment decisions	Applicable during construction phase	Need to be complied. Equal opportunity should be given to both men and women depending on their skills and capacity wages, work hours and other benefits should be as per the national labour and employment Laws.
	Provide a mechanism for workers to raise workplace concerns.	Applicable during construction and operation phase	<p>SBE 's Grievance Redressal Mechanism (GRM) should be in place under integrated management policy the same will be implemented at project level.</p> <p>This is applicable both during construction and operation phase and should be supervised by SBE. This is applicable both during construction and operation phase and should be supervised by SBE</p>
	Provide workers with a safe and healthy work environment, considering risks inherent to the particular project sector	Applicable during construction and operation phase	<p>SBE or their contractor should follow its EHS policy while operating onsite. In absence of EHS policy of contractor, EHS policies of SBE will be applicable.</p> <p>SBE or their contractor should appoint an EHS manager onsite, who has well defined roles and responsibilities at all the solar power site</p>
PS 3: Resource Efficiency & Pollution Prevention		PS-3 is applicable to projects resulting in increased levels of pollution and requires project to avoid, minimize, or reduce adverse impacts on human health and environment by	<p>During construction water is sourced through vendor and supplied by tanker and during operation phase water will be sourced through the same means. Drinking water needs during the construction phase will be met via local tankers/approve vendors. Drinking water supply will be met by local tankers/package water.</p> <p>In the event, project proponent installed bore well in future for ground water extraction in the operational phase,</p>

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
		<p>adopting pollution preventive and control technologies throughout the Project life cycle. The proposed project is a clean energy project and will not have major pollution sources associated with it. The construction works for the development of project will result in generation of wastes like wastewater, waste oil and construction debris. The operation phase will result in noise emissions and generation of minor quantities of waste such as transformer oil which may result in contamination of ground and nearby surface water.</p> <p>Hence PS 3 is applicable for the project.</p>	<p>permission from regulatory authority shall be obtained prior to extraction of ground water through borewell.</p> <p>The project is expected to contribute to significant GHG avoidance beginning in FY 2020 – 2021. No material impact on ambient air quality is expected on account of this project. However, temporary impacts on ambient air quality and noise levels may be expected during construction phase.</p> <p>However, temporary impacts on noise levels and shadow may be expected during operational stage. Project developer should implement measures to minimize noise and shadow in this stage.</p> <p>SBE should implement measures during construction for management of excavated earth and construction rubble, and minimization of fugitive dust emissions. Further, SBE should ensure through its contractors that other wastes (packing material, metal, debris, cement bags, drums/cardboards etc.) are collected, stored and disposed off to re-users or in appropriate authorized debris disposal areas.</p> <p>No material impact on surface or groundwater resources is expected on account of the project, except that the water sourcing requirement during the construction phase will need to safeguard the immediate and medium-term needs of water by the local communities. The sub-contractors should ensure that the water made available to workers and employees' meets national potable water quality norms.</p> <p>The project site if equipped with appropriate facilities for collection, treatment and disposal of sewage (septic tank and soak pit) which is used both during construction and operation phases should be provided.</p> <p>Further, SBE should ensure through its contractors that other wastes (packing material, metal, debris, cement bags, drums/cardboards etc.) are collected, stored and</p>

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
			<p>disposed to re-users or in appropriate authorized debris disposal areas.</p> <p>Limited concreting work is expected for structure foundations, sub-station, and transmission towers. Cement concrete mixers will be expected to be used at site since significant concreting work is not expected. Concreting and other construction activities including use of earth moving equipment and increased traffic for material movement is expected to result in increase in ambient noise levels. However, this increase is short term during construction stage only. The construction work will be carried out only during daytime and no noise generating equipment will be operated at night.</p>
	<p>The project proponent should ensure that adequate control techniques are provided to minimize emissions or achieve a pre-established performance level and minimize pollution from project activities. The client will avoid the release of pollutants or, when avoidance is not feasible, minimize and/or control the intensity and mass flow of their release.</p>	<p>During the construction phase, the vehicles involved for hauling of equipment's and materials to the project site may increase the pollution level and dust in the air.</p>	<p>Project developer should ensure water sprinkling as and when needed on the unpaved roads to reduce dust emission.</p> <p>All the project vehicles should have valid PUC.</p>
	<p>The client will implement technically and financially feasible and cost-effective measures for improving efficiency in its consumption of energy, water, as well as other resources and material inputs, with a focus on areas that are considered core business activities.</p>	<p>During construction and operation phase.</p>	<p>SBE should plan and implement pollution control measures. Practices like minimal release of waste, safe disposal of waste, wastewater management etc. should be considered in all phases of project life cycle.</p>
<p>PS 4: Community Health, Safety and Security</p>		<p>This Performance Standard is applicable to projects which entail potential risks and impacts to the health and safety of affected communities from project activities. The project will involve transportation of components such as mounting structures, electrical equipment's, solar</p>	<p>The Applicability will be limited to construction period with movement of heavy machinery / vehicles. Unskilled labour and security staff should be engaged from local community. SBE through its contractors will try to engage maximum workers from the neighbouring villages.</p> <p>During operation phase effects due to shadow flickering and noise generated due to wind turbines will pose an impact on the community if properly not mitigated.</p>

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
		<p>modules, which may pose safety risks to the local communities.</p> <p>While Hybrid power projects have a limited and controlled footprint major issue is related to glare or reflection. Considering scale of project substantial movement of heavy vehicles are envisaged.</p> <p>Impacts due to generation of noise and shadow – flicker effect will be assessed on habitations that are close to wind turbines.</p> <p><i>The PS 4 is therefore applicable for the project.</i></p>	<p>The construction phase will involve movement of vehicles on the approach road passing through villages on both the land parcels proposed. The traffic must be managed near villages/settlements/social infrastructure like school, etc. Further, at the project site, the company will need to exercise appropriate access control, barricading of excavated areas; safety signage; illumination and other measures to prevent the risk of accidents for public during construction and operation.</p> <p>It should be ensured by SBE that the subcontractors use vehicles having valid PUC certificate. The Proper signage's should be provided along the access road and project site indicating 'Construction in Process' and other safety alarm signs, preferably in local language.</p> <p>Also, the project envisages influx of labours from different nearby areas. As such community health and safety need to be taken care by the project developer and ensure safety measures to be put in place both during construction and operation phase of the project.</p>
	<p>Evaluation of risks and impacts of the project on health & safety of the affected community during the project lifecycle and establish preventive/mitigation measures to reduce/ minimize the impacts. Disclosure of action plans to affected community and the government agency.</p>	<p>During Construction Phase</p>	<p>The potential occupational hazards arising from the project activities and the impacts on health & safety of the affected community have been identified and assessed in Chapter 6 of ESIA.</p>
	<p>Design, construct, operate and decommission of Structural elements or components in accordance with good industrial practice to reduce impact on community health & safety.</p>	<p>During Construction Phase</p>	<p>An occupation health safety plan has been formulated (Chapter 7) of this report. All steps to reduce the impact on the health and safety of the community to minimal will be taken.</p>
	<p>Minimization of impacts on the health and safety of the community caused by natural hazards that could arise from the land use changes due to project activities.</p>	<p>During Construction Phase and Operational phase</p>	<p>A management plan (ESMP) has been formulated as part of ESIA process to address the issue.</p>

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
	Prevent or minimize the potentials for community exposure to communicable diseases during project activities	During Construction Phase	CSR Plan and activities has been provided as a part of ESIA.
PS 5: Land and Acquisition Involuntary Resettlement	<p>PS 5 is applicable when there is physical and/or economic displacement due to acquisition of land for the project.</p> <p>This PS does not apply to resettlement resulting from voluntary land transactions (i.e. market transactions in which the seller is not obliged to sell, and the buyer cannot resort to expropriation or other compulsory procedures if negotiation fails). The impacts arising from such transactions should be dealt with as under PS1, though sometimes, when risks are identified, the project proponent may decide to adhere to PS 5 requirement</p>	PS 5 is not applicable for this project.	<p>A total of 1100 Ha. of government land will be procured for the proposed 450 MW Hybrid power project. Out of that, 840 Ha. of government land will be leased for Solar from Rewari village of Seo taluk in Jaisalmer district and 260 Ha for Wind project in 6 villages of Sam block in Barmer District. The government revenue land will be allotted to SBE on sublease basis.</p> <p>The allotted land is barren and non-agricultural land and there is no habitation reported during consultations. There is no economic or physical displacement envisaged.</p> <p>Therefore, PS 5 is not applicable</p>
	Avoidance or at least minimization of involuntary resettlement by exploring alternative project designs balancing environmental, social and economic costs and benefits; and by acquiring land through negotiated Settlements.		No resettlement of people is required
	Compensation and benefits for displaced person as per Performance Standard	Compensation and benefits for displaced person as per Performance Standard.	No locals have been displaced.
	Disclosure of all relevant information and consultation with affected persons and communities in decision making process related to resettlement.		No resettlement has taken place due to the project activity.
	Establish a grievance mechanism to record and resolve communities' concerns and grievances about the relocation (if any) and compensation	During the construction and operation phase.	SBE have grievance redressal mechanism (GRM) at corporate level for implementation which will be implemented in this project.
PS 6: Biodiversity Conservation and Sustainable	As a matter of priority, the client should seek to avoid impacts on biodiversity and ecosystem services. When avoidance of impacts is not possible, measures	<ul style="list-style-type: none"> The project site is located within 30 km 	<p>Following actions are required to be taken</p> <ul style="list-style-type: none"> During Construction Phase

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
<p>Management of Living Natural Resources</p>	<p>to minimize impacts and restore biodiversity and ecosystem services should be implemented. Given the complexity in predicting project impacts on biodiversity and ecosystem services over the long term, the client should adopt a practice of adaptive management in which the implementation of mitigation and management measures are responsive to changing conditions and the results of monitoring throughout the project's lifecycle.</p>	<p>from Desert National Park.</p> <ul style="list-style-type: none"> The access road leading to site, does not pass through any reserve forest. The vegetation within 5 km radius of the project is mostly scrubland vegetation stony wasteland with huge stretches of barren land. Champion and Seth (1968) have classified these DNP forests as Tropical Dry Deciduous & Tropical Thorn Forests. No significant waterbody has been observed in the core or the buffer zone of this site as informed by the site surveyors. So aquatic ecology is not of importance for this project (no significant waterbodies was observed within 10 km radius from project site). However, as per 	<ul style="list-style-type: none"> Activities generating high noise shall be restricted to daytime and will be mitigated to minimize the noise level outside the site boundary. General awareness regarding flora plantation shall be enhanced through trainings, posters, etc. among the staff and labourers. Fencing along with proper lighting along the fencing must be constructed. Food waste shall be collected in a manner that it does not attract scavenging animals. Temporary barriers shall be installed on excavated areas. The footprints of the construction activities shall be kept to minimum so as to reduce disturbance to flora and fauna. If any nests of ground dwelling birds/ reptiles are found the Forest Department is to be notified so that the eggs of reptiles/ birds don't get displaced. During Operation Phase Fencing of appropriate height should be properly maintained along with lighting. Solar panels shall have an anti-reflective coating to minimize the light reflecting off the panels so that there is very less impact due to glare from the panels. Moreover, to minimize "Lake effect", visual frightening techniques may be considered to frighten any bird trying to land on panels and prevent birds from landing. As WLPA, 1972 any accidental death due to species listed in the schedule will lead to legal action against the responsible party irrespective of the location where the incident occurred.

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
		<p>toposheet and the drainage map of the site, few scattered water bodies are present in the buffer zone. There are no known rare, endangered or ecologically significant animal and plant species observed around the site periphery.</p> <ul style="list-style-type: none"> • During site visit Nil Gai, Chinkara and Deer were seen. As per the consultation with villagers no other wild species are observed in the area. • Also, no forest land is involved in this project. • Impact on avifauna is also expected due to the operation of WTG <p>PS -6 is applicable for the project.</p>	<ul style="list-style-type: none"> • The power pole configuration should be designed to minimize avian electrocution risk • Bird diverter should be installed in transmission line which the client will be complying with respect to the sensitive areas as suggested by the study undertaken by Bombay Natural History Society (BNHS) • Painting the tip of the blades for better visibility • Any dead animals/carcass shall be removed in time from the site so that it does not attract movement of raptors near to the WTGs • While planning project transmission lines, feasibility should be checked for avoiding water bodies crossings. This can be considered for water bodies that could be important when they turn into suitable habitats. • Native vegetation must be planted or allowed to grow around the wind-turbines, such that their canopy screens potential prey on the ground from raptors flying overhead. • Appropriate storm-water management measure shall be implemented to avoid creating ponds which can attract birds and bats for feeding or nesting in the windfarm area • Training of local staff and security guards for spotting of bird carcass and reporting the same. This will help to ensure the strategic actions when the species are spotted in the region. • Towers be regularly checked to avoid any nesting in any suitable gaps or platforms. • Flash lamps on the WTGs should be installed to reduce the collision risks during nights.

Title of Performance Standard	Performance Standard (PS) requirements in brief	Applicability to project (Compliance)	Requirements
PS 7: Indigenous Peoples	<p>Performance Standard 7 recognizes that Indigenous Peoples, as social groups with identities that are distinct from mainstream groups in national societies, are often among the most marginalized and vulnerable segments of the population. Indigenous Peoples are particularly vulnerable if their lands and resources are transformed, encroached upon, or significantly degraded. Their languages, cultures, religions, spiritual beliefs, and institutions may also come under threat. Therefore, Indigenous Peoples may be more vulnerable to the adverse impacts associated with project development than non-indigenous communities</p>	<i>PS 7 is not applicable</i>	<p>As per discussion with Sarpanch (village head) 100 -150 ST families living in surrounding villages of wind site & around 8-10 ST families are living in surrounding village of solar site. During site visit, Arcadis held consultations with ST population (locally known as Bhil tribe) residing in Reevasi & Devka village. The consultation revealed that local ST community are not socially secluded. They live with the mainstream population & have access to all common property resources. Also, as reported, no acquisition/procurement of ST land was planned/undertaken for the project. Considering the fact of not taking ST land in project, and no physical and or economical displacement of tribal populations is necessitated, therefore, no adverse negative impacts are envisaged due to project development.</p>
PS 8: Cultural Heritage	<p>Performance Standard 8 recognizes the importance of cultural heritage for current and future generations. Consistent with the Convention Concerning the Protection of the World Cultural and Natural Heritage, this Performance Standard aims to ensure that clients protect cultural heritage during their project activities. In addition, the requirements of this Performance Standard on a project's use of cultural heritage are based in part on standards set by the Convention on Biological Diversity.</p>	<i>PS8 is not applicable.</i>	<p>During site visit of Arcadis team, no notified Cultural Heritage site is recorded within the vicinity of the project. However, wind sites traverse through a number of religious common properties such as temples, mosques which though not of archaeological significance but nevertheless are significant to the local community. Kapuria math (temple) is located 15 km (approx.) from solar site.</p> <p>Based on the information available and observation made, PS 8 is not applicable at present.</p>

3.3. Categorization of Projects

3.3.1. Categorization of Projects as per IFC guideline

As part of its review of a project's expected social and environmental impacts, IFC uses a system of social and environmental categorization. This categorization is used to reflect the size of impacts understood as a result of the client's social and environmental assessment and to specify IFC's institutional requirements. The categories used by the IFC are:

- **Category A Projects:** Projects with potential significant adverse social or environmental risks or/and impacts that are diverse, irreversible or unprecedented.
- **Category B Projects:** Projects with potential limited adverse social or environmental risks or/and impacts that are few number, generally site-specific, largely reversible and readily addressed through mitigation measures.
- **Category C Projects:** Projects with minimal or no adverse social or environmental risks or/and impacts, including certain financial intermediary (FI) projects with minimal or no adverse risks.
- **Category FI Projects:** Business activities involving investments in financial institutions (FIs) or through delivery mechanisms involving financial intermediation.

IFC therefore categorizes the project primarily according to the significance and nature of its impacts. IFC defines the project's area of influence as the primary project site(s) and related facilities that the client (including its contractors) develops or controls associated facilities that are not funded as part of the project (funding may be provided separately by a client or a third party including the government), and whose viability and existence depend exclusively on the project and whose goods or services are essential for the successful operation of the project; areas potentially impacted by cumulative impacts from further planned development of the project; and areas potentially affected by impacts from unplanned but predictable developments caused by the project that may occur later or at a different location. The area of influence does not include potential impacts that would occur without the project or independently of the project.

With respect to the intensity of impacts due to project activities on environment, resources, biodiversity, labors and community, the project can be categorized as **Category B** (as per IFCs categorization of projects), which specifies that this project is expected to have limited adverse environment and social impacts, which can be mitigated by adopting suitable mitigating measures.

3.4. World Bank Group's EHS Guidelines and applicable sector guidelines

IFC has issued Environmental, Health, and Safety Guidelines in 2007. The key requirements stated in the EHS guidelines have been discussed in **Table** .

Table 7: World Bank Group's EHS Guidelines and applicable sector guidelines

S. N	Relevant Requirements as Stated in EHS Guidelines	Section in ESIA Report where Addressed
I	ENVIRONMENTAL ATTRIBUTES	
i	Air Emissions and Ambient Air Quality	Please refer the section on ambient air quality in Sec 4.3.1 and 6.2.1
ii	Energy Conservation	Please refer the section on Resource Efficiency & Pollution Prevention in sec. 3.2
iii	Wastewater and Ambient Water Quality	Segregating or diverting clean water runoff to prevent it mixing with water containing high solids content, to minimize the volume of water to be treated prior to release. Refer mitigation measures for water under Table 7.1 and under section 6.2.5
iv	Water Conservation	Refer mitigation measures in Section 6.2.5 and Table 7.1
v	Hazardous Materials Management	Refer mitigation measures in Section 6.2.7 and Table 7.1
vi	Waste Management	Refer mitigation measures in Section 6.2.7 and Table 7.1
vii	Noise	Refer mitigation measures in Section 6.2.3 and Table 7.1
viii	Contaminated Land	Refer mitigation measures in Section 6.2.2 and Table 7.1
II	OCCUPATIONAL HEALTH AND SAFETY	
i	General Facility Design and Operation	Please refer the section on Project Design and Technology in Sec.2.4
ii	Communication and Training	This has been provided in Section 7.1.1 as well as in Section 7.5.2 and 7.5.3.
iii	Physical/Chemical/Biological Hazards	Discussed in Section 6.2.10
iv	Personal Protective Equipment (PPE)	The logistic arrangement for the workers w.r.t. housing space, drinking water, food has been described in section 2.6.5 and 6.2.10. The Occupational health and safety aspects has been mentioned in sec. 6.2.10 and Table 7.1
v	Monitoring	Please refer Section 7.2
III	COMMUNITY HEALTH AND SAFETY	
i	Water Quality and Availability	Please refer Section 4.2.5 and 4.2.6
ii	Structural Safety of Project Infrastructure	Detailed in Section 2.4
iii	Life and Fire Safety (L&FS)	Discussed in Section 6.2.10 and in section 7.5.1
iv	Traffic Safety	Provided in Table 7.1 as well as in Sec. 7.5.8 Providing adequate road drainage based on road width, surface material, compaction, and maintenance. Vehicles should have PUC certificate. Refer mitigation measures for Transport and Traffic
v	Transport of Hazardous Materials	Provided in Table 7.1

vi	Disease Prevention	Provided in Table 7.1
vii	Emergency Preparedness and Response	Detailed in Section 7.5.1
IV CONSTRUCTION AND DECOMMISSIONING		
i	Environment	Baseline environmental conditions have been described in chapter 4.
ii	Occupational Health and Safety	The logistic arrangement for the workers w.r.t housing space, drinking water, food has been described in Sec 2.6.5. The Occupational health and safety aspects has been mentioned in sec. 6.2.10. Proper training should be given to workers working on site. Personal protective gears should also be provided to the workers.
iii	Community Health and Safety	Measures to be taken to address the Community, Health and Safety issue has been addressed in Table 7.1 and the impacts during construction phase is given in Sec. 6.2.10 and management plan given in sec. 7.5.2, 7.5.3 and 7.5.6 Preliminary modelling should be carried out to determine whether more detailed investigation is warranted. Keep stationary source of noise such as DG sets (currently used only for back up) at farthest point from the settlements. During construction phase, safety flags on the roadsides should be displayed during work in progress. The solar project site location should also be fenced/ to prohibit public access to solar power. Follow periodic Grievance Redressal Mechanism framed for site and timely register complaints if any received by locals, investigate and resolve in the best possible manner.

3.5. Equator Principles

The Equator Principles comprise of a group of Ten principles adopted by the Equator Principle Financial Institutions (EPFIs) in order to ensure that the projects funded by them are developed in a manner that is socially responsible and reflect sound environmental management practices. The applicability of each of the principles with respect to project is discussed below:

Table 8: Compliance to Equator Principles

Equator Principle	Applicability	Project Information/Application
Principle 1: Review and Categorisation	As the project is seeking financing from EPFIs, the project has to be categorized based on the magnitude of its potential impacts and risks in accordance with the environmental and social screening criteria of IFC (Exhibit I)	Based on the IFC environmental and social screening criteria the Hybrid power project is identified as a “Category B” project with potential limited adverse social or environmental impacts that are few in number, generally site-specific, largely reversible and can be readily addressed through mitigation measures
Principle 2: Social and Environmental Assessment	An Environmental and Social Assessment has to be carried out for the project that addresses relevant social and environmental impacts and risks of the project (illustrative list of issues as found in Exhibit II) and also propose mitigation and management measures relevant and appropriate to the nature and scale of the project.	This report presents the Environmental and Social Impacts Assessment (ESIA) carried out for the project. Land lease has been completed by SBE prior to the development of this project the land parcels were devoid of settlements (as reported) hence does not trigger the requirement of Resettlement and Rehabilitation.
Principle 3: Applicable Social and Environmental Standards	This Principle requires the Environment and Social Assessment to refer to the applicable IFC Performance Standards and the then applicable Industry Specific EHS Guidelines including the project’s overall compliance with, or justified deviation from, the respective Performance Standards and EHS Guidelines.	The ESIA report has been prepared including the requirements of IFC performance standards and EHS guidelines.
Principle 4: Action Plan and Management System	The action plan will describe and priorities the actions needed to implement mitigation measures, corrective actions and monitoring measures necessary to manage the impacts and risks identified in the Assessment	The management plan is given in Chapters 7 of this ESIA report.
Principle 5: Consultation and Disclosure	The project affected communities are required to be consulted in a structured and culturally appropriate manner.	Since this is entirely Revenue Land, SBE is required to make an application to RRECL which then recommends for allotment of the said project land to District Collector for allotment. After obtaining necessary NOCs and approvals from relevant govt. departments, allotment order is issued by District collector and lease deed is signed. At present, owner is Govt. of Rajasthan and Application has been made to RREC for allotment of land.
Principle 6: Grievance Mechanism	Proponent is required to establish a grievance mechanism as part of the management system	Grievance redress procedure has been developed by SBE and the same will be implemented at project level. Proper complaints register should

Equator Principle	Applicability	Project Information/Application
		be maintained onsite. This is applicable during both construction and operation phase.
Principle 7: Independent review	An independent social or environmental expert, not directly associated with SBE is required to review the Assessment, action plans and consultation process documentation to assist EPFI's due diligence and assess Equator Principles compliance.	Arcadis has been appointed as third-party expert to assess the environment and social impact of the project as per IFC safeguards through ESIA study and ESDD study. One ESDD for construction and operation phase each will be conducted
Principle 8: Covenants	The covenants would be a part of the contract documents between SBE and financing agency as well as contractors and technology suppliers	E&S Covenants should be embedded within the contracts drawn between the contractors and technology providers and waste handlers. Periodic reporting should be done
Principle 9: Independent Monitoring and Reporting	EPFIs will, for all Category A Projects, and as appropriate, for Category B projects, require appointment of an independent environmental and/or social expert, or require that the borrower retain qualified and experienced external experts to verify its monitoring information which would be shared with EPFIs.	Arcadis has been appointed as third-party expert to assess the environment and social impact of the project as per IFC safeguards as ESIA study. The requirements of the principle are also met by adhering to requirements of PS 1
Principle 10: Reporting and Transparency	This should be prepared by the EPFI	Based on the audit and monitoring reports submitted by independent agencies the EPFI will report the findings publicly at least once a year

4. DESCRIPTION OF ENVIRONMENT

This chapter describes the existing environmental settings of the project area and its immediate surroundings. This includes physical environment comprising air, water and noise components, biological environment and socio-economic environment. Attributes of the physical environment such as air, water, soil and noise quality in the block and surrounding area were assessed primarily through monitoring and analysis of samples collected from the area.

Information on geology, hydrology, prevailing natural hazards such as floods, and earthquakes have been collected from literature reviews and authenticated information made available by government departments. Primary surveys were carried out to understand and record the biological environment prevailing in the area and the same was verified by the forest officials and against published information and literature. The socioeconomic environment has been studied through consultations with various stakeholders within the site. Additionally, socioeconomic data have been obtained from the Census of India, 2011 report.

4.1. Study Area

To understand and assess the environmental and social risks associated with the project, the study area was divided into core area (5 km around the project site) and buffer area (10 km around the project site).

While selecting locations for primary monitoring of air, noise and water emphasis is given to collect the representative baseline data. Monitoring stations for air and noise has been selected depending upon its proximity to settlements as well as approach roads and availability of power for carrying out monitoring. Three monitoring locations for air and noise each, one monitoring location for surface water and groundwater each has been selected at project site and nearby settlements.

4.2. Baseline Conditions

4.2.1. Climate and Meteorological Conditions

Barmer:

As per CGWB the district experiences arid to semi-arid type of climate. Mean annual rainfall (1971-2012) of the district is 374 mm whereas normal rainfall (1901-1970) is lower than average rainfall and is placed at 314 mm. Rainy days are limited to maximum 15 in a year. Almost 80% of the total annual rainfall is received during the southwest monsoon, which enters the district in the first week of July and withdraws in the mid of September. Probability of annual rainfall exceeding 650 mm is only 10%. However, there is 90% probability that the annual rainfall will be more than 190 mm. The probability of occurrence of mean annual rainfall is 45%. Drought analysis based on agriculture criteria indicates that the district is prone to mild and normal type of droughts. Occurrence of severe and very severe type of drought is very rare. As the district lies in the desert area, extremes of heat in summer and cold in winter are the characteristic of the desert. Both day and night temperatures increase gradually and reach their maximum in May and June respectively. The temperature varies from 49°C in summer to 1°C in winter.

Atmosphere is generally dry except during the monsoon period. Humidity is the highest in August with mean daily relative humidity at 81%. The annual maximum potential evapotranspiration in the district is quite high and is highest (264.7 mm) in the month of May and lowest (76.5 mm) in the month of December.

Recorded high temperatures ranging from 41°C and lowest temperature 9°C.


Table 9: Climate Data for Barmer (1901-2000)

Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Highest °C	25.0	27.08	33.04	38.4	41.04	40.01	36.00	33.07	35.00	36.00	31.05	26.08
Lowest °C	9.06	11.08	17.02	22.7	26.08	28.02	26.08	25.03	24.01	19.09	14.05	10.08
Average Rainfall(mm) monthly total	10.02	4.08	3.09	5.01	66.01	35.01	120.8	128.09	57.06	8.01	2.06	1.06

Source: India Meteorological Department -Climatological table & CWWB District groundwater brochure Barmer,2013

The monthly mean rainfall distribution of Barmer district for the ten-year period (1901-2000) has been represented below:

Figure 4-1: Monthly mean rainfall distribution of Barmer



Jaisalmer:

As per CGWB the district experiences arid type of climate. Normal rainfall in the district during the period 1951-2000 is 181mm. Mean annual rainfall during the period 2001 – 2011 has been higher than the normal rainfall. Almost 90% of the total annual rainfall is received during the southwest monsoon, which enters the district in the first week of July and withdraws in the mid of September. As the district lies in the desert area, extremes of heat in summer and cold in winter are the characteristic of the desert. Both day and night temperatures increase gradually and reach their maximum in May and June. The temperature varies from 48 degrees in summer to 2 degree in winter. Atmosphere is generally dry except during the monsoon period. The humidity is highest in August with mean daily relative humidity is 43%. The annual maximum potential evapotranspiration in the district is 1850 mm and it is highest in the month of June and lowest in the month of December.

Table 10: Climate Data for Jaisalmer (1901-2000)


Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Highest °C	23.7	27.1	32.6	38.2	41.6	40.8	37.7	36	36.4	36.1	31	25.5

Lowest °C	7.6	10.5	32.6	38.2	41.6	40.8	37.7	36	36.4	36.1	31	25.5
Average rainfall (mm) monthly total	1.5	3	2.7	21	8.9	15.1	60.1	75.8	17.6	2.4	1.5	2.4

Source: India Meteorological Department -Climatological table & CWWB District groundwater brochure Jaisalmer,2013

The monthly mean rainfall distribution of Jaisalmer district for the ten-year period (1901-2000) has been presented in below.

Figure 4-2: Monthly mean rainfall distribution of Jaisalmer




India's Solar Radiation Profile

Selection of project location for solar energy project is very critical with solar intensity playing a key role. Rajasthan receives considerable solar radiation intensity in India. In addition, the average rainfall is very low in the state.

Indian solar radiation map of India, which is based on the measured data of Nation Renewable Energy Laboratory (NREL) and satellite data, indicates that Rajasthan state receives good amount of solar radiation. Rajasthan receives around 5.5 - 6 kWh/sq. m/day.

Figure 4-3: Indian Solar Resources



Source: National Renewable Energy Laboratory

4.2.2. Topography

The project site is spread across an open area with mild undulation. Erection of solar panels and WTG structures would not require to be of varying pole height for mounting solar panels as the land is flat and not a large number of slopes exists. Hence, the installation is easy and reduces the cost of technical modifications required to adjust for undulations at the ground. The highest and lowest elevation is 266 m to 220m within the study area. There were no agricultural activities observed in the land parcels of the project site. The digital elevation map is depicted in **Figure 4-4**.

Figure 4-4: Topography of the Project Site




Barmer District Site photos



Jaisalmer District Site photos


Figure 4-5: Digital Elevation Map



4.2.3. Land use Analysis

The land-use and land-cover of the study area (20 km including solar and wind) has been interpreted from visual interpretation, google earth satellite imagery of the area, and subsequently by ground truthing verification during site visit has been conducted. The land use within study area represent road transportation (0.56%) ,Agricultural land (18.26 %),open scrub land (73.95 %), seasonal water bodies (0.21 %), settlement (0.82%) and stony gravel waste (6.19%) .The land use map of the study area is depicted in **Figure 4-6**.

Figure 4-6: Land Use Map



4.2.4. Drainage

Barmer

As per CGWB Barmer district forms part of Great Thar Desert of Rajasthan. In this arid region, there are sand dunes, alluvial areas dotted with few hillocks and hill chains scattered in the area. In the eastern part of the district, the area between Bilara and Barmer is covered by alluvium deposited due to fluvial action of Luni river system.

Barmer district falls in the Luni & Barmer Basins. Major River of the district is Luni, which flows in ENE – WSW direction. It enters Barmer district near village Jhak in Bilara tehsil and leaves the district near village Dhundhara. Total length of the Luni River in Barmer district is 125 km. Channel pattern of Luni is dendritic to sub-parallel. However, in major part of the district, the drainage is essentially ephemeral and internal. Important tributaries to the Luni river are Mithri and Bandi. Other streams in the district are Jojri, Golasmi, Guniamata and Bastua, which are all ephemeral.


Jaisalmer

As per CGWB report, Jaisalmer district is a part of the ‘Great Thar Desert’. The terrain around Jaisalmer town, within a radius of about 60 km is stony and rocky. The area is barren, undulating with its famous

sand dunes. There are no rivers worth the name in the area nor are there any perennial streams in the area. Small nallas are purely seasonal and ephemeral with the result that there is lack of effective discharge in the event of heavy precipitation.

The drainage map of the study area is depicted in **Figure 4-7**.

Figure 4-7: Drainage Map




4.2.5. Hydrogeology

Barmer:

Ground water occurs under unconfined to semi-confined conditions in rocks of Delhi Super Group, Barmer sandstone, Bilara limestone, Nagaur sandstone, Lathi sandstone and unconsolidated sediments (valley fills and alluvium). These form the chief source of ground water in the district. Confined condition is also met sometimes at deeper levels in the northwestern part of the district.

Hydrogeological map of the district is presented in **Figure4-8**:

Figure 4-8: Hydrogeology Map of Barmer district




Jaisalmer:

Hydrogeological formations forming aquifer in the district vary from Proterozoic to Quaternary in age. The main water bearing formations in the district are granites, Lathi sandstone, Tertiary sandstone and Quaternary alluvium. In Quaternary alluvium, ground water occurs under semi-confined to unconfined conditions, in semi- consolidated Tertiary and Mesozoic formations, it occurs under unconfined to confined conditions and in weathered and fractured zones in hard rocks, it occurs under phreatic conditions.

Hydrogeological map of the district is presented in **Figure4-9:**

Figure 4-9: Hydrogeology Map of Jaisalmer district



4.2.6. Ground Water Resources

Barmer

As per CGWB report ground water resources have been estimated jointly by Central Ground Water Board and State Ground Water Department as per the norms recommended by GEC' 97 as of 2009. Annual replenishable ground water resource of the district has been estimated as 420.8565 mcm and net annual ground water availability as 388.8043 mcm. Gross ground water draft for all uses is estimated as 809.7057 mcm and over all stage of development is 208%.

Jaisalmer

Central Ground Water Board and Rajasthan Ground Water Department (RGWD) have jointly estimated the ground water resources of Jaisalmer district (as on 2009) based on GEC-97 methodology. Ground Water Resource estimation has been carried out for 12090 sq. km. area excluding saline area. The total annually replenishable resource of the district has been assessed to be 72.1216 MCM and net annual ground water availability has been estimated to be 68.3625 MCM. Gross annual ground water draft for all uses has been estimated to be 94.5896 MCM with stage of ground water development at 138%.

As per the categorization by CGWB the Blocks where the project sites are located falls under over exploited category.

Depth to water level


Barmer

During pre-monsoon (May 2011) depth to water level in the district generally ranges from less than 1m to more than 100 m below ground level (mbgl). It varied from and 0.01 to 82.51 m. Depth to water level in major part of the district varied from 20 m to more than 40 m bgl except for parts of Luni, Mandore, Bilara, Osian, Bhopalgarh and Bap blocks where shallower water levels upto 20 m bgl were observed (**Figure 4-10**).

During post monsoon (November 2011), depth to water level varied from 0.01 to 114.9 m bgl. Shallow water level upto 20 m bgl has been observed in western half of Bap, central part of Osian, southern


part of Balesar, southern and eastern parts of Mandore and major parts of Luni and Bilara blocks .Water levels in the remaining areas have been found to be 20 to more than 40 m bgl.(**Figure 4-11**).

Figure 4-10: Depth to water level during pre-monsoon -Barmer



Source: District Groundwater brochure, Barmer district, CGWB, 2013

Figure 4-11: Depth to water level during post-monsoon -Barmer




Source: District Groundwater brochure, Barmer district, CGWB, 2013

Jaisalmer

During pre-monsoon (May 2011), the depth to water level in the district varied largely from 1.85 to 108.86 mbgl. Over a major part of the district, water levels are deeper (more than 20 m). Water levels more than 40 m were recorded in northern and southern parts of the district. Shallow water levels less than 10 m have been registered in localized pockets in the district **Figure 4-12**).


During post-monsoon period (November 2011), the depth to water level varied from 1.24 to 116.1 mbgl. Wells in major parts of Jaisalmer and Sam blocks registered water levels deeper than 40 mbgl (Figure 4-13).

Figure 4-12: Depth to water level during pre-monsoon -Jaisalmer



Source: District Groundwater brochure, Barmer district, CGWB, 2013

Figure 4-13: Depth to water level during post-monsoon -Jaisalmer



Source: District Groundwater brochure, Barmer district, CGWB, 2013

4.2.7. Seismic Hazard

The project site is located in seismic zones III as per the seismic zoning map of India. Accordingly, implying that potential threats of damage due to earthquake is moderately active. The seismic zoning map of India has been shown in **Figure 4-14**.

Figure 4-14: Seismic Map




Source: www.mapsofindia.com/maps/india/seismiczone.htm

4.2.8. Wind Hazard

The project site is located in High Damage Risk Zone as per the wind hazard map of India. Accordingly, implying that potential threats of damage due to earthquake is high. The wind hazard map of India has been shown in **Figure 4-15**.


Figure 4-15: Wind Hazard Map



4.2.9.Flood Hazard

As per the flood hazard map of India, the project site is not located in area liable to flood. The flood hazard map of India depicted in **Figure 4-16**.

Figure 4-16: Flood Hazard Map



4.3. Environmental Monitoring

Environmental quality monitoring was conducted on 25th to 27th June 2020. Details of environmental quality monitoring location coordinates are depicted below in **Monitoring Location Map**.

4.3.1. Ambient Air Quality

Ambient air monitoring was carried out at three locations (24-hourly sampling for particulate & gaseous pollutants and 8-hourly sampling for CO). The monitoring was conducted on 25th to 27th June 2020. Sampling and analysis was done as per the guidelines prescribed by CPCB /IS-5182. Monitoring stations were chosen based on their proximity to sensitive receivers, settlements, topography, and predominant wind direction. The details of the monitoring locations are depicted below in **Table**.


Table 11: Ambient Air Quality Monitoring Results


Sl. No.	Parameter	Unit	Locations			NAAQS Limit
			Devaka village (AAQ-1)	Harwa village (AAQ-2)	Reevari village (AAQ-3)	
1	Particulate Matter (PM ₁₀)	µg/m ³	39.2	44.5	45.3	<100
2	Particulate Matter (PM _{2.5})	µg/m ³	20.4	22.8	23.7	<60
3	Sulphur Dioxide (SO ₂)	µg/m ³	5.2	6.4	5.8	<80
4	Oxide of Nitrogen (as NO ₂)	µg/m ³	14.4	18.1	16.6	<80
5	Carbon Monoxide (CO)	µg/m ³	<1.00	<1.00	<1.00	<2.00

Interpretation of Air Quality Results

- Interpretation of Air Quality Results Concentrations of all the ambient air quality parameters (PM₁₀, PM_{2.5}, SO₂, NO₂ and CO) at all three monitoring stations were observed to be well within the NAAQS 2009 prescribed standards.
- Particulate Matter (PM₁₀) Concentration monitored was in the range of 39.2 µg/m³ to 45.3 µg/m³ i.e. well within the NAAQS permissible limit of 60 µg/m³. PM_{2.5}, Sulphur dioxide, Nitrogen Oxide and Carbon monoxide too were recorded well below the CPCB permissible limits as depicted in Table 4-3.
- No significant impact on the ambient air is anticipated at this stage.

Figure 4-17: AAQ Monitoring Results Graphical Interpretation





4.3.2. Ambient Noise Quality

The ambient noise monitoring was conducted at three locations in the study area. The noise monitoring network was established based on the understanding of the project activities and professional judgment.

Sound pressure level (SPL) measurements in dB(A) were recorded for every hour continuously for 24 hours for the aforesaid monitoring stations and equivalent noise levels in the form of Leq day and Leq night. The results so obtained were compared with the standard specified in Noise Pollution (Regulation and Control) Rules, 2000. The summary of noise quality results is presented in Error! Reference source not found. below.

Table 12: Noise Quality Monitoring Results


Sl. no.	Parameter	Unit	Results		
			Devaka village (ANQ-1)	Harwa Village (ANQ-2)	Reevadi Nagar (ANQ-3)
1	Leq Day	dB(A)	49	50.3	50.6

Sl. no.	Parameter	Unit	Results		
			Devaka village (ANQ-1)	Harwa Village (ANQ-2)	Reevadi Nagar (ANQ-3)
2	Leq Night	dB(A)	37.9	38.1	37.8
CPCB standard (day-Night) dB(A)			55-45	55-45	55-45

Interpretation of Noise Quality Results

On comparison of day and night equivalent values with Ambient Noise Quality Standards in respect to Residential areas, the obtained values are well within the prescribed standards of CPCB for residential area.

Figure 4-18: ANQ Monitoring Results Graphical Interpretation



4.3.3. Surface water Quality

Results of physio chemical analysis of surface water sample collected from one location namely Reevadi village (SW1) was studied to have an idea of the quality of surface water in the study area. Analysis were done as per IS: 2296 Class C Specifications and results are presented in the **Table 13**,

Table 13: Surface water Analysis Results

S.No	Parameters/Characteristic	Test Method	Units	Test Results	IS: 2296 Class C Specifications
1.	pH at 25 deg C	IS:3025 part 11 1983	-	7.78	6.5 – 8.5
2.	Colour	IS: 3025 Part 4 1983	Hazen	40	300
3.	Conductivity at 25 deg C	IS: 3025 Part 14 1984	mS/cm	234	--
4.	Temperature at Site	IS: 3025 Part 38 1989	° C	26.1	--
5.	Turbidity	IS: 3025 Part 10 1984	NTU	4.30	--
6.	Dissolved Oxygen	IS: 3025 Part 38 1989	mg/L	4.0	4 min
7.	Chemical Oxygen Demand	IS: 3025 Part 58 2006	mg/L	20	--
8.	Total Suspended Solids	IS: 3025 Part 17 1984	mg/L	2.4	--
9.	Total Dissolved Solids	IS: 3025 Part 16 1984	mg/L	144	1500
10.	BOD (3 days at 27°C)	IS: 3025 Part 44 1993	mg/L	05	< 3.0
11.	Total Hardness as CaCO ₃	IS: 3025 Part 21 2009	mg/L	40	--
12.	Chloride as Cl	IS: 3025 Part 32 1988	mg/L	25	600
13.	Fluorides as F ⁻	IS: 3025 Part 60 2008	mg/L	0.20	1.5
14.	Sulphate as SO ₄ ²⁻	IS: 3025 Part 24 1986	mg/L	24.7	400
15.	Alkalinity	IS: 3025 Part 23 1986	mg/L	50	--
16.	Total Nitrogen	IS: 3025 Part 34 1988	mg/L	1.6	--

S.No	Parameters/Characteristic	Test Method	Units	Test Results	IS: 2296 Class C Specifications
17.	Cyanides as CN	IS: 3025 Part 27 1986	mg/L	<0.001	0.05
18.	Calcium as Ca	IS: 3025 Part 40 1991	mg/L	8.0	--
19.	Magnesium as Mg	IS: 3025 Part 46 1994	mg/L	4.8	--
20.	Sodium as Na	IS: 3025 Part 45 1993	mg/L	32.6	--
21.	Potassium as K	IS: 3025 Part 45 1993	mg/L	1.5	--
22.	Iron as Fe	IS: 3025 Part 53 2003	mg/L	0.08	50
23.	Lead as Pb	IS 3025 Part 47 1994	mg/L	<0.001	0.1
24.	Copper as Cu	IS 3025 Part 42 1992	mg/L	0.010	1.5
25.	Arsenic as As	IS: 3025 Part 37 1988	mg/L	<0.02	0.2
26.	Phenolics as C ₆ H ₅ OH	IS: 3025 Part 43 1992	mg/L	<0.001	0.005
27.	Boron	IS 3025 Part 57 2005	mg/L	<0.001	--
28.	Total Chromium as Cr	IS 3025 Part 52 2003	mg/L	<0.001	0.05
29.	Zinc as Zn	IS 3025 Part 49 1994	mg/L	0.024	15
30.	Total Phosphorus	IS 3025 Part 31 1988	mg/L	<0.02	--
31.	Mercury as Hg	IS 3025 Part 48 1994	mg/L	<0.001	--
32.	Oil and grease	IS 3025 Part 39 1991	mg/L	<1.0	0.1
33.	Coli form Organisms	IS: 1622:1981 RA 1996	MPN/100 ml	260	Should not exceed 5000
34.	Faecal Coliform	IS: 1622:1981 RA 1996	MPN/100 ml	98	--
35.	Pesticides	USEPA	µg/L	<0.001	<0.001

Interpretation of Surface Water Quality Results:

Except for dissolved oxygen (just meets the minimum limits) and BOD, all the other above tested parameters meet the IS: 2296 Class C specifications.

4.3.4. Groundwater Quality

Results of physio chemical analysis of ground water samples from bore well at Harwa village (GW1) was studied to have an idea of the quality of ground water in the study area. Analysis were done as per standard methods prescribed by IS: 10500:2012 specifications and results are presented in the **Table**

Table 14: Groundwater Analysis Results

Sr. No	Parameters	Test Method	Units	Test Results	Drinking Water Limits As per IS: 10500:2012	
					Acceptable Limits	Permissible Limits
1.	pH at 25°C	IS:3025 part 11 1983	--	7.52	6.50 - 8.50	--
2.	Turbidity	IS: 3025 Part 10 1984	NTU	<1.0	1	5
3.	Conductivity at 25°C	IS: 3025 Part 14 1984	µMho/cm	1646	--	--
4.	Total Suspended Solids	IS: 3025 Part 17 1984	mg/L	<1.0	--	--
5.	Total Dissolved Solids	IS: 3025 Part 16 1984	mg/L	1048	500	2000
6.	Colour	IS: 3025 Part 4 1983	Hazen	<01	5.00	15.00
7.	Taste	IS:3025 part 08 1984	-	Agreeable	Agreeable	--
8.	Odour	IS:3025 part 05 1983	-	Agreeable	Agreeable	--
CHEMICAL PARAMETERS						
9.	Total Alkalinity as CaCO ₃	IS: 3025 Part 23 1986	mg/L	280	200	600
10.	Chlorides as Cl ⁻	IS: 3025 Part 32 1988	mg/L	200	250	1000
11.	Sulphates as SO ₄ ⁻²	IS: 3025 Part 24 1986	mg/L	227	200	400
12.	Nitrates as NO ₃	IS: 3025 Part 34 1988	mg/L	15.1	45	--


Sr. No	Parameters	Test Method	Units	Test Results	Drinking Water Limits As per IS: 10500:2012	
					Acceptable Limits	Permissible Limits
13.	Phosphates as PO ₄	IS: 3025 Part 31 1988	mg/L	<0.02	--	--
14.	Total Hardness as CaCO ₃	IS: 3025 Part 21 2009	mg/L	530	200	600
15.	Calcium as Ca	IS: 3025 Part 40 2009	mg/L	120	75	200
16.	Magnesium as Mg	IS: 3025 Part 46 1994	mg/L	55.2	30	100
17.	Sodium as Na	IS: 3025 Part 45 1993	mg/L	129.7	--	--
18.	Potassium as K	IS: 3025 Part 45 1993	mg/L	3.5	--	--
19.	Fluoride as F ⁻	IS: 3025 Part 60 1993	mg/L	0.90	1	1.5
20.	Iron as Fe	IS: 3025 Part 53 2003	mg/L	0.16	0.3	--
21.	Phenolic Compounds	IS:3025 Part 43 1985	mg/L	<0.001	0.001	0.002
22.	Cyanide as CN ⁻	IS 3025 Part 27 1986	mg/L	<0.001	0.05	--
23.	Cadmium as Cd	IS 3025 Part 41 1992	mg/L	<0.001	0.003	--
24.	Total Chromium as Cr	IS 3025 Part 52 2003	mg/L	<0.001	0.05	--
25.	Lead as Pb	IS 3025 Part 47 1994	mg/L	<0.02	0.01	--
26.	Arsenic as As	IS: 3025 Part 37 1988	mg/L	<0.01	0.01	--
27.	Zinc as Zn	IS 3025 Part 49 1994	mg/L	0.042	5	15
28.	Manganese as Mn	IS: 3025 Part 59 2006	mg/L	<0.001	0.1	0.3
29.	Copper as Cu	IS 3025 Part 42 1992	mg/L	0.021	0.05	1.5
30.	Nickel as Ni	IS 3025 Part 54 2003	mg/L	<0.001	0.02	--

Sr. No	Parameters	Test Method	Units	Test Results	Drinking Water Limits As per IS: 10500:2012	
					Acceptable Limits	Permissible Limits
31.	Boron	IS 3025 Part 57 2005	mg/L	0.010	0.5	1.0
32.	Anionic Detergents	IS 13428 Annex K	mg/L	<0.001	0.20	1.0
33.	Mineral Oil	APHA 23 rd Edition 2012	mg/L	<0.001	0.5	--
34.	Aluminium as Al	IS 3025 Part 55 2003	mg/L	<0.001	0.003	0.2
35.	Mercury as Hg	IS 3025 Part 48 1994	mg/L	<0.0002	0.001	--
36.	Pesticides	USEPA	µg/L	<0.001	--	--

Interpretation of Ground Water Quality Results:

- The above tested parameters Village (GW1) sample exceeds the acceptable limit of following parameters: Total Dissolved Solids (1048 mg/l), Total Alkalinity as CaCO₃ (280 mg/l), Sulphates as SO₄-2 (227 mg/l). Total Hardness as CaCO₃ (530 mg/l), Calcium as Ca (120 mg/l), Magnesium as Mg (55.2 mg/l)
- The tested water shows the characteristics of hard water which is caused by a high mineral content.
- Rest all tested parameters meet the Drinking Water Limits as per IS: 10500:2012

Figure 4-19: Environmental Quality Monitoring Location Map



4.4. Ecological Environment

Reconnaissance survey was conducted along with personnel from Project developer with the aim to assess the existing ecological resources on or near the project site. The main objective of the survey was to collect ground data on flora and fauna of the area. Published secondary information was also collected on the same from government officials, journals and residents of the area.

This information will further enable to gauge potential ecological impacts that can be generated from the project activities. Understanding the significant risks and impacts is important to undertake mitigation measures & suggest changes, if the associated risks are huge. Such mitigation measures will help to reduce the impacts and develop ecological monitoring parameters. The project site comprises of dry and barren land with very little vegetation.

Main objectives for Ecological surveys:

Flora

- Identification of floral species, endangered as well as endemic species (if any), important habitats, forests area within the study area;
- Surveys to identify local, widespread floral species, any endangered or endemic species and protected species in the study area;
- Identification of any notified area under international conventions, national or local legislation for their ecological, landscape, cultural or other related values within the study site.

Fauna

- Identification of fauna (terrestrial, aerial and aquatic) by direct sighting and through secondary means like, nests, roosts, pug marks, droppings, etc.
- Identification and classification of species recognized as critically endangered, endangered, threatened etc. as per IUCN Red list and scheduled species as per WPA (1972).
- Identification of areas important for breeding, foraging, nesting, resting or over wintering areas include migratory corridors/ avian migratory routes.
- Identification and assessment of aquatic fauna near the study area.

4.4.1. Methodologies for Ecological Surveys

Desktop Review

A desktop review (published document) was conducted to determine the land use and land cover, vegetation type (Champion and Seth, 1968), floral and faunal assemblage in the study area through secondary data.

In order to provide representative ecological status for the project a study area is defined for ecological study. As this is a hybrid project, solar project site has no moving part or emission, most of the project related impact (if any) will be confined to the project site only and access roads. Therefore, project development area and 100m around the project site was considered as the "high risk zone" or "core study area", and 10-km radius surrounding the project site is considered as the "buffer zone" or the zone of influence of the project.

Baseline Survey

Baseline survey was carried out to determine the existing ecological conditions and was designed to fill any data gaps, and to facilitate an adequate assessment of the project's impacts upon ecology and the development of appropriate mitigation measures. Survey was conducted in last week of 24th -27th June

2020 for habitat survey, flora & faunal diversity in the study area. Baseline survey has two parts- (i) Secondary data collection and (ii) Primary data collection

Secondary Data Collection

Secondary baseline data regarding sensitive ecological habitat (National Park, Sanctuary, Ecological Sensitive Area, Migratory Corridor, habitat of endangered, vulnerable and range restricted species etc.), flora & fauna in the study area, forest cover was collected from other published and unpublished documents. Stakeholder consultations (Local People etc.) were also carried out to understand the major flora & fauna in the study area, pressure on forest resources, presence of any Schedule I species.

Secondary data collection was the only component of the baseline survey. Secondary data regarding sensitive ecological habitat (National Park, Sanctuary, Ecological Sensitive Area, Migratory Corridor, habitat of endangered, vulnerable and range restricted species etc.), flora & fauna in the project area was recorded by referring other published and unpublished documents.

Establishing ecological hotspots through Secondary Data Base

A Secondary Data Base review was conducted to determine the presence of any hotspots or sightings around the project area. All with available literature review, research papers and websites with online database of bird observations with real-time data about bird distribution and abundance were used. Through the secondary data base review it was established that there were no forest areas around the project area and there were no hotspots around the project area as well.




Figure 4-20: Map showing presence of no hotspots and sightings around the project area


4.4.2. Habitat Survey

According to the Biogeographic provinces of India published by Wildlife Institute of India (Rodgers, Panwar and Mathur, 2002), the project site falls under the Biogeographic Province – 3-A Desert Thar. The site survey also included understanding of important habitats in the area

A “Habitat” according to IFC is defined as a terrestrial, freshwater, or marine geographical unit or airway that supports assemblage of living organisms and their interactions with the non-living environment. As per IFC, habitats are divided into - Natural, Modified or Critical the purpose of implementation of IFC Performance Standard-6 (Biodiversity Conservation and Sustainable Management of Living Natural

Resources). Critical habitats are subsets of Natural habitats. No Critical habitats were observed in the study area. Types of habitats are described in detail in this section below.

Figure 4-21: Location of project area on the Biogeographic Zones.




Types of Habitats in the Study Area

Scrub Land: This type of vegetation is extensively found in non-cultivated lands, particularly revenue lands/grazing land located within the study area. These type of land gets grown by *Prosopis Juliflora* and local villagers make charcoal by burning the well grown logs of these plants. Tall trees were generally found absent or sparsely distributed. Solid wood thorny trees like *Acacia nilotica*, *Prosopis juliflora*, *Morinda tinctoria*, *Commiphora berryi*, *Catunaregam spinosa*, *Azima tetraacantha*, *Opuntia sp*, *Cassia auriculata*, *Capparis decidua* (Ker sangri) etc. were commonly observed in the natural scrublands. A plenty of *Borassus flabellifer* (palm tree) were observed along the bunds of the agricultural fields.

In general, type 6A/C2/DS1 – Southern Thorn Scrub forest as per Champion & Seth 1968 is found in the study area. These forests contain spare and stunted growth of species like *Acacia nilotica*, *Prosopis juliflora*, *Morinda tinctoria*, *Commiphora berryi*, *Catunaregam spinosa*, *Azima tetraacantha*, *Opuntia sp*, *Cassia auriculata* and thorny bushes etc along with other ground cover represented by *Calotropis gigantea*, *Ziziphus sp*, *Croton bonplandianum*, *Capparis sepiaria*, *Cassia auriculata*. Important landuse features in the study area is shown in **Figure 4-2**.

Figure 4-22: Important Land use features in the study area



Agricultural Field: Major agricultural crops include Guar (*Cyamopsis tetragonoloba*), Bajra (*Pennisetum glaucum*), Channa (*Cicer Arietinum*), cumin seeds (*Cuminum cyminum*), Jowar (*Sorghum*) etc. Thorny bushes dominated by *Prosopis juliflora* grow on its own in the abandoned agricultural fields/culturable wastes.

Protected Areas:

Arcadis team met with the Forest officials of Jaisalmer division, Desert National Park (DNP), Jaisalmer to understand if there are any forest areas coming in the project area and the movement of Great Indian Bustards which are seen in Desert National Park. As part of the stakeholder consultation, discussion was conducted with the Forest Guard Mr Jalan Singh. The objective of the discussion was to get the information about local flora and fauna of the area, animal movements and if there are any issues faced

by Forest Officials in the proposed project area. Apart from this, the GIB presence if any in proposed area was also discussed.

During discussion with Forest Officials, Desert National Park (DNP), Jaisalmer following was highlighted

- No notified/designated forest area exists within 10 km from project site. DNP is located within 30 km from project site.
- As per BNHS Report, “during surveys, Great Indian Bustard *Ardeotis nigriceps* was not seen. While two unconfirmed sightings of GIB were reported by local people in year 2017–18 at Negarda (26.280847°, 71.143286°) and in between Khyala and Reevari (26.469018°, 71.052508°) which are westernmost part of the study area. Rasla enclosure, Desert National Park (DNP) is 40 km North-East from one of the edges of study area and birds might not be using the site regularly.
- Khejri tree also found in the region but not near the project site.

Forest department expectation:

- Bird diverter should be installed in transmission line which the client will be complying with respect to the sensitive areas as suggested by the study undertaken by Bombay Natural History Society (BNHS)
- Transmission line should be planned careful keeping DNP buffer zone (10 km) in mind. They have suggested for underground transmission line if it passes through the buffer zone of DNP.

Desert National Park:

Desert National Park is a beautiful place, located in the Jaisalmer district of the state of Rajasthan. Desert National Park is one of the largest national parks in India. The Desert National Park is also a protected sanctuary.

The Desert protected sanctuary was declared as a National park in 1980. Total area of the National park is about 3162 km². The desert is a harsh place to sustain life and thus most of the fauna and flora live on the edge. Desert National Park is an excellent example of the desert ecosystem. The landform primarily comprises rocks and compact Salt Lake bottoms, intermediate areas and fixed dunes. Across the landscape of Jaisalmer, altitudes are low, ranging from 210-320 m above mean sea level. The topography of Desert National Park supports sandy, gravelly, rocky, and compact Salt Lake bottoms. Sandy areas dominate the western parts of Jaisalmer district, while gravelly and rocky areas are scattered throughout central, southern and eastern areas. The Desert National Park is barren with several sand dunes and a few hills in the north-western region. The Park forms a vast sandy and undulating terrain.

Its inhabitants include the blackbuck, chinkara, wolf, Indian fox, desert fox, hare and desert cat. Birds like Sandgrouse, Grey Partridge, Blue tailed and green bee-eaters, Drongo, Common and Bush quail and Indian rollers are observed. The park is also home to the Great Indian Bustard which is peril of extinction

Figure 4-23: Forest Office of Jaisalmer



Figure 4-24: Eco-Sensitivity of Project Area





Figure 4-25: Topographical Map of Project Area



4.4.3. Primary Survey

Flora Survey

The primary floral survey was conducted to record site specific floral species and its diversity. At the time of the survey, xerophytic thorny vegetation was recorded from the proposed project site. More than 90% of the project area is surrounded by xerophytic thorny vegetation. Further data were gathered from secondary sources like governmental department records, forest officials and local villagers. None of the species recorded falls in the IUCN red list category

The proposed project site is located in the semi-arid and arid climate zone. Arid, generally dry, thorny scrubs patches are observed in the study area. High temperature and low rainfall in the area also influences the vegetation pattern. The floral survey was limited to record site specific floral species (both woody trees/small tree species as well as ephemeral ground vegetation). Assessing the existing floral profile is necessary to understand the baseline conditions of the area as the project activities may lead to loss of significant ecological resources, if present. The information will add on to the knowledge of ecological resources and help in further evaluating the possible risks due to project activities and feasibility of the proposed mitigation measures.

- Trees: Among trees, *Capparis decidua*, *Prosopis cineraria*, *Vachellia nilotica*, *Tecomella undulata* were the most dominant tree
- Shrubs and Herbs: The ground vegetation is completely absent or covered with grass in most of the locations. The common species are *Euphorbia Ligularia*, *Salvadora persica*, *Cassia augustiflora*, *Calotropis procera*, *Ziziphus mauritiana* etc.

Grasses: There are 3 grasses species are observed during the field survey. The most common species are *Lasiurus scindicus*

List of important trees and herbs and shrubs reported in the study area has been enlisted in Error! Reference source not found..

Table 15: List of Trees Observed in the Project Area

Sl. No.	Local Name	Botanical Names	Family
1.	<i>Capparis decidua</i>	Tree	Kair
2.	<i>Calotropis procera</i>	shrub	Aarka
3.	Grass sp.	Grass	-
4.	<i>Prosopis juliflora</i>	Shrub	Vilaytati Babul
5.	<i>Prosopis cineraria</i>	Tree	Khejri
6.	<i>Ziziphus mauritiana</i>	Shrub	Ber
7.	<i>Eruca sativa</i>	Herb	Taramira
8.	<i>Leptadenia pyrotechnica</i>	Shrub	Kheemp
9.	<i>Cassia augustiflora</i>	Shrub	Sinniya
10.	<i>Salvadora persica</i>	Shrub	Peelu
11.	<i>Euphorbia caducifolia</i>	Shrub	Thor
12.	<i>Aerva javanica</i>	Shrub	Bui
13.	<i>Saccharum sp.</i>	Grass	Kaas
14.	<i>Cuminum cyminum</i>	Herb	Jeera
15.	<i>Lasiurus scindicus</i>	Grass	sevan
16.	<i>Vachellia nilotica</i>	Tree	Babool
17.	<i>Calligonum polygonoides</i>	Shrub	Phog
18.	<i>Jambo Grass</i>		
19.	<i>Tecomella undulata</i>	Tree	Rohida
20.	<i>Euphorbia ligularia</i>	Shrub	Thor
21.	<i>Brassica juncea</i>	Herb	Sarson
22.	<i>Cenchrus setiger</i>	Grass	Bhurat

Source: Primary observations, Late Winter Season Report - Bird surveys at the proposed hybrid project sites in Rewari and Devaka, Rajasthan by Bombay Natural History Society 4th May 2020, discussion with local people and Information obtained from Range Forest Officer, Fatehgarh and Jaisalmer.

Faunal Survey

To assess the faunal diversity in the project site, point survey was carried out. Locations around the proposed WTG & solar project were visited to find out the presence of faunal species near the project site. The faunal survey focused mainly on three groups viz. mammals, avifauna and herpeto fauna of the study area. Surveys were undertaken to observe daily movements of birds from roosting to foraging sites if any. The survey area comprises of the WTG themselves plus a 2 km buffer and a 20 km radius of the project site. Data related to the other faunal species were also noted based on the direct sightings and from authentic secondary sources. Secondary sources like published books and reports, government departmental records, interviews with forest department and information from residents were further used to gather information and support primary observations.

During site visit a few animals like Chinkara and Nilguy were seen in and around the project site and study area. However, during consultation with local villagers and forest department, it was confirmed the presence of mammalian species such as Neel gai (*Boselaphus tragocamelus*), Indian common Hare (*Lepus nigricollis*), Common Mongoose (*Herpestes edwardsi*), Jackal (*Canis aureus*), House rat (*Rattus rattus*) etc also reported by the local community and Panchayat members of the study area. Presence of Chinkara (*Gazella bennettii*) which is a schedule-I species as per Wild Life (protection) Act, 1972, is reported by the forest department. No other schedule -I species reported from the study area. A list of mammalian species that reported to be present in the study are enlisted below.

Table 16: List of Fauna observed in the Project Area

Sl. No.	English Name	Scientific Name	Occurrence	WPA Schedule/ IUCN Status
1.	Common Mongoose	<i>Herpestes edwardsii</i>	Rare	II/LC
2.	Striped Squirrel	<i>Funambulus palmarum</i>	Common	IV/LC
3.	White-Footed Fox	<i>Vulpes pusilla</i>	Rare	I/LC
4.	Indian Fox	<i>Vulpes bengalensis</i>	Common	II/LC
5.	Nilgai	<i>Boselaphus.tragocamelus</i>	Common	LC
6.	Chinkara	<i>Gazella bennettii</i>	Common	I/Vulnerable
7.	Indian Desert Gerbil	<i>Meriones hurrianae</i>	Common	LC
8.	Indian Camel	<i>Camelus</i>	Common	LC
9.	Indian Long-eared Hedgehog	<i>Hemiechinus collaris</i>	Common	LC
10.	Indian Desert Cat	<i>Felis lybica ornata</i>	Common	I/LC
11.	Indian Desert Jird	<i>Meriones hurrianae</i>	Common	V/LC
12.	Wild Boar	<i>Sus scrofa</i>	Common	III/LC
13.	Five-striped Palm Squirrel	<i>Funambulus pennantii</i>	Common	IV/LC
14.	Indian Hare	<i>Lepus nigricollis</i>	Common	IV/LC

Vulnerable; NT-Near Threatened, LC-Least Concern (IUCN Ver. 3.1), Schedule – I, IV, V (Indian Wildlife Protection Act -1972)

Source: Primary observations, Late Winter Season Report - Bird surveys at the proposed hybrid project sites in Reevari and Devaka, Rajasthan by Bombay Natural History Society 4th May 2020, discussion with local people and Information obtained from Range Forest Officer, Fatehgarh and Jaisalmer

Birds

As the migration season had ended no prominent bird activity was observed in and around the site. House sparrow, House Crow and Indian Peafowl were the only birds observed due to extreme weather conditions. However, during discussion with Forest Officials it was informed that during peak migratory season a lot of bird activity- both migratory and resident birds like raptors, ground dwelling birds are seen in this region. In the table are birds that have been reported around the project site as mentioned in the late Winter Season Report - Bird surveys at the proposed hybrid project sites in Reevari and Devaka, Rajasthan by Bombay Natural History Society 4th May 2020 and during the discussions with Forest Officials.

Table 17: List of Recorded Birds

S.No.	Common Name	Scientific Name	Wetland s	IUCN Status	WPA Status	R/M/LM
1.	Ashy-crowned Sparrow-Lark	<i>Eremopterix griseus</i>	0	LC	IV	R
2.	Asian Desert Warbler	<i>Sylvia nana</i>	0	LC	IV	M
3.	Asian Green Bee-eater	<i>Merops orientalis</i>	1-2	LC	IV	R
4.	Barn Swallow	<i>Hirundo rustica</i>	1-6	LC	IV	R
5.	Bimaculated Lark	<i>Melanocorypha bimaculata</i>	0	LC	IV	M
6.	Black Drongo	<i>Dicrurus macrocercus</i>	1-2	LC	IV	R

S.No.	Common Name	Scientific Name	Wetlands	IUCN Status	WPA Status	R/M/LM
7.	Black Redstart	<i>Phoenicurus ochruros</i>	0	LC	IV	R
8.	Black Stork	<i>Ciconia nigra</i>	0	LC	IV	M
9.	Black-crowned Sparrow-lark	<i>Eremopterix nigriceps</i>	0	LC	IV	R
10.	Black-winged Kite	<i>Elanus caeruleus</i>	0	LC	I	R
11.	Black-winged Stilt	<i>Himantopus himantopus</i>	1-12	LC	IV	R
12.	Blue-cheeked Bee-eater	<i>Merops persicus</i>	0	LC	IV	R
13.	Blyth's Pipit	<i>Anthus godlewskii</i>	0	LC	IV	M
14.	Bonelli's Eagle	<i>Aquila fasciata</i>	0	LC	I	R
15.	Chestnut-bellied Sandgrouse	<i>Pterocles exustus</i>	1-2	LC	IV	R
16.	Cinereous Vulture	<i>Aegypius monachus</i>	0	NT	IV	LM
17.	Citrine Wagtail	<i>Motacilla citreola</i>	0	LC	IV	LM
18.	Common Babbler	<i>Argya caudata</i>	1-2	LC	IV	R
19.	Common Crane	<i>Grus grus</i>	0	LC	IV	M
20.	Common Hoopoe	<i>Upupa epops</i>	1-3	LC	IV	LM
21.	Common Kestrel	<i>Falco tinnunculus</i>	0	LC	IV	LM
22.	Common Moorhen	<i>Gallinula chloropus</i>	0	LC	IV	R
23.	Common Myna	<i>Acridotheres tristis</i>	1-2	LC	IV	R
24.	Common Coot	<i>Fulica atra</i>	1-12	LC	IV	R
25.	Common Pochard	<i>Aythya ferina</i>	1-9	VU	IV	M
26.	Common Raven	<i>Corvus corax</i>	0	LC	IV	LM
27.	Common Redshank	<i>Tringa totanus</i>	1-8	LC	IV	M
28.	Common Sandpiper	<i>Actitis hypoleucos</i>	0-1	VU	IV	LM
29.	Common Snipe	<i>Gallinago gallinago</i>	0-1	LC	IV	M
30.	Common Tailorbird	<i>Orthotomus sutorius</i>	0	LC	IV	R
31.	Common Teal	<i>Anas crecca</i>	1-19	LC	IV	M
32.	Demoiselle Crane	<i>Anthropoides virgo</i>	500 3-	LC	IV	M
33.	Desert Lark	<i>Ammomanes deserti</i>	0	LC	IV	R
34.	Desert Wheatear	<i>Oenanthe deserti</i>	0	LC	IV	M
35.	Eastern Imperial Eagle	<i>Aquila heliaca</i>	0	VU	I	M
36.	Egyptian Vulture	<i>Neophron percnopterus</i>	0	EN	IV	M
37.	Eurasian Collared-dove	<i>Streptopelia decaocto</i>	1-8	LC	IV	R
38.	Eurasian Sparrowhawk	<i>Accipiter nisus</i>	0	LC	I	M
39.	Eurasian Spoonbill	<i>Platalea leucorodia</i>	0-1	LC	IV	M
40.	Gadwall	<i>Mareca strepera</i>	1-10	LC	IV	M
41.	Garganey	<i>Spatula querquedula</i>	0	LC	IV	M
42.	Great Grey Shrike	<i>Lanius excubitor</i>	0	LC	IV	R

S.No.	Common Name	Scientific Name	Wetlands	IUCN Status	WPA Status	R/M/LM
43.	Greater Short toed Lark	<i>Calandrella rachydactyla</i>	0	LC	IV	M
44.	Greater Spotted Eagle	<i>Clanga clanga</i>	0	VU	I	M
45.	Grey Francolin	<i>Francolinus pondicerianus</i>	0-1	LC	IV	R
46.	Grey Heron	<i>Ardea cinerea</i>	0-1	LC	IV	R
47.	Eurasian Griffon	<i>Gyps fulvus</i>	0	LC	IV	LM
48.	Himalayan Griffon	<i>Gyps himalayensis</i>	-	NT	I	M
49.	Horsfield's Bushlark	<i>Mirafra cantillans</i>	0	LC	IV	R
50.	House Crow	<i>Corvus splendens</i>	1-50	LC	V	R
51.	House Sparrow	<i>domesticus Passer</i>	200 1-	LC	IV	R
52.	Indian Peafowl	<i>Pavo cristatus</i>	1-9	LC	I	R
53.	Indian Pond heron	<i>Ardeola grayii</i>	1	LC	IV	R
54.	Indian Robin	<i>Saxicoloides fulicatus</i>	0	LC	IV	R
55.	Indian Roller	<i>Coracias benghalensis</i>	0	LC	IV	R
56.	Indian Silverbill	<i>Euodice malabarica</i>	6	LC	IV	R
57.	Intermediate Egret	<i>Ardea intermedia</i>	0	LC	IV	R
58.	Isabelline Shrike	<i>Lanius isabellinus</i>	0	LC	IV	M
59.	Laggar Falcon	<i>Falco jugger</i>	0	NT	IV	R
60.	Large-billed Crow	<i>Corvus macrorhynchos</i>	0	LC	IV	R
61.	Laughing Dove	<i>Spilopelia senegalensis</i>	0	LC	IV	R
62.	Lesser Whitethroat	<i>Sylvia curruca</i>	1	LC	IV	M
63.	Little Egret	<i>Egretta garzetta</i>	1	LC	IV	R
64.	Little Grebe	<i>Tachybaptus ruficollis</i>	1-6	LC	IV	R
65.	Little Ringed Plover	<i>Charadrius dubius</i>	1-22	LC	IV	R
66.	Little Stint	<i>Calidris minuta</i>	12	LC	IV	M
67.	Mallard	<i>Anas platyrhynchos</i>	3-30	LC	IV	M
68.	Northern Pintail	<i>Anas acuta</i>	0	LC	IV	M
69.	Northern Shoveler	<i>Spatula clypeata</i>	1-8	LC	IV	M
70.	Paddyfield Pipit	<i>Anthus rufulus</i>	1	LC	IV	R
71.	Pallid Harrier	<i>Circus macrourus</i>	0	NT	I	M
72.	Pied Bushchat	<i>Saxicola caprata</i>	0.00	LC	IV	R
73.	Plain Prinia	<i>Prinia inornata</i>	0.00	LC	IV	R
74.	Purple Sunbird	<i>Cinnyris asiaticus</i>	0	LC	IV	R
75.	Red-crested Pochard	<i>Netta rufina</i>	1-3	LC	IV	M
76.	Red-naped Ibis	<i>Pseudibis papillosa</i>	0	LC	IV	R
77.	Red-vented Bulbul	<i>Pycnonotus cafer</i>	0	LC	IV	R
78.	Red-wattled Lapwing	<i>Vanellus indicus</i>	1-18	LC	IV	R
79.	Rock Dove	<i>Columba livia</i>	1-50	LC	IV	R
80.	Rosy Starling	<i>Pastor roseus</i>	0	LC	IV	M

S.No.	Common Name	Scientific Name	Wetlands	IUCN Status	WPA Status	R/M/LM
81.	Ruff	<i>Calidris pugnax</i>	0	LC	IV	R
82.	Rufous Treepie	<i>Dendrocitta vagabunda</i>	0	LC	IV	R
83.	Rufous-fronted Prinia	<i>Prinia buchanani</i>	0	LC	IV	R
84.	Rufous-tailed Lark	<i>Ammomanes phoenicura</i>	0	LC	IV	R
85.	Shikra	<i>Accipiter badius</i>	0	LC	I	R
86.	Short-eared Owl	<i>Asio flammeus</i>	0	LC	IV	R
87.	Short-toed Snake-eagle	<i>Circaetus gallicus</i>	0	LC	I	R
88.	Sind Sparrow	<i>Passer pyrrhonotus</i>	0	LC	IV	R
89.	Tawny Eagle	<i>Aquila rapax</i>	0	VU	I	R
90.	Tree Pipit	<i>Anthus trivialis</i>	0	LC	IV	M
91.	Variable Wheatear	<i>Oenanthe picata</i>	0	LC	IV	R
92.	Western Marsh harrier	<i>Circus aeruginosus</i>	0	LC	I	M
93.	Western Yellow Wagtail	<i>Motacilla flava</i>	0	LC	IV	R
94.	White Wagtail	<i>Motacilla alba</i>	1-4	LC	IV	R
95.	White-breasted Kingfisher	<i>Halcyon smyrnensis</i>	0	LC	IV	R
96.	White-browed Bushchat	<i>Saxicola macrorhynchus</i>	0	VU	IV	R
97.	White-eared Bulbul	<i>Pycnonotus leucotis</i>	1-3	LC	IV	R
98.	Wood Sandpiper	<i>Tringa glareola</i>	1-2	LC	IV	M

Vulnerable; NT-Near Threatened, LC-Least Concern, NA- Not Evaluated (IUCN Ver. 3.1), Schedule – I, IV, V (Indian Wildlife Protection Act -1972), R- resident, M- Migrant, PM- Passage Migrant

Source: Primary observations and late Winter Season Report - Bird surveys at the proposed hybrid project sites in Reewari and Devaka, Rajasthan by Bombay Natural History Society 4th May 2020, discussion with local people and Information obtained from Range Forest Officer, Fatehgarh

Figure 4-26: Birds recorded at Project site.



Egyptian Vulture



Western Marsh harrier



Variable Wheatear



Short-toed Snake-eagle



Purple Sunbird



Red vented Bulbul



Laughing Dove



Brown Rock Chat



Indian Robbin



Collar Dove



House Sparrow



Red wattled Lapwing



Common Kestrel



Black Drongo



Gargany



Common sandpiper



Common green shank



Grey Francolin



Little Grebe



Shikra

Due to the presence of raptors in and around the project area, a detailed Bird & Bat survey along with long term monitoring is recommended.

The Primary Observations of these report are as follows:

- The project site does not make part of any protected habitats for birds and bats.
- Project area maintains substantial distances from the Important Bird Areas of Rajasthan.
- Project area maintains substantial distances from Wildlife Sanctuaries and their eco-sensitive zones of Rajasthan.

4.5. Socio-Economic Environment

This section describes the socio-economic condition in the study area and relates the village level socio-economic conditions with tehsil and district level. The objective of analysis of information at village, tehsil and district level is to identify the existing facilities and gaps at village level which can be considered as need of the study area.

Along with site visit, the study was based on primary & secondary data collection from various sources and consultations with various stakeholders. Telephonic Interviews and face to face interaction were also undertaken with Project Proponent, local villagers and government officials. Information and documents were collected from SBE, project site and land details as per requirements. The assessment of socio-economic environment was carried out based on the primary telephonic survey with the help of framed questionnaire to conduct community consultation (as presented in **APPENDIX C**). Secondary data includes Census 2011, information available on the official website of the district of Barmer and Jaisalmer and other available data on official Government websites.

The socio-economic assessment has been done based on the information's provided by SBE like land details etc. and the outcomes of the consultation with the Revenue officers, SB Energy officials and other community members conducted onsite.

4.5.1. Objective

The main objective of the telephonic consultations was to develop an understating of the community in general of the project affected area. Through the consultative process the areas which the project is impacting the individuals and the community, is also perceived. Along with that, the feasible mitigation measures of the impacts are also identified.

The observations made in this section are intended to capture the status of the project and, therefore, briefly mention the 'way ahead' to successfully complete the ESIA study. The understanding of the

project profile was carried out with the project proponent and details of the same will be included in the ESIA report.

4.5.2. Methodology

The social assessment is primarily based on the analysis of the secondary data obtained from the Census 2011, district portal website and conducted the consultation with community & different level stakeholder with the help of framed sample questionnaire for village profiling. Considering the nature of the project, operations and understanding of the demographic characteristics of the area from the secondary data it is designed to capture occupational patterns, societal set up, access to basic amenities along with socio - economic profiling of villages and communities.

The following methodology was adopted:

- Telephonic and site Consultation with local representatives of project proponent;
- Telephonic Consultation with Land Aggregator;
- Telephonic and personal Consultation with Revenue officer,
- Telephonic Consultation with local sub-registrar office;
- Telephonic and site Consultation with all level stakeholders in the study area villages (e.g. Panchayat Members, Village Heads, Teachers, Farmers, Health Worker, ICDS Workers etc.

4.5.3. Demographic Profile

The 450 MW Hybrid Power Project is located at 7 villages, out of which 6 villages fall in Sheo taluk of Barmer district and village Reewari in Sam block of Jaisalmer district, Rajasthan. The details of the study area for which socio-economic profiling has been carried is depicted in **Table .**

Table 18: Project Location

Sl. No.	State	District	Mandal/ Taluka	Village
1	Rajasthan	Barmer	Sheo	Mati Ka Gol
2				Manihari
3				Junejon Ki Basti
4				Harwa
				Bhairoopura
6				Deoka
7		Jaisalmer	Sam	Reewari

Source: (SBE), Primary Consultation and Census 2011

Demographic Profile of the District Barmer

In 2011, Barmer had population of 2,603,751 of which male and female were 1,369,022 and 1,234,729 respectively. Average literacy rate of Barmer were 56.53 of which male and female literacy were 70.86 and 40.63. With regards to Sex Ratio in Barmer, it stood at 902 per 1000 male. The Socio- Economic profile of the Barmer District is presented in **Table .**

Table 19: Socio- Economic profile of the Barmer District

Particulars		Project Influence Area
General	Area in Sq.m	28387.00

Particulars		Project Influence Area		
	No. of Households	4,50,624		
	Sex ratio (Per 1000)	902		
	Child Sex ratio (Per 1000)			
	Density/Km2	92		
Population	Particulars	Male	Female	Total
	Rural	12,73,249	11,48,665	24,21,914
	Urban	95,773	86,064	1,81,837
	Total Population	13,69,022	12,34,729	26,03,751
	Childs Population (0-6)	2,63,356	2,38,166	5,01,522
	Schedule Castes %	16.69	16.84	16.76
	Schedule tribes %	6.76	6.77	6.77
Literacy Rate	Literacy in No.	7,83,461	4,04,861	11,88,322
	Literacy %	70.86	40.63	56.53
Economic Activities	Total Workers %	50.86	41.00	46.18
	Main Workers %	38.45	17.41	28.47
	Marginal Workers %	12.40	23.59	17.41
	Non-Workers %	49.14	59.00	53.82
Category of Workers	Cultivators %	57.45	69.98	62.73
	Agriculture Labour %	8.98	13.86	11.04
	Main Household %	2.47	2.64	2.54
	Other workers %	31.10	13.52	23.70

Source: Census of India 2011

Demographic Profile of the District

In 2011, Jaisalmer had population of 669919 of which male and female were 3,61,708 and 308211 respectively. With regards to Sex Ratio in Jaisalmer, it stood at 852 females per 1000 male. There were total 130463 children under 0-6 yrs of age. Child Sex Ratio as per census 2011 was 874. The Socio-Economic profile of the Jaisalmer District is presented in **Table .**

Table 20: List of Villages within the Project Area

Particulars		Project Influence Area		
General	Area in sq. m	38401		
	No. of Households	117171		
	Sex ratio (Per 1000)	852		
	Child Sex ratio (Per 1000)	874		
Population	Particulars	Male	Female	Total
	Rural	312447	268447	5,80,894
	Urban	49261	39764	89025
	Total Population	3,61,708	308211	669919
	Childs Population (0-6)	69610	60853	130463

Particulars		Project Influence Area		
	Schedule Castes	52776	46358	99134
	Schedule tribes	22497	19932	42429
Literacy Rate	Literacy in No.	210415	98238	308653
	Literacy %	72.035 %	39.71 %	57.21 %
Economic Activities	Total Workers %	1,82,565 (62.50 %)	106338 (42.98 %)	288903 (53.55 %)
	Main Workers %	137757 (47.16 %)	37626 (15.21 %)	175383.00 (32.51 %)
	Marginal Workers %	44808 (15.34 %)	68712 (27.77 %)	1,13,520 (21.04 %)
	Non-Workers %	179143 (61.32 %)	201873 (81.61 %)	381016 (70.62 %)
Category of Workers	Cultivators %	22265 (7.62 %)	33473 (13.53 %)	55738 (10.33 %)
	Agriculture Labour %	11122 (3.80 %)	18019 (7.28 %)	29141 (5.40 %)
	Main Household %	3444 (1.17 %)	1129 (0.45%)	4477 (0.82 %)
	Other workers %	70012 (23.96 %)	9339 (3.77%)	79351 (14.70%)

Source: Census of India, 2011

Study Area Villages

Demographic Profile


The demographic profile in terms of total population and sex-ratio of the study area villages are discussed in the section below.

Table 21: Demographic Profile of the Project Area

Taluk/ Village	Total Population	Male Population	% Male	Female Population	% Female	Sex Ratio
Barmer District						
Taluk- Sheo	2,37,080	1,27,247	53.67	1,09,833	46.33	863
Village Mati Ka Gol	488	257	52.7	231	47.34	1113
Village Manihari	787	417	53.0	370	47.01	1127
Village Junejon Ki Basti	1223	634	51.8	589	48.16	1076
Village Harwa	1417	757	53.4	660	46.6	1147
Village Bhairoopura	323	169	52.3	154	47.7	1097
Village Deoka	981	532	54.2	449	45.8	1185
Jaisalmer District						
Taluk- Sam	1,89,707	1,03,813	54.7	85,894	45.3	1209
Village Reewari	1208	651	53.9	557	46.1	2170

Source: Census of India 2011

Figure 4-27: Population Distribution in the study Area



4.5.4. Schedule Caste and Schedule Tribes (SC/ST)


As per census 2011, the study area has sizable no of SC population & and negligible no of ST population. Details of the study area SC & ST population percentage with respect to the total population is appended herein **Table 22**.

Table 22: Study Area SC & ST Percentage

Study Area	Scheduled Caste (No)	Scheduled Caste (%)	Scheduled Tribe (No)	Scheduled Tribe (%)
Barmer District				
Taluk- Sheo	40,679	17.16	9,790	4.1
Village Mati Ka Gol	13	2.66	0	0
Village Manihari	0	0.00	0	0
Village Junejon Ki Basti	28	2.29	0	0
Village Harwa	306	21.59	21	1.5
Village Bhairoopura	29	8.98	0	0.0
Village Deoka	7	0.71	34	3.5
Jaisalmer District				
Taluk- Sam	31,340	16.52	9,413	5.0
Village Reewari	530	43.87	53	4.4

Source: Census of India, 2011

Figure 4-28: SC & ST Population in the Study Area




4.5.5. Literacy in the Study Area

Average literacy rate of Sheo Taluk in 2011 were 44.3 % and Sam Taluk is 42.2 % respectively. As per census 2011 details of the study area literacy scenario is given in **Table 23**.

Table 23: Study Area Literacy Scenario

Study Area	Total Literacy	Male Literacy	Female Literacy	Total Literacy %	Male Literacy %	Female Literacy %
Barmer District						
Taluk- Sheo	1,05,075	71,894	33,181	44.3	56.5	30.2
Village Mati Ka Gol	284	163	121	58.2	63.4	52.4
Village Manihari	384	257	127	48.8	61.6	34.3
Village Junejon Ki Basti	163	113	50	13.3	17.8	8.5
Village Harwa	699	483	216	49.3	63.8	32.7
Village Bhairoopura	144	106	38	44.6	62.7	24.7
Village Deoka	451	298	153	46.0	56.0	34.1
Jaisalmer District						
Taluk- Sam	80,015	56,818	23,197	42.2	54.7	27.0
Village Reewari	487	340	147	40.3	52.2	26.4

Source: Census of India, 2011

Figure 4-29: Literacy in the Study Area


4.5.6. Workers and Occupation

Study Area Barmer: Based on secondary census data, consultation with stakeholders and site photographs/Videos observation, the primary occupation on the study area is agriculture activities. According to Census 2011 the percentage of cultivators among the total working population of the villages in Barmer in the range of more than 70 percent to 100 percent and in Jaisalmer is 10 percent and rest are agriculture labour. Worker scenario is given in **Table 24** and **Table 25**.

Table 4-16: Study Area working Scenario

Study Area	Total Workers	Total Main Workers	Total Marginal Workers	Total Workers %	Total Main Workers %	Total Marginal Workers %
Barmer District						
Taluk- Sheo	105177	57,544	47,633	44.4	54.7	45.3
Village Mati Ka Gol	244	9	235	50.0	3.7	96.3
Village Manihari	350	347	3	44.5	99.1	0.9
Village Junejon Ki Basti	175	39	136	14.3	22.3	77.7
Village Harwa	740	151	589	52.2	20.4	79.6
Village Bhairoopura	161	123	38	49.8	76.4	23.6
Village Deoka	499	215	284	50.9	43.1	56.9
Jaisalmer District						
Taluk- Sam	83,518	47,362	36,156	44.0	56.7	43.3
Village Reewari	617	65	552	51.1	10.5	89.5


Source: Census of India, 2011


Table 25: Categorization of workers

Village	Total Cultivator %	Total Agri Labour %	Main Household Industries %	Total Other Workers %
Barmer District				
Taluk- Sheo	72	9.7	2.2	16.0
Village Mati Ka Gol	100	0	0	0
Village Manihari	94.6	0.3	1.7	3.4
Village Junejon Ki Basti	95.6	0.0	0.0	4.4
Village Harwa	0	0.0	47.7	52.3
Village Bhairoopura	73.8	0.4	0.8	25.0
Village Deoka	95.0	0	0	5.0
Jaisalmer District				
Taluk- Sam	46.5	17.0	1.8	34.7
Village Reewari	10.2	81.0	1.1	7.1

Source: Census of India, 2011

Figure 4-30: Status of working population in the Study Area





4.5.7. Wages

As per circular of Labour Department, Govt of Rajasthan, the minimum wage for Contract Labors in all sector is Rs. 249, Rs. 237 and Rs.225 for skilled, semi- skilled and unskilled laborer's respectively w.e.f 1st May 2019.

Table 26: Minimum Wages for Labourers (INR)

Sl. No	CONTRACT LABOUR	BASIC WAGE (INR)
	CATEGORY	PER DAY
1.	Skilled	249.00/day
2.	Semi-Skilled	237.00/day
3.	Unskilled	225.00/day

Source: <https://paycheck.in/salary/minimumwages/Rajasthan>

4.5.8. Livelihood Resource

Agriculture and cropping pattern: As per Census 2011, more than 80 percent of the working population is directly dependent on agriculture, animal husbandry and labourers in nearby mining area. The agriculture in the area is majorly dependent on rain and large portion of the land remains barren in most part of the year. Though, during site visit, it was noticed that there is no irrigational facility available and there is severe shortage of rainfall and ground water level is also very high which led to loss of agriculture production in the region. Yet, in absence of any other alternative source for livelihood, Agriculture and animal husbandry continuing to be the prime livelihood resource. The important crops grown are Jowar, bajra, pulses, jeera and cotton.

4.5.9. Livestock

Project area has rich livestock resources especially goat and sheep population. The livestock population of the study area consists mainly of wool and milk producing animals. The village have notable number of livestock population i.e. sheep, goats, cow and buffalo. Gauchar land are available for grazing purpose in most the villages.



Animal Husbandry is commonly practice in the study area

4.5.10. Local Employment and Migration

During consultation with the community at the study area village, it was observed that animal husbandry and agriculture are important sources for livelihood. The same pattern of local engagement is for the weaker sections like SCs & STs. Also, the same has been verified with information available from Census 2011. There is no big industry in the region. People have migrated to urban center for better education & job opportunities.

4.5.11. Gender Empowerment Status

The female work participation rate in the area was observed to be lower in comparison to male work participation rate. In study area village, more than 50 % of the total working population are male and 41% of the total working population are female in Barmer district and in Jaisalmer, 62.50 percent are male working population and 43 percent are female engaged in economic activities. the women workforce is mainly concentrated in activities which are unorganized and informal. Household chores are mainly managed by women. Female laborers are engaged mainly in agriculture and animal husbandry.

4.5.12. BPL Families & Vulnerabilities

As reported by the panchayat and community members, a few persons from different vulnerable groups (e.g. BPL, SCs, STs, landless family, orphans & children, old aged/senior citizens, differently abled people, physically handicapped and lone widow, poor migrants etc.) are present in the village.

In Harwa gram panchayat, there are 15 physical handicaps and as per the updated BPL list under Pradhan Mantri awas yojana, there are 197 BPL families. The project proponent may be required to focus on providing livelihood support opportunity to the vulnerable members and implementation of development programs under CSR activity.

4.5.13. Land Holding Pattern

During discussions with the local community in the study area, it was understood that the average land holding size varies between 25-30 bigha per household in study area villages. As information revealed during telephonic consultation with the community, govt. bore well is the one of sources for irrigation and other source is artificial ponds/wells and through tanker supply. Harwa Panchayat water supply available through tube well.

4.5.14. Irrigation

As per information revealed during consultation with the community, there is no government irrigation facility available in the study area. Irrigation is mostly dependent on seasonal rainfall.

4.5.15. Amenities & Infrastructure

The Social and physical infrastructure and amenities available in the study area denotes the social and economic wellbeing as well as the Quality of Life (QoL) of the region. No major physical and social infrastructure facilities are available in the study area. Communications and transportation facility are very poor.

A review of infrastructure facilities available in the area has been done based on the information given in Barmer and Jaisalmer District Census Handbook, the data of National Informatics Center, for the year 2011 as well as from other resources and site visit undertaken.

Medical Facilities: Study area- village

As observed the health facility in study area villages is inadequate to cater the needs of the population. Harwa, Manihari and Reevadi have public health sub center and people normally go to the nearest Community Health Centre (CHC) at Seo and Sam taluka which is around 7 and 20 km away from the area. ANMs also move into the village for promotion of routine immunisation. Emergency No. 108 is availed for ambulance from Govt. support in times of need. Also, emergency No. 104 is availed for medical assistance. Communicable seasonal diseases like Malaria, dengue is the common disease among the village.

Figure 4-31: Medical facility Available at Villages



Primary Health sub Centre at village Reevadi



Medical Available at Sub Center and No Sitting Arrangement at village Reevadi

Education:

As reported during telephonic consultation with Harwa panchayat head, there are 4 primary schools, 2 Senior Secondary School, 2 Secondary and 1 Upper Primary School in the study area villages. There is one Primary school and one middle high school and one High School in Rewri village of Sam tehsil. College is at Sheo taluka which is about 7 km away. In the school midday meal is provided for students. The schools have separate toilet arrangements for girls and boys. Students normally go to Sheo, Barmer and Sam and Pokhran taluka for availing further higher education.

Figure 4-32: Educational Facility at study area



Rajkiye Aadarsh Uccha Vidhyalaya at Reevadi



Rajkiye Madyamik School at Hadwa



Drinking Water Facility at Reevadi School



Toilet Facility at Reevadi School

Anganwadi Centres (AWC):

“Integrated Child Development Services’ is a 100% centrally sponsored scheme under which six services i.e. supplementary nutrition, pre-school education, immunization, health checkup, health and nutrition education and referral services are provided to the children in the age group of 0-6 years, pregnant women & lactating mothers.

As reported during consultation with community and village panchayat head, there is at least one Anganwadi in each village of the study area. It was reported that anganwadi has its own drinking water facility but there is no toilet facility in the anganwadi. On an average, the Anganwadi Centers has enrolment between 20-50 children and 8- 20 mothers. Some of them visit the centers occasionally and few regularly. Water is mostly carried from the nearby school.

Figure 4-33: Anganwadi Center



Consultation at Anganwadi Lawan

Drinking Water Facility:

It was informed by villagers that tube well is present in Harwa gram panchayat and rest of the villages carry water from the old ponds/well or tanka for drinking purpose. Water is also supplied through tanker to different localities. Average rate of the tanker varies from INR 700-1000 per tanker.

Figure 4-34: Drinking Water Facility



Water Facility in Harwa Village

Other Physical & Social Infrastructure facilities

Communication and Transportation Facilities: Government bus service are not available in the study area villages but other local transport facilities not inadequate. Auto rickshaw services are available for local movement. Otherwise people use their self-owned two and/ or four-wheeler.

Cooking fuel source: During consultation, a gradual growth of preferring LPG over fuel wood was reported in the consulted villages. On an average around 30-40% households use LPG and rest 70 % population use firewood, dried biomass, cow dung briquette are the other sources of energy by villagers for cooking and heating.

Sanitation: Most of the households of the study area have their own sanitation facilities in form of sanitary latrines. Sanitary grant is provided to the villager under the Central Government Scheme Swachh Bharat mission.

Power Supply: Households of all study area villages were observed to have electricity connections. It was told by the local people that electricity is available only for 7-8 hours. Tariffs are being charged for these connections.

4.5.16. Common Property Resources (CPR)

During consultation with Panchayat members and villagers, it was noted that villages have some Common Property Resources (CPR) like community ponds, temples, other ICDS centres, community halls, cremation ground etc. In terms of CPR, there is no impact reported from the project development.

Figure 4-35: Common Property Resources at Study area Villages



Gram Panchayat Bhawan



Tehsildar Office



Internal village road



Dry Pond



Graveyard at Village Reevadi



Artificial pond used for agricultural purpose



Temple in Village Reevadi



Water Supply System at Hadwa



Rajiv Gandhi Service Center at Reevadi



Community Center at Reevadi

4.5.17. Archaeological Site

As observed during field visit there is no designated archaeological or cultural heritage site within 10 Km radius of the study area village.

4.5.18. Community & Institutional Consultation:

Village profiling and community consultation has been carried out in one village located in the proposed project area. Stakeholder consultation included discussion with Harwa & reevadi village panchayats, Anganwadi, educational institute and community health Centre etc. The list of stakeholders consulted for the proposed project is provided in **Table 27**.

Table 27: Telephonic Consultation with Stakeholders

Stakeholder type	Name & Designation	Department/Address	Date
Project Proponent	Mr. Abhishek (Project Head) Mr. Anil Mishra (Rajasthan Project head)	Representatives SBE Renewables Ten Pvt Ltd	05/06/2020
Land Aggregator	CS Bohra		04/06/2020
Revenue officer	Bheru Singh, Krishana Ram Bhadu	Patwari, Bherupura Hadwa Village & Reevadi Village	02/06/2020
Irrigation Department	Mr. Nakhta Ram	Irrigation Supervisor, Sajit	02/06/2020
Panchayat Members	Mr. Anoop Singh Rathor	Hadwa, Bherupura and Manihari	02/06/2020
Primary Sub Health Centre	Mrs. Anita Singh, ANM Teejo, ANM	Sajit Village & Reevadi Village	02/06/2020
Forest Range office	Mr. Jalan Singh	Forest Guard, Reevadi Village	02/06/2020
Primary School & Secondary School	Mr. Raju Ram Suther Mr. Ridmal Dan	Reevadi & Bhuiyasar Village	02/06/2020
Anganwadi Center	Ms Geeta Devi	Sajit Village	02/06/2020
Villagers	Swender Singh, Sarpanch Aman Singh, Sawai Singh Dilip Singh, Latez Khan Lalit Kumar, Aidaan Khan Mana Ram	Farmers of Reevadi Village	02/06/2020

Source: Primary consultation

Table 28: Stakeholders Consultation Contact details

Name	Designation	Village	Date
<i>kishana Ram Bhadu</i> Phone No: 9784692365	<i>Patwari</i>	<i>Rewari</i>	<i>25-06-20</i>
<i>Jalam Singh</i> Phone No: 9828484962	<i>Sarpanch</i>	<i>Rewari</i>	<i>25-06-20</i>
Tarachand Paliwal - general Phone No: 9983450402	villager	Rewari	26-06-20
Hari Singh – OBC Phone No: 9828490647	villager	Rewari	26-06-20
Parbat Singh Phone No: 9950138682	villager	Rewari	26-06-20
Nar Singh Rao Phone: 8890641519	villager	Rewari	26-06-20
Bhima Ram Phone: 7877374950	villager	Rewari	26-06-20
Satta Ram – ST	villager	Rewari	26-06-20

Phone: 9571452092			
Chala Ram – SC- Phone: 7665295761	villager	Rewari	26-06-20
Anup Singh Phone: 8118878433	Sarpanch	Harwa	25-06-20
Fakira Ram – ST Phone: 9549612494	Villager	Devka	25-06-20
Samda Devi – ST	Villager	Devka	25-06-20
Rasul Khan Phone: 9660117593	Villager	Juneju Ki Dhani	26-06-20

Source: Primary consultation

Consultations were carried out through physical site visit and telephonically with the locals, Anganwadi workers, primary health center, teachers and panchayat members at the study area villages arranged by project proponent field officers (Details given in **Appendix D**). Discussion was based on a set of questionnaires including project specific negative and positive impacts, socio-economic resource, and demographic profile of the village. Needs & expectations of local's along with the project development was also discussed.

During discussion, it was found that majority of stakeholder's consulted were aware about the upcoming Hybrid solar & wind project. Locals were aware that project would involve government revenue land and some government land for transmission line tower, access road, and pooling substation, which would be procured from the Rajasthan Revenue department on lease for 30 years. Land identification have been done and land lease process will start soon. The locals are also aware about the positive impact associated with the development of the project which would majorly bring a rise in direct and indirect employment /economic opportunities. At the same time, locals were not apprehensive on the health and safety risk associated with movement of heavy vehicles for transportation of solar/wind equipment's onsite and demanded proper health and safety plan.

Figure 4-36: Stakeholder consultations at project study area



Consultation with Sarpanch at Reevadi Village



Consultation with Local Villagers



Consultation with patwari in rewari for solar site



Consultation with sarpanch of Harwa for wind site



Consultation with Local villagers



Consultation with ANM Worker at Reevadi



Consultation with Primary School Teacher



Consultation with School Teacher at Reevadi



Meeting with Forest Officer & Irrigation Officer



Meeting with Anganwadi Worker at Reevadi



Consultation with Revenue Officer of Bherupura & Hadwa



Meeting with Local & Sarpanch of Hadwa/ Bherupura/ Manihari

Key Findings of Consultation

Some notable key findings of different level stakeholder consultation are appended below:

- SB Energy is the sole authority and responsible for all land related matter for the entire 450 MW Hybrid Power Project
- Government Revenue land will be sub leased to SBE for the proposed project.
- Animal Husbandry & Agriculture is the major livelihood resource of the study area village and also of the surrounding area. Almost 70-80 percent of population is involved in animal husbandry & agriculture, rest are labourers engaged in NAREGA.
- The main crops are jowar, bajra, til along with other crops included black grams and cumin,
- Agriculture is mainly dependent on rainwater and few places bore wells are available.
- Female literacy rate is much lower than male literacy rate in the study area village.
- Sanitation facilities are adequate in the study area villages.
- Scarcity of water is an issue in the study area village, especially potable water.
- Drinking water facility is now adequate in the Harwa village panchayat through tube well. A few scattered manmade wells/ponds are available and mostly used for drinking purpose for domestic animals.
- There is no community health centre available within the study area villages but, local people have to rely on ANM & Local quacks. To avail hospital facility, people generally visit to either Seo community health center (around 7-10 Km) and Barmer (around 20-25 Km) for Govt. and private hospitals.
- Education Facility: Rewari is having – 1 anganwadi, primary school, Senior secondary school. Schools are almost 2-3 km away from the site. Colleges are there in Jaisalmer and Barmer
- Based on the visual observation during site visit of Arcadis team and people's consultation, land parcels were devoid of settlements, hence, there is no such evidence of physical and economic displacement and resettlement witnessed for this project.
- As per discussion with Sarpanch (village head) 100 -150 ST families living in surrounding villages of wind site & around 8-10 ST families are living in surrounding village of solar site. During site visit, Arcadis held consultations with ST population (locally known as Bhil tribe) residing in Rivdi & Devka village. The consultation revealed that local ST community are not

socially secluded. They live with the mainstream population & have access to all common property resources. Also, as reported, no acquisition/procurement of ST land was planned/undertaken for the project. Considering the fact of not taking ST land in project, and no physical and or economical displacement of tribal populations is necessitated, therefore, no adverse negative impacts are envisaged.

- During site visit of Arcadis team, no notified Cultural Heritage site is recorded within the vicinity of the project. However, wind sites traverse through a number of religious common properties such as temples, mosques which though not of archaeological significance but nevertheless are significant to the local community. Kapuria math (temple) is located 15 km (approx.) from solar site

4.5.19. Needs Gap Assessment for CSR Initiatives

Analysis of above socio - economics description and local telephonic consultation in project area villages reveal that majority of the needs and expectations are linked with the fulfilment of basic needs and improvement of some infrastructural facilities at school/ Anganwadi/ health etc. levels.

SBE has its own CSR Policy. CSR initiatives shall be implemented in the project affected villages as per the policy. However, during discussion with villagers, Panchayat Members, anganwadi workers and ANM workers following gaps are identified which is mentioned in **Table 29**. Needs have been classified as high, medium and low to assess the further take up in the CSR study/initiatives.

Table 29: Key Needs/Gaps Identified

Key Areas	Gaps identified	Suggestions	Needs
Drinking water & Drainage system	<ul style="list-style-type: none"> • Limited no. of bore well/tube wells are available for drinking purpose in the study area. • There is no fresh/filtered drinking water available in the villages. Fluoride content in water is very high. • There is no drainage facility in the village 	<ul style="list-style-type: none"> • Providing additional drinking water facilities like more tube well and other drinking water facility with RO filters in affected village with help of concerned government dept. • Provision for better drainage facility. 	High
Education	<ul style="list-style-type: none"> • Lack of Higher Education facilities • Very low female literacy rate compared to male • Lack of skill development & vocational training in study area village • Lack of basic infrastructure facilities like drinking water, sitting arrangements, sports equipment, library & electricity etc. 	<ul style="list-style-type: none"> • Awareness program regarding female education at village level. This can be linked with vocational training programme in the study area village focussing on Weaker sections specially who belongs to SCs & STs. • Providing computer literacy program at village level • Providing functional Cultural Hall, drinking water facility, borewell, toilet facility, electricity, and tables & chairs 	Medium
Health	<ul style="list-style-type: none"> • Absence of health care facility in study area village which is affecting the basic health of the local people Major diseases are observed – Fluorosis, Malaria, dengue, Body 	<ul style="list-style-type: none"> • Organizing awareness camp on general health awareness. • Health camps or mobile health clinics can be provided. 	High

Key Areas	Gaps identified	Suggestions	Needs
	<p>Pain, and other general diseases are common.</p>		
<p>Agriculture/ Irrigation</p>	<ul style="list-style-type: none"> • Agriculture is dependent both on rain and irrigation. But the project affected village lacks inadequate irrigation system. 	<ul style="list-style-type: none"> • Rainwater harvesting should be planned wherever possible with the project site to improve groundwater recharge. 	<p>Low</p>
<p>Employment opportunities in the area</p>	<ul style="list-style-type: none"> • Only a few numbers of SHGs (all under Development of women and children in Rural Areas) are reported in the village • Majority of the youth population are unskilled and unemployed. • Labourers are mostly seasonal workers and migrate only for a short while in the nearby towns, either as artist or masons. 	<ul style="list-style-type: none"> • Organizing training/capacity building program for SHGs regarding entrepreneurship and linkages with bank. Separate training programme can be arranged for weaker section of social categories like SCs, STs, PHs etc. • Introduction of processing of dairy and other allied activities related to livestock where preference is given to Weaker sections. 	<p>Medium</p>

5. ANALYSIS OF ALTERNATIVES

The section gives analysis of alternatives with respect to the project. The following scenarios have been considered:

- Current or No Project Scenario
- Alternate methods of power generation
- Site suitability and justification for the project

5.1. Current or No Project Scenario

There is a need to bridge the gap between the demand and supply, renewable/non-conventional sources of power to supplement the conventional sources. The project intends to contribute towards bridging this demand supply gap being a non-conventional source of power generation.

The project presents an opportunity to utilize the potential for solar and wind power generation. A “No Project Scenario” will not address the issue of power shortage. An alternative without the project is undesirable, as it would worsen the power supply-demand scenario, which would be a constraint on economic growth of the surrounding region.

Rajasthan is rich in solar resources and solar energy will complement the conventional sources of energy in a large way. Also, maximum wind energy is generated in Jaisalmer and also in Bikaner and Barmer of western Rajasthan, with many private companies involved in the business. The State of Rajasthan is blessed with about 240 to 300 sunny days with good solar radiation of 5.08 to 5.77 kWh/m²/day. The solar energy potential in Rajasthan is estimated in excess of 18,382 MW. However, the actual potential for solar energy is significantly higher than the estimated capacity, considering the recent technological advances and increasing efficiencies brought in solar energy segments

5.2. Energy Security

In 2007 the Ministry of Environment Forests and Climate Change (MoEF&CC), Ministry of Power (MoP) and the Bureau of Energy Efficiency (BEE) issued a paper entitled ‘India: Addressing Energy Security and Climate Change’. In India the need for expanding the role of domestic Renewable Energy (RE) sources is a logical next step. Solar power is already in a position to provide a significant portion of India’s planned capacity addition up to 2030, with simple regulatory and grid modernization initiatives. Unlike oil, coal or LNG, solar power is not subject to fluctuating fuel prices which drain India’s limited foreign reserves, and in addition, solar power helps in reducing the carbon footprint of the economy.

5.3. Alternate Methods of Power Generation

There are various non-renewable and renewable energy sources which can be utilized for power generation. Each option has its own advantages and disadvantages. Based on the site conditions, availability of resources, environmental & social concerns and project cost suitable option for power generation need to be selected. Comparison of advantages and disadvantages of various non-renewable and renewable energy is represented in table given below.

Table 30: Advantages and Disadvantages of various non-renewable and renewable energy

Source of Energy	Advantages	Disadvantages
Coal	<ul style="list-style-type: none"> • Relatively cheap form of energy availability in large scale worldwide • Easily transported to power stations 	<ul style="list-style-type: none"> • Non-renewable energy source • Large water requirement

Source of Energy	Advantages	Disadvantages
	<ul style="list-style-type: none"> Reliable source of energy with steady output Coal is available in India 	<ul style="list-style-type: none"> High emission and generation of fly ash Source of greenhouse gases Mining of coal causes impacts on land and surrounding environment.
Oil & Gas	<ul style="list-style-type: none"> Oil and gas can be easily transported by pipes or ships. Natural gas is the “cleanest” of the fossil fuels 	<ul style="list-style-type: none"> Non-renewable energy source Working environment risks to staff and environment Burning oil and gas releases can cause pollution & health impacts Releases GHG and hence causes global warming and climate change India imports majority of Oil and Gas requirement and hence high dependency of raw material outside the country
Nuclear	<ul style="list-style-type: none"> Nuclear fuel does not create greenhouse gases when making energy. Only a very small amount of nuclear fuel is needed to make a lot of energy. Does not produce significant atmospheric pollutants. 	<ul style="list-style-type: none"> Expensive, especially in capital costs, maintenance costs The waste produced from nuclear energy is radioactive and Safe long-term disposal of nuclear waste can be difficult.
Solar	<ul style="list-style-type: none"> Energy from the sun is exhaustive & free. Solar energy does not create greenhouse gases. 	<ul style="list-style-type: none"> Only specified places are right for solar power. Solar energy cannot be produced at night
Wind	<ul style="list-style-type: none"> Wind power does not create greenhouse gases. The energy used to build one of the large turbines is repaid in 3-6 months. They last for 25 years. 	<ul style="list-style-type: none"> Need a lot of turbines to make electricity. Location specific resource Wind turbines can only be used where it is windy. On days where there is little wind, less energy will be generated.
Hydroelectric	<ul style="list-style-type: none"> Hydroelectricity creates no greenhouse gases. Energy from water is free and will not run out. Hydroelectric energy is more reliable than wind or solar power. 	<ul style="list-style-type: none"> Hydroelectric power needs enough water to turn the turbines. Dams are expensive to build. Building large dams can cause damage to water courses which affects people and wildlife and it can be difficult to find the right site. Small dams for local buildings on weirs do not have these problems.
Biomass	<ul style="list-style-type: none"> Biomass fuel is cheap and could use rubbish that we might otherwise throw away. Biomass fuels will not run out. Biomass crops that are grown absorb the same amount of pollution whilst they are growing as they release when they are burned, so do not create extra greenhouse gases in the atmosphere. 	<ul style="list-style-type: none"> Growing biomass crops needs a lot of space and could replace growing valuable food crops. Biomass fuels that are not grown (such as waste products) create greenhouse gases when burned.

The conventional sources of power generation have high environmental cost when compared to non-conventional sources like solar, wind, hydro, etc. its construction periods are longer with higher environmental risks from emissions. On the contrary power source from solar energy is most eco-friendly. It does not have any kind of emissions during operation. Wind power requires high wind zones

to be set up and micro siting along with detailed meteorological analysis is required which is very much favourable in Jaisalmer district, site selection for solar power is relatively easier there as well. Both Solar and Wind power energy is a clean power project with no emissions and feasible for the project area keeping in mind the good solar and wind potential in Jaisalmer, Rajasthan throughout the year.

5.3.1. Alternate Routes for Transmission Lines

As discussed with SB Energy official, the route of the transmission line will be selected keeping in mind the following factors

- Transmission line route is planned to avoid any habitations along the route
- No house or community structures are located under the transmission line
- Areas requiring extensive clearing of vegetation have been avoided
- Selection of the transmission route avoids any environmental sensitive site like schools, health centres, etc.
- Right of way/access roads will be shared with the common user of the substation.

The shortest possible route after considering the above factors will be selected for the transmission lines. Consideration of all the above factors will reduce the environmental and social footprint of the transmission line.

5.4. Site suitability and justification for the project

Solar- wind hybrid energy projects are site specific and its feasibility depends on a number of factors which can be broadly categorized as solar and wind resource assessment, land availability, cost of land and impact on community.

5.5. Conclusion

Various factors are considered such as solar and wind resource potential at the project site, favorable environmental and social settings, lowest GHG emissions in the project life cycle. Availability and suitability of solar and wind power potential, land and other allied infrastructure availability and various government supporting policies. Considering these factors, it can be concluded that the site is the good location for development of Hybrid power project.

6. ENVIRONMENTAL & SOCIAL IMPACT ASSESSMENT

6.1. Approach & Methodology

Primary impacts are assessed for a radius of 1 km around the project site and secondary impacts are assessed within the study area (10 km radius from project site). Also, 100 m RoW along the tentative transmission line route is also considered for impact assessment. IFC's safeguard policies require that (i) impacts are identified and assessed early in the project cycle; (ii) plans to avoid, minimize, mitigate, or compensate for the potential adverse impacts are developed and implemented; and (iii) affected people are informed and consulted during project preparation and implementation. IFC emphasizes on the use of a screening process as early as possible, to determine the appropriate extent and type of environmental assessment so that appropriate studies are undertaken commensurate with the significance of potential impacts and risks.

The methodology adopted to assess the significance of impact associated with project activities during construction and operational phase has taken following criteria into consideration. Details of screening criteria are given in **Table .**

Table 31: Screening Criteria for Environmental and Social Impact Assessment

Impact	Distribution of impact	Duration of Impact	Intensity
Low/ Short	Influence of impact within the project site boundary and RoW of Transmission line (Site)	Limited for duration of less than 6 months (Short)	Limited local scale impact resulting in temporary disturbance/ loss of environment/ social components (low)
Moderate/ Medium	Spread of impact within 2 km from the of the project site boundary (Buffer)	Impact may extend up to 2 years (Medium)	Local scale impact resulting in short term change and/ or damage to the environment components. (Moderate)
High/ Long	Influence of impact beyond 2 km from the project site boundary (Widespread)	Impact extends beyond 2 years (Long)	Regional impact resulting in long term changes and/ or damage to the environment components. (High)

6.1.1. Significance Evaluation Matrix

Significance evaluation matrix as shown in **Table 32** has been used to evaluate the significance of identified potential environmental impacts. This matrix includes criteria as discussed above to analyses the significance of impact. Color codes have been given to signify the impact intensity.

Significance of environmental impact has been analyzed and presented in further section of this chapter. The environmental impacts associated with the project activities have been identified and analyzed to evaluate their significance. Because of clean category projects, environmental impacts are very few with minor significance and can be controlled through mitigation measures.

Table 32: Impact Significance Matrix

Distribution	Duration	Intensity	Significance
Within Site	Short	Low	LOW
Within Site	Short	Moderate	
Within Site	Medium	Low	
Within Site	Medium	Moderate	

Distribution	Duration	Intensity	Significance
Within site	Long	Low	
Buffer area	Short	Low	
Widespread	Long	Low	
Within Site	Short	High	MODERATE
Within Site	Medium	High	
Within Site	Long	Moderate	
Within Site	Long	Low	
Buffer area	Short	Moderate	
Buffer area	Medium	Low	
Buffer area	Medium	Moderate	
Buffer area	Long	Low	
Buffer area	Long	Moderate	
Widespread	Short	Low	
Widespread	Short	Moderate	
Widespread	Medium	Low	
Widespread	Medium	Moderate	
Widespread	Long	Moderate	
Within Site	Long	High	
Buffer area	Short	High	
Buffer area	Long	High	
Widespread	Short	High	
Widespread	Medium	High	
Widespread	Long	Moderate	
Widespread	Short	Low	
Widespread	Short	High	
			NO IMPACT
			POSITIVE IMPACT

Table 33: Aspect Impact Matrix for Construction and Operation Phase

	PHYSICAL ENVIRONMENT									BIOLOGICAL ENVIRONMENT						SOCIO-ECONOMIC ENVIRONMENT					
	Aesthetics and Visual impacts	Air Quality	Noise Quality	Top soil removal / Soil Quality	Land Use	Local Drainage and Physiography	Surface water quality	Ground Water Resources	Ground water quality	Terrestrial habitat	Ecological Sensitive Areas	Aquatic Habitat and resources	Migratory Birds/Avifauna	Agriculture	Domesticated Animals	Loss of land and livelihood source	Common Property Usage Conflict	Local Job and Economic Opportunity	Cultural and Behavioral Conflict	Community Health and Safety	Occupational Health and Safety
A. Construction Phase																					
Land sub lease/purchase process					L					L						L	M				
Sourcing and transportation of construction material etc.		M	L	L						L							L	P		L	L
Storage and handling of raw material and debris	L	L	L	L																L	
Interaction of migrant labor with locals																	L	P	L	L	
Operation of DG sets		L	L	L																	
Access road construction		M	L	L	L					L							M	P			L
Site Clearance		M	L	L						L					M			P		L	L
Foundation excavation		M	L	M						L								P		L	L
Transformer yard construction		L	L	L																L	L
Substation construction		L	L	L																L	L
Laying of transmission lines																	L		L	L	L
B. Operation Phase																					
Vehicular movement carrying Officials on site during routine inspection, maintenance and operation of Wind - Solar Hybrid Power Project		L	L							L											
Periodic maintenance of all solar modules (washing modules)																		P			L
Maintenance of ancillary facilities such as store, yard, site office																					
Inspection of transmission lines													L								L
Security of Wind - Solar Hybrid Power Project in operation																		P			L
Operation of Wind - Solar Hybrid Power Project													M					P			L
C. Decommissioning Phase																					
Access roads and other components	L	M	L																		
Disconnecting and removal of Inverter Stations, Substation	P			P	M																
Loss of Jobs																		P	M	M	

6.2. Impacts on Physical Environment

6.2.1. Air Quality

Construction Phase:

In construction phase, various project components such as site preparation, transmission cable laying, switchgear, approach roads, internal road network and porta cabin construction will require land clearing, levelling, excavation, grading activities, vehicle movement and DG set operation. This results in an increased level of dust and particulate matter emissions, which in turn will directly and temporarily impact ambient air quality. If improperly managed, there is a risk of nuisance and health effects to construction workers onsite and to a lesser extent to nearby receptors from windblown dust (on the village access roads) due to transportation of raw materials. However, most of these project activities are expected to be restricted within the project boundary. Further, the movement of vehicles carrying raw materials on unpaved area within the project site and on access road causes fugitive dust emission and may extend to surrounding of project site like nearest settlements. Hence, the distribution of impact can be considered medium, duration of impact is short and intensity of the impact as medium. Since the impact is widespread, but for short duration and of low intensity, the impact can be termed of a **Moderate significance**, But the impact is reversible, and temporary in nature, if the following mitigation measures are adopted.

Mitigation Measures:

- Vehicles speed to be restricted to 20-30 km/hr on unpaved road.
- Raw material should be covered with tarpaulin sheet during transportation and in storage area.
- Ensure water sprinkling on unpaved area to minimize the dust emission.
- Fine materials (e.g. sand) should be covered during transportation.
- All the project vehicles shall have PUC. Regularly ensure maintenance of project vehicles during construction and operational phase.
- Turn off the machineries when not in use.

Operational Phase:

During operational phase, there would be minimal vehicular movement about 2-3 nos. project vehicles for O&M purpose. Since major source of emission into the ambient air will be absent during the operational phase therefore impact can be termed as insignificant.

Mitigation Measure:

- Restrict movement of vehicles on unpaved surface within the site.

6.2.2. Soil Quality

These impacts are associated with the project activities such as piling of module mounting structure and storage of diesel, spent oil or transformer oil.

Construction Phase:

During construction phase, Loose topsoil is generated due to excavation on project site due to site levelling for erection of module structures towers and access roads. The impact anticipated here is loss

of topsoil because of inappropriate storage. However, these activities and associated impacts are limited to be within the project boundary and during construction phase only. Considering the activities limited within the site, short duration of construction phase and low intensity, significance of impact is evaluated as **Low**. Soil contamination may result due to accidental spillage and inappropriate storage of diesel or used oil during construction phase. Improper handling of broken solar modules may also lead to soil contamination. However, distribution of impact within the project boundary and short duration of construction phase with low intensity makes impact of **Low** significance and can be controlled with the recommended mitigation measures:

Mitigation Measures:

- Use topsoil at the time of plantation and it can be given to nearby agricultural field after taking consent with the landowners/farmers.
- Plantation activities has been undertaken by SBE
- Store hazardous material like diesel and used oil in isolated room and on impervious surface to prevent seepage into project site soil
- Filling and transfer of oil to and from the container shall be on impervious surface
- Care should be taken with regard to possible changes in soil quality due to human activities, such as disposal of waste material and domestic effluents on soil of the surrounding area.
- Broken solar panels should be stored in paved surface and be handed back to manufacturers / authorised recycler within 15 days.

Operational Phase:

During operational phase, project activities such as excavation and usage of chemicals such as diesel and spent oil will be absent except chances of accidental release of used oil from transformer, therefore impact associated with these activities such as topsoil loss and soil contamination are minimal. Impact can be considered as insignificant. Improper handling of broken / damaged solar modules may also lead to soil contamination.

Mitigation Measure:

- Broken solar panels should be stored in paved surface and be handed back to manufacturers / authorised recycler within 15 days.

6.2.3.Noise Quality

The environmental impact anticipated in the project is the increment in ambient noise level due to various project activities.

Construction Phase

The major noise generating sources in the project are operation of vehicular traffic, and construction equipment like dozer, scrapers, concrete mixers, generators, pumps, compressors, rock drills, pneumatic tools, and vibrators. The project site is located amongst barren fields with no continuous noise generating sources in the vicinity of the project site. Assuming, the operation of these equipment's is expected to generate noise in a range of 75 – 90 dB (A) and it can be lower down from 90 dB(A) to 47 dB(A).

The project site is located on barren fields with no continuous noise generating sources in the vicinity of the project site. majority of the receptors are found to be rest house structures with temporary usage (seasonal usage as shelter during agricultural work) located near some of the WTG's.

Workers in close proximity to machines are prone to exposure of high levels of noise of machinery. This will be taken care by providing personal protective equipment like ear plugs/muffs and works will be rotated in shifts to avoid long term noise exposure.

Considering the short duration, localized distribution and low intensity, impact has been assessed as **Low** significance and can be controlled with the recommended mitigation measures:

Mitigation Measures:

- Use DG set with acoustic enclosure.
- Restrict major noise generating activities during night-time 10:00 pm to 6:00 am.
- Regular maintenance of project vehicles.
- Provide personal protective equipment (e.g., Ear plugs, Muffs) job rotation etc., to all workers wherever noise is generated due to machinery operation.
- Use of equipments /machines with inbuilt noise enclosure, wherever possible or provision of special acoustic enclosures for individual noise generating equipment's, wherever possible.
- Low noise equipment shall be used as far as practicable
- The number of equipment operating simultaneously shall be reduced as far as practicable.
- Workers should be prevented from continuous exposure to noise.
- During material movement, honking should be done cautiously to avoid disturbance to locals.
- In case of complaints of higher noise levels and uncomfortable received from the inhabitants of nearby settlements possibility of putting noise barriers near to the receptor need to be considered.

Operational Phase:

Any significant noise generating activity during operation of Wind - Solar Hybrid Power Project is absent therefore impact in terms of increment in ambient noise level is not anticipated during the operational phase of the project.

Wind turbines produce noise through a number of different mechanisms, which can be roughly grouped into mechanical and aerodynamic sources. Wind turbines noise could impact on annoyance, sleep and health of the residents at close proximity to the wind turbines. Reconnaissance survey highlighted majority of the receptors to be rest house structures with temporary usage (seasonal usage as shelter during agricultural work)

In India, there are no specific guidelines for wind power project noise levels. As per IFC's General EHS Guidelines: Environmental, Noise Management Noise, noise impacts should not result in a maximum increase in background levels of 3 dB at the nearest receptor location off-site.

Estimated noise generated during operation phase was calculated using Windpro software. DECIBEL is the module of the Windpro program used, which calculates the noise emission and checks if the noise requirements are met at neighbors and noise-sensitive areas. Furthermore, DECIBEL can calculate

and plot noise level curves for the project to enable an assessment of which areas will be prevented from being used for noise-sensitive activities in the future.

The assumptions made for modelling are:

- Noise modelling has been conducted assuming the fixed wind speed range.
- General Ground attenuation factor is considered as 1.0
- WTG plus ambient noise is compared to ambient noise plus margin
- Fixed penalty added to source noise of WTGs with pure tones
- Impact of Cumulative noise is considered at 10m receptor height.

The ambient noise levels measured at near WTG locations (SBE 39 and SBE 5) located in Devaka and Harwa village used as background ambient noise.




These ambient noise levels at village level were observed to be within permissible limits specified for Residential area as per Noise Pollution (Regulation and Control) Rules, 2000 (without project), However the increment in ambient noise level due to WTG operations is anticipated to increase up to a range of 1.7 to 3.8 dB(A), in night time during the operational phase of the project.





Based on the modelling result and ground truthing studies out of 7 identified receptors 2 locations seems to be temporary structure (Cattle shade, Agricultural house) and rest of the structures are permanent dwellings. Identification of structures depicted in **Table 34**.



The background noise levels at WTGs locations without project is expected to be within Residential area as per Noise Pollution (Regulation and Control) Rules, 2000, mainly due to absence of any noise generating residential, commercial, or industrial activity.

As per the Modelling results It is expected that with WTG operation there will not be any major increment in baseline noise levels near WTG locations and identified receptors considering the maximum background noise and still being well within the specified increment limit of 3 dB(A) as per IFC's General EHS Guidelines indicates the impact to be of low significance. Noise modelling results are depicted in **Table 34**. Noise modelling map is depicted in **Appendix E**

Table 34: Noise modelling results

Sr.No	Noise Receptors	Coordinates Noise Receptor	Impacting WTG	Sound Level Ambient+ WTG (dbA)	Additional Exposure	Type of Receptor	Google earth Photograph	Site Photograph	Site visit Findings/ Remarks
1.	SBE05_R1	717,836 E 2,917,731 N	SBE05	47.6	2.3	Permanent use Structure			Government office cum control building (Devaka)
2.	SBE 18 (1)	717,475 E 2,914,208 N	SBE 18	46.1	1.7				

Sr.No	Noise Receptors	Coordinates Noise Receptor	Impacting WTG	Sound Level Ambient+ WTG (dbA)	Additional Exposure	Type of Receptor	Google earth Photograph	Site Photograph	Site visit Findings/ Remarks
3.	SBE 39(1)	714,960 E 2,907,845 N	SBE 39	45.5	3.8				
4.	SBE65_R1	721,313 E 2,913,969N	SBE65	45.4	1.6	Permanent use Structure			Cluster of households (Near Juejo ki Dhani village)
5.	SBE65_R2	721,255 2,914,102	SBE65	45.7	1.9	Permanent use Structure			
6.	SBE65_R3	721,343 2,914,12945.7	SBE65	47.3	3.5	Permanent use Structure			

Sr.No	Noise Receptors	Coordinates Noise Receptor	Impacting WTG	Sound Level Ambient+ WTG (dbA)	Additional Exposure	Type of Receptor	Google earth Photograph	Site Photograph	Site visit Findings/ Remarks
7.	SBE_11_R1	717,958 E 2,916,445 N	SBE_11	48.4	4.6	Temporary use structure			Abandoned cattle shade

Out of 7 Identified receptors SBE_11_R1 and SBE 18 (1) are temporary structures and SBE05_R1 is found to be Government office hence very limited mobility expected during day time and hence it is interpreted that there will no impact to these receptors during operation phase of the project.

However, for permanent Structures such as SBE 39(1), SBE65_R1, SBE65_R2, SBE65_R3 following mitigation measures suggested.

Mitigation measures:

- Shifting WTG's to few meters out of setback distance 270 m.
- Regular maintenance of WTG would be carried out to make sure the parts have been well oiled to reduce friction between parts and generate excess noise.
- All nearby community will be informed about the GRM and the grievance would be addressed on priority bases.
- Plantation would be initiated around the turbine base area to absorb the noise generated by the turbines.
- In case of any complaint related to noise, appropriate measures should be taken to manage the same.
- Implement the recommended complaint resolution procedure (Grievance Redress Mechanism) to assure that any complaints regarding operational noise are promptly and adequately investigated and resolved.

6.2.4.Alteration of Natural Drainage Pattern

Topography of the project site can be characterized as mix (flat and mild undulations) therefore levelling or filling is expected to alter the natural drainage pattern.

Construction Phase:

During construction phase, site levelling activities, construction of underground reservoir will be carried out which in turn may result in change of contour level and natural drainage system. Therefore, change in contour level may affect the flow of surface runoff from project site. After the levelling and paving, increment in surface runoff is expected which should be diverted to the natural drainage/canal exists in nearby area. If it is not carried out, then surface runoff from the site may affect nearby landowners which may cause social agitation.

Considering the extent of impact outside of project boundary and high intensity, impact is considered as major significance and following mitigation measures are suggested to implement:

Mitigation Measures:

- Site levelling should be done with minimum alteration in contour level
- Design storm water drainage management system to discharge the surface runoff in the nearby natural drainage
- Do not disturb the natural drainage system
- The exit of runoff from the project site in the adjacent surrounding land area should be restricted

Operational Phase

In operational phase, project activities causing the alteration of natural drainage pattern will not exist, therefore associated impact is not anticipated.

6.2.5. Water Resources

Construction Phase

During the project construction phase, water is required for preparing RCC foundations for module mounting structures, building control room and security rooms, and domestic purpose such as drinking and washing by the construction workers and staff. During operations, robotic cleaning techniques will be used for cleaning of solar panels. Water will be required for domestic purposes by the operations staff. The indicative estimated quantities of water required during the construction and operation phases are presented below.

Phase	Activity	Max. Consumption
Construction	Civil works water requirement (53 WTG @ 60KLD/WTG)	3180 KLD
	Domestic use – drinking (during peak construction phase) considering 2900 persons @ 110 lpcd	319 KLD
Operation	Domestic use – considering 150 operation and maintenance (O&M) site personals and security guards @ 45 lpcd	6.75 KLD

Considering the limited distribution of impact (within the site), short duration of activities and low intensity, significance of impact is assessed as **Moderate**.

Operational Phase

In operational phase robotic cleaning of solar panel is planned by the developer hence water may require only for domestic use by labours. The water requirement would be approximately 9.9 KLD during operation phase for domestic use. Water will be required for domestic purposes by the operations staff. This will be met through borewells. Considering the distribution of impact in within the site, long duration with moderate intensity, significance of impact is assessed as **Low**.

Mitigation Measures:

- CGWB/CGWA approval needs to obtain in the event of extraction of ground water or installation of bore well water at site as a source of ground water.
- Construct of rainwater harvesting pit to recharge the ground water table.

6.2.6. Solid/ Hazardous Waste Disposal

Construction Phase:

Solid waste during the construction phase consists primarily of scrapped building materials, excess concrete and cement, excavated material, rejected components and materials, packing materials (pallets, crates, plastics etc.) and human waste. As consulted with representative of SBE, the broken solar panels will be properly packed and will be sent back to authorized hazardous waste recycler.

However, taking in consideration the impact within site, short duration and moderate intensity, the impact is considered as **Low**.

Mitigation Measures

- The excavated material generated will be reused for site filling and levelling operation to the maximum extent possible.
- Ensure contractual obligation that necessitates broken solar panels being accepted by manufacturer
- Use a 2-bin system so that food waste and recyclables viz. paper, plastic, glass, scrap metal waste etc. are segregated and stored in designated waste bins/ containers. The recyclables should be periodically sold to local recyclers while food waste will be disposed through waste handling agency.
- Waste/spent/used oil & bottom sludge from transformer will be collected and stored in paved and enclosed area and subsequently sold to SPCB authorised recyclers.

Operation phase:

There will not be any substantial generation of solid waste, other than insignificant domestic waste, and broken solar panels. The broken solar panels will be sent back to hazardous waste authorized recyclers.. Considering the limited distribution of impact (within the site), long duration of activities and low intensity, significance of impact is assessed as **low**.

Mitigation Measures

- Use a 2- bin system so that food waste and recyclables viz. paper, plastic, glass, scrap metal waste etc. are segregated and stored in designated waste bins/ containers. The recyclables should be periodically sold to local recyclers while food waste will be disposed through govt. approved waste handling agency.
- Ensure broken solar panels are properly packed and sent back to hazardous waste authorized recyclers.

6.2.7. Impact on Land and Land use

Construction Phase

During construction phase, impact on land use is anticipated due to various activities such as site levelling, filling and development of Wind - Solar Hybrid Power Project. Land use classification will change into industrial land use after the development of Wind - Solar Hybrid Power Project. Some impact on natural drainage system is also anticipated. Further, impact will be of long term and permanent in nature, but impact will not be of adverse nature.

Mitigation measures

- Changes in contour level should be avoided to the extent possible
- Maintain natural drainage system

Operation Phase

No impact on land use is envisaged during the operation phase.

6.2.8. Impact on Local Ecology

Construction Phase

The below aspects of the construction phase can have an impact on ecology

- Clearing and levelling of land
- Fencing of land
- Laying of solar module and WTG - foundation and erection
- Laying of transmission towers and transmission lines
- Creating access roads

The detailed explanation of the **significant** impacts is given below.

Destruction and Loss of Vegetation

The site is mainly open scrubby land due to not so fertile soil condition. Project construction involves land clearance, leveling, etc. causing the loss of vegetation. The clearance of vegetation will be restricted to the project site. Clearing of vegetation is also required for access route. Only scrubby vegetation can be found in the project site, and the level of impact generated from removal of topsoil (ground cover) can be termed as low as the species are very common and have least conservation value.

The livestock of the area mostly graze on grasses and other ephemeral herbaceous species and the loss of this ground cover will have a minimal impact as it will be for a very short period and the impact is reversible. Hence, impact on ecological environment due to vegetation clearance during construction phase is “**low**” from the project activities.

Disturbance to Fauna

IFC Performance Standard 6 recognizes that protecting and conserving biodiversity - the variety of life in all its forms, including genetic, species and ecosystem diversity - and its ability to change and evolve. This Performance Standard reflects the objectives of the Convention on Biological Diversity to conserve biological diversity and promote use of renewable natural resources in a sustainable manner. Performance Standard 6 is designed to protect and conserve biodiversity.

Construction and associated activity like movement of vehicle will be temporary in nature. Most of the mammalian species (Chinkara, Desert Fox, Indian Fox and Nilgai as reported in Bombay Natural History Society 4th May 2020 final report) were sometimes spotted around the project site as reported in), birds and reptiles those are named through primary and secondary sources are Least concern species under IUCN Red List and commonly found all over the region. Temporarily, they may abandon the project activity area during the construction period and migrate to nearby areas. Although the construction activity is of very short duration, activities are limited and confined but the area spread of the project site is large, thus the impact on these mammalian species from construction related activities be termed as ‘**Moderate**’.

During construction period due to added noise and vehicular movement domestic animals, wild reptiles may temporarily move away from adjacent suitable habitats but may recolonize once the construction phase is over.

Habitat Loss, Disturbance and Modification

Habitat loss due to wind turbines and associated infrastructures viz., turbine bases, substation and access roads is anticipated from such type of project. As the land requirement to setup the wind turbines are relatively low. Earth will be excavated for making roads, etc. and vegetation clearance will result in habitat modification in the study area. Moreover, project area is not a designated or qualifying site of national and international importance for biodiversity. Hence, from this aspect, the impact is “**Low**”.

Other Impacts

Due to influx of labour and project personal during the construction phase, there is a probability of “man animal conflict”. But the impact would be temporary and expected to be very minor and limited to the construction phase only.

Mitigation Measures

The following measures should be considered in the project design to mitigate the impact during construction phase due to the project:

- Project proponent should plan to build an appropriate level of fencing with lighting as a preventive measure to prevent man animal conflict.
- All project activities shall be undertaken with appropriate noise mitigation measures to avoid disturbance to faunal population (herpetofauna) in the region.
- If any nests of ground dwelling birds/reptiles are found the Forest Department is to be notified so that the birds don't get displaced.
- Activities generating high noise shall be restricted to daytime and will be mitigated to minimize the noise level outside the site boundary.
- Movement of construction and transport vehicles shall be restricted to dedicated paths to minimize any harm to small fauna within the site.
- Transportation of construction material shall be restricted to daytime hours in order to minimize noise and disturbance to fauna in the area.
- Temporary barriers be installed around the excavated areas so that the wildlife especially Nilguy and livestock is not trapped in pits.
- General awareness regarding natural resource conservation shall be enhanced through trainings, posters, etc. among the staff and labourers.
- Kitchen waste shall be collected and disposed in a manner that it does not attract scavenging animals.
- Temporary barriers shall be installed on excavated areas.
- The footprints of the construction activities shall be kept to minimum so as to reduce disturbance to flora and fauna.
- Forest department must be informed in case of any wildlife sighting or any incident involving wildlife.

Operation Phase

Impact

Impacts during operation phase are likely to be restricted to the maintenance activities within the project site like ground cover clearing under PV arrays and from internal road network within site. Apart from a relatively small direct loss of habitat, the shading of the soil by the solar panels is likely to impact reptile composition in these areas, as the shading is likely to alter soil temperatures which has direct implications for cold-blooded animals. Most reptiles are also sensitive to the amount of vegetation cover which is also likely to be affected by the arrays.

However, there is potential for avian distraction due to glare/ reflection from solar panels. PV solar energy facilities appear to be an “evolutionary trap” for birds who perceive them to be bodies of water on which they attempt to land. Insects, the prey of insectivorous birds, are also apparently attracted by this so-called “Lake Effect.” It might cause fatality or injury as birds contact the solar panels or surrounding ground as they attempt to land mistaking it for water (Upton, 2014). But the “lake effect” phenomena and its impact on avian fauna is very poorly understood, and detailed study is required to establish threat from such phenomenon.

Apart from this there could be significant impact on the avifaunal species due to the turbines and transmission lines.

Effect on Flora and Fauna:

On visual inspection during site visit, it appeared that there is no presence of any big trees in the project area; so, there is no chance of logging/ clearing of any trees for the construction of solar power project, But clearance of vegetation were going on during site visit. The proposed project site is not located in any environmental sensitive area. However, proposed project site is occupied by scrub vegetation, thorny vegetation was also observed during site visit. The scrub vegetation may be acts as extended area of the nearest reserve forest area i, e, Desert National Park which is located 30 km away from the proposed site. During site visit Chinkara, Deer and Nilgai was observed on site

Noise, vibration and emission from vehicles, equipment will occur during construction and pre-construction stages in temporary manner.

The impacts related to above activities are temporary and can be mitigated through following measures:

- Strict attention on worker force regarding disturbance to surrounding habitats, flora and fauna
- Selection of approved locations for material storage yards away from the environmental sensitive areas, and
- Avoid entering of construction waste (cement particles, rock, rubbles and wastewater) and sanitary waste to the surrounding water bodies.

Impact on Terrestrial Ecology:

The temporary phase would not result in any adverse impacts on the flora and fauna within or around the proposed project site, provided dust suppression measures and other procedures are followed.

The impact is of low significance and temporary in nature.

There is absence of sensitive ecological area (Reserve Forest area) in the core area of project. The removal of herbaceous vegetation from the soil and loosening of the topsoil generally causes soil erosion. However, such impacts would be primarily confined to the project site during initial periods of the construction phase and would be minimized through adoption of mitigation measures like paving and surface treatment and water sprinkling. Also, recommendations will be provided with list of tree species that can be planted to improve terrestrial ecology and vegetation cover of land.

Impact on Avian Habitat:

Wind turbine operation has few direct and indirect impact on bird and bat communities. Bird and bat mortalities has been reported from various operational wind farms across the country. The impacts during operation phase of wind farm is discussed in the sections below. The impacts of wind farm on the birds and bats identified the main potential hazards as:

- Disturbance & displacement
- Collision mortality
- Loss of habitats resulting from wind turbines and associated infrastructure

Disturbance & displacement

According to Birdlife International's report on effect of wind farm impacts on birds, these effects are variable and species, season and site specific. Disturbance can lead to displacement and exclusion from areas. Human activity during the installation of wind turbine such as movement on access roads may also lead to disturbance.

Noise generating from turbines affect birds and bats from using an area close to these. The effect of birds altering their migration flyways or local flight paths to avoid wind farm is another type of displacement. This effect depends on species, type of bird's movement, flight height, distance to turbines, wind force and wind direction etc. This can be highly variable ranging from a slight check in flight direction, height or speed to significant diversions which may reduce the number of birds using areas beyond wind farm. Some study indicates alteration of flight line whereas some other studies says birds will fly between turbines rows (Christensen et al. 2004, Kahlert et al. 2004a).

Collision and Electrocuting risk due to Transmission Lines

The collision mortality and electrocuting risk is another impact due to wind power project, especially in area of more bird usage i.e. Important Bird Area (IBA). Direct mortality or lethal injury of birds can result from collision with rotor, towers, nacelles and associated infrastructure such as guy cables, power lines and meteorological masts. Although majority of studies indicates low mortality level from wind turbines (Painter et al. 1999, Erickson et al. 2001). Collision risk depends on a range of factors related to bird species, numbers and behaviour, weather condition, topography and scale of wind farm.

Avian electrocution occurs when a bird's wingspan completes a circuit between energized and/or grounded structures, conductors, hardware, or equipment (Avian Power Line Interaction Committee 2006) and is typically a problem with lower voltage distribution lines where the typical distance between conductors is 2 to 6 feet. Avian electrocution is not an issue with high-voltage transmission lines, because the typical distance between conductors is about 12 feet. Even the largest local birds do not have a sufficient wing span to touch two conductors simultaneously and be electrocuted. Types of transmission lines are provided in Figure 6-1.




Figure 6-1: types of transmission lines

According to the avian habitat reported in *Late Winter Season Report - Bird surveys at the proposed hybrid project sites in Reewari and Devaka, Rajasthan* by Bombay Natural History Society and primary observations, the overall impact on avian habitat due to the project activity during the operational phase is Moderate which can be further confirmed after a detailed bird and bat study to gather more concrete information on bird species, their abundance diversity, local migrating flying path, nesting & breeding areas, flying height and flying duration. Client has undertaken winter season avifaunal study through BNHS.

Mitigation Measures

- Vegetation clearing through brush cutting for maintenance activities shall be done manually wherever possible (not applicable in this site, as there is absence of any green vegetation and land in barren)
- Any areas which vegetation cover do not have shall be re-vegetated with locally occurring species and monitored to ensure recovery is taking place.
- Vegetation that needs to be reduced in height shall be mowed or brush-cut to an acceptable height, and not to ground level except where necessary (not applicable in this site, as there is absence of any green vegetation and land in barren)
- General awareness regarding wildlife and natural resource conservation shall be enhanced through trainings, posters, etc. among the staff and labourers.
- Solar panels shall have an anti-reflective coating to minimize the light reflecting off of the panels so that there is very less impact due to glare from the panels.
- Moreover, to minimize effect of “Lake effect”, visual frightening techniques” may be considered to frighten any bird trying to land on panels and prevent birds from landing.
- Fencing and lighting along the project boundary must be properly maintained all through the project lifecycle.
- Above ground wiring, if any should be provided with markers to avoid chances of perching of birds and avoid electrocution;
- Daytime visual markers, visibility enhancement objects such as marker balls, bird deterrents, or diverters shall be installed on any guy wires and transmission lines to enhance visibility of towers/transmission lines for bird. to avoid avian collision;
- Daytime visual markers shall be provided on any guy wires used to support towers to enhance visibility of towers for bird. Visibility enhancement objects such as marker balls, bird deterrents, or diverters shall also be installed along the transmission line to avoid avian collision;
- Use of reflectors and bird flappers to be used at suitable intervals to avoid easy visibility of transmission wires and the risk of electrocution.
- Additionally, installation of insulator capacitors (Jumpers) at the cut point will reduce the risk of electrocution.
- The tip of blades of WTGs should be painted to increase visibility and avoid collision. This is also done for established aircraft navigation path.

- Any dead animals/carcass shall be removed in time from the site so that it does not attract movement of raptors near to the WTGs
- While planning project transmission lines, feasibility should be checked for avoiding water bodies crossings. This can be considered for water bodies that could be important when they turn into suitable habitats.
- Native vegetation must be planted or allowed to grow around the wind-turbines, such that their canopy screens potential prey on the ground from raptors flying overhead.
- Appropriate storm-water management measure shall be implemented to avoid creating ponds which can attract birds and bats for feeding or nesting in the windfarm area
- Training of local staff and security guards for spotting of bird carcass and reporting the same. This will help to ensure the strategic actions when the species are spotted in the region.
- Towers be regularly checked to avoid any nesting in any suitable gaps or platforms.
- Flash lamps on the WTGs should be installed to reduce the collision risks during nights.

Green Belt Development: Greenbelt is recommended as one of the major components of ESIA, to enhance environmental quality attenuation of noise levels, balancing eco-environment, consumption of treated effluent, prevention of soil erosion, and creation of aesthetic environment. An ideal greenbelt always imparts scenic beauty besides providing roosting/perching place for birds and ground surface for naturally available reptiles, other flora and fauna species, to make the area more natural and hazard free. Greenbelt of maximum 2.0 m width can be considered to be developed around the periphery of project boundary with comparatively low height trees & shrubs and no restriction of tree height along the project access road with local species for better survival.

Table 35: Details of Plantation Recommended for Greenbelt

Botanical Name	Local Name	English Name
<i>Acacia auriculiformis</i> A. Cunn. ex Benth.	Bangali baval	Australian wattle
<i>Acacia nilotica</i> (L.) Willd ex Delile ssp. indica (Benth.) Brenan		<i>Acacia nilotica</i> (L.) Wild ex Delile ssp. Indica (Benth.) Brenan
<i>Aegle marmelos</i> (L.) Corr.	Bili	Bael tree, Golden apple
<i>Ailanthus excelsa</i> Roxb.	Moto Arduso	Tree of Heaven
<i>Albizia lebbeck</i> (L.) Benth.	Kalo saras, Siris, Moti Haradi	Indian walnut and Parrot tree
<i>Albizia procera</i> (Roxb.) Benth.	Gular, Kilai	
<i>Azadirachta indica</i> A. Juss.	Limdo	Neem
<i>Bambusa arundinacea</i> (Retz.) Willd.	Kanti vaans	Bamboo tree
<i>Boswellia serrata</i> Roxb. ex Colebr.	Gugal, Dhupelio, Salai	Incense tree Butea
<i>Butea monosperma</i> (Lamk.) Taub.	Kesudo, Khakharo, Palas	Flame of the forest
<i>Callistemon citrinus</i> (Curtis.) Skeels	Bottle brush	Bottle brush
<i>Cassia auriculata</i> L.	Aval	
<i>Cassia fistula</i> L.	Garmalo	Golden shower
<i>Casuarina equisetifolia</i> L.	Mayurpankhi, Sharu	Beef- wood tree
<i>Commiphora wightii</i> (Arn.) Bhandari	Guggal	

Botanical Name	Local Name	English Name
Cordia gharaf (Forsk.) Ehrenb & Asch.	Nani gundi	
Emblica officinalis Gaertn.	Amla	Indian Gooseberry
Eucalyptus globulus Labill.	Nilgiri	Tasmanian blue gum tree
Gliricidia sepium (Jacq.) Kunth ex Walp	Gliricidia	Gliricidia
Gmelina arborea Roxb.	Sevan	Malay- Bushbeech, white teak
Lagerstroemia indica L.	Chinai mendhi	
Madhuca indica J.f.	Mahudo	Mowra butter tree
Manilkara hexandra (Roxb) Dubard.	Rayan	
Melia azedarach L.	Bakan limdo	Persian Lilac
Morus alba L.	Shetur	White mulberry
Parkinsonia aculeata L.	Rambaval	Horse bean tree
Phoenix acaulis Roxb. ex Buch. -Ham.		
Pongamia pinnata (L.) Pierre	Karanj	Indian beach
Prosopis cineraria (L.) Druce.	Khijdo, Shami	
Prosopis juliflora (Swartz.) DC.	Gando baval	Mesquit
Punica granatum L.	Dadam	Pomegranate
Salvadora oleoides Decne.	Mithijar	
Salvadora persica L.	Piludi	Toothbrush tree
Sapindus emarginatus Vahl.	Aritha	Soap-nut tree
Tamarindus indica L.	Khati amla	Tamarind
Terminalia arjuna (Roxb. Ex DC) Wight & Arn	Arjun	
Thespesia populnea L.	Paraspiplo, Pardesi bhindi	
Vitex negundo L.	Nagod	Chaste Tree, Vitex
Ziziphus mauritiana Lamk.	Bor, khatibor	The Chinese date

The following measures should be considered in the project design to mitigate the avian species impact due to the project:

Overall Impact Assessment

The overall assessment suggests that the proposed project will not lead to significant displacement of habitat for birds and the impact on faunal species and vegetation is moderate. Also, loss of habitat is not anticipated for mammals and other avifauna. Based on above discussion, the impact on ecology during operation phase of the project is envisaged to be Moderate.

Phase of the Project	Risk Assessed
Construction	Moderate
Operation	Moderate

6.2.9. Socio - economic Impact

Key Social Impact

Socio-economic impact assessment is designed to assist communities in making decisions that promote long-term sustainability, including economic prosperity, a healthy community, and social wellbeing. To assess and understand the social impacts associated with the project, social indicators have been identified and analyzed.

(A) Loss of Land/ Livelihood Conflict

Construction Phase: Approximately 1100 Ha. of government revenue lands will be leased by RRECL to SBE for development of proposed 450 MW Hybrid Power Project. Land in the proposed project influenced area is predominantly barren and unused. Grazing activities are limited to post-monsoon months when adequate vegetation is present. Agriculture in the area is majorly dependent on rain and large portion of the land remains barren most part of the year. There were no habitation or cultivation land observed in land parcels where the development of the project is proposed.

Consultation were carried out with project proponent, land aggregator, land revenue & irrigation department representative as well as with the community including the panchayat members, there is no private land is involved in the project and other livelihood activities are not envisaged on the proposed government land. Though no evidence of physical or economic displacement was noticed during public consultation.

Based on the consultation with landowners, it was reported that no land parcels were leased from people who belongs to the scheduled tribes community (Bhil community).

Hence, considering all the above points neither physical nor economical displacement is envisaged. Hence, taking the distribution of impact as within site for short duration and medium intensity, the impact significance can be termed as '**LOW**'.

Mitigation Measures:

- Stakeholder engagement plan and community development plan should be implemented project affected village
- It should be ensured that maximum employment is to be provided to marginalised and vulnerable communities like Schedule caste and schedule tribes and the locals as per their capacity and skill set.
- It should be ensured that the villagers/locals are given first preference towards employment followed by the neighbour communities.
- Grievance Redressal Mechanism will be followed onsite.
- Complaints from the locals should be timely registered, investigated and resolved.

Operation Phase

There would be no impact on land during operation phase. There would be a requirement of security guards for plant site, hence local employment opportunity would be generated, and this would be a **Positive** impact of the project as it would enhance the economic opportunities to the locals.

Mitigation Measures:

- SBE has their own CSR Policy. CSR initiatives shall be implemented in the project affected village as per the policy.
- Community development plan should be implemented.

- SBE to ensure that benefit may be in the form of financial, employment opportunity, training should be given on priority to the landowners who belongs to tribal category.
- It should be ensured that maximum employment preference is given to the locals as per their capacity and skills useful for project, wherever possible.
- Grievance Redressal Mechanism should be followed onsite.
- Complaints from the locals should be timely registered, investigated and resolved.

(B) Engagement of Local and Migrant Labour

Construction Phase:

The social impact associated with the engagement of local and migrant labour in the project is conflict between labour and contractor or developer which in turn may result in suspension of project and reputational risk on project developer. Considering the project in construction phase indicators have been discussed to provide sense of what should not be done with respect to labour engagement. The issues discussed here in the form of indicators IFC PS 2 and ILO guidelines. The distribution of impact is buffer area, duration is short, and intensity is moderate, the impact significance can be termed as “Moderate”

Considering the sensitiveness associated with the engagement of child, forced labour, SBE has laid down policies through which it demonstrates compliance to all of the above factors. Its contractors should be made aware of all its policies for labour requirements and incorporated in their contracts prior to the starting of the project. SBE need to monitor the implementation of the policies on regular basis.

Mitigation Measures:

- Employment will be provided to local people wherever possible, especially as unskilled construction workers and security guards
- SBE should include clause or provisions related with non-engagement of forced and child labour, gender equity, non-discrimination on employment and opportunity and freedom to express their view in contractor's agreement and HR policy
- SBE through its contractors should ensure that labour is being adequately paid by contractors. Also, ensure that wages are being paid as per the requirement of minimum wages act.
- SBE will conduct internal audits as when required to monitor the performance of contractor.
- SBE through the contractor will inform the labour about emergency preparedness plan and communication system to be followed during emergency
- SBE through contractor should ensure that labour receive training on health and safety issues involved in the project.

Operation Phase

Locals are hired as security guards and unskilled job for both the project site. Moreover, there is no direct conflicting issues between the Locals and the Project Proponent

This will enhance the local employment and would be a **Positive Impact**.

(C) Labour Accommodation Offsite

Construction Phase:

There may have some chances of conflict between the migrated labours and the local community arise during staying of migrant labours in the nearby village. Considering the possibilities of such conflicts

and the existing situation the distribution of impact is buffer area, duration is short, and intensity is moderate, the impact significance can be termed as “**Moderate**”

Considering the sensitiveness associated with the engagement of child, forced labour, SBE has laid down policies through which it demonstrates compliance to all the above factors. Its contractors should be made aware of all its policies for labour requirements and incorporated in their contracts prior to the starting of the project. SBE need to monitor the implementation of the policies on regular basis.

Mitigation Measures:

SBE will monitor and supervise to avoid any conflict between migrated labour and local community.

(D) Social Issues Regarding Right of way and Such Matter

Construction Phase:

It was observed during site visit, the project site is located far distance from any human habitation and cultivation field. Hence, there is no chance regarding issues arise on Right of Way for transmission line etc. and thereby obstruction of places of importance at entre of the Project Site. Considering the existing condition and the records, information that has been received from the Project Proponent) of the Hybrid power project the impact significance can be termed as “**Low**”.

Mitigation Measures:

- The layout for access roads and transmission lines should consider minimum land requirement and should avoid procurement of agricultural land;
- Site Management should ensure that all agreements will be executed properly and documented
- Any waste generated during the construction phase should not be accumulated near the religious structure as this might affect the sentiment of the locals.

(E) Community Engagement

Construction Phase:

This probable impact is applicable throughout the project life. The project influenced area is home to communities from various castes and religions.

At any stage of the project, preference, and bias towards certain communities over others for labor, business or CSR initiatives could result in communal disharmony. Grievance Redress Mechanism should be developed to effectively deal with the communities' concerns, grievances and keep them adequately informed about the project. In case of an absence of an efficient information disclosure mechanism and grievance redressal mechanism, the stakeholder engagement process is likely to get hindered, consequently, preventing a healthy relationship between the company and local community.

During construction phase, the distribution of impact is buffer area, duration short and intensity moderate, the impact significance can be termed as **Moderate**.

Mitigation Measure:

- To ensure an open and effective communication between the local populations and SBE, a documented grievance redress mechanism must be adopted at the site level for external stakeholders such as the local community.
- Furthermore, the local community must be kept informed of the project and its relevant details, with information disclosure meetings being necessary prior to every major stage of the project.

Operation Phase

During operation phase, very limited employees will be employed on site and limited movement of project employees will take place, mainly for maintenance activities.

The distribution of impact is buffer area, duration long and intensity very low, the impact significance can be termed as **Low**

Mitigation Measures:

- To ensure an open and effective communication between the local populations and SBE, a documented grievance redress mechanism must be adopted at the site level for external stakeholders such as the local community.

6.2.10. Health and Safety Impact

Occupational Health & Safety Hazards for workers

Construction Phase:

Occupational Health and safety hazard associated with project activities (during construction) in Wind - Solar Hybrid Power Projects are identified as follows:

- **Electrocution and Firing due to short-circuit:** It should be ensured that proper training be given to workers before they initiation of any project activity as well as the workers wear their appropriate Personal Protective Equipment (PPE) viz. helmets, safety jackets, safety shoes, goggles, gloves etc. as per their nature of work involved.
- Possible injuries associated with working with transmission line laying.
- Accidents during cutting, chipping and piling.
- **Physical injuries:** These can occur when workers involved in loading/unloading activities don't adhere to proper ergonomics discipline. Injuries like muscle strain, ligament tear, slip disc can occur which may prove to be fatal.
- **Trip and fall hazards:** The injuries are similar to those discussed under working at height. They occur when workers trip over/fall when debris etc. lies in the walkway/ passages.
- **Diseases due to unhygienic condition:** It should be ensured that proper and adequate number of toilets should be constructed for the labourers so that hygienic conditions prevail in the site area.
- **Violation of privacy and dignity of women involved:** There can be a violation of the privacy and dignity of the women involved in the work force as there is no enclosed or exclusive provision for women. SBE following their Environment, Health and Safety ("EHS") Management Policy and abide by the IFC Principles and Standards will ensure that the dignity and privacy of women is maintained through separate and protected provision for Sanitation Facilities during operation phase of the project as well as in other future projects of SBE .

Also, there can be dissatisfaction among the labourers due to many conflicts/issues unresolved, hence there should be a complaint register onsite. Contractor of SBE should ensure to have regular medical check-up of their hired labourers. SBE and/ or their contractor should ensure to have regular medical check-up of their hired labourers. Hence, taking the distribution of impact as within site, duration as short and intensity as moderate, the impact significance can be taken as **Moderate**.

Mitigation Measures

- All material will be arranged in a systematic manner with proper labelling and without protrusion or extension onto the access corridor.
- Loading and unloading operation of equipment should be done under the supervision of a trained professional
- All work at height to be undertaken during daytime with sufficient sunlight.
- Proper PPEs should be provided to all workers.
- There should be periodic training to educate the workers for proper use of PPE's.
- There should be a proper monitoring system to ensure that each and every individual labourer is using the PPEs properly.
- Fire extinguishing equipment should be provided in adequate number on site to handle any possible fire outbreaks
- An accident reporting and monitoring record should be maintained.
- Display of phone numbers of the city/local fire services, etc. at site should be done.
- The labour engaged for working at height should be trained for temporary fall protection devices.
- There should be an arrangement for hygienic and sanitation facilities for all the labourers working in the site.
- There needs to be an enclosed and exclusive provision for women to protect the privacy and dignity of the women involved in the work force.
- Provision of the Contract Labour Rules, 1971 requires the operator of a construction site to provide adequate sanitation facilities to workers within the site premises
- SBE should inform the labour about the Grievance Redressal Mechanism (GRM) by which they can inform about any grievances.
- SBE should ensure that labour receive training on health and safety issues involved in the project.
 - SBE should inform the labour about Emergency Preparedness Plan (EPP) and communication system to be followed during emergency situation.
 - SBE should involve their EHS person/site EHS representative as mentioned in their Policy.

Operation Phase:

Occupational Health and safety hazard associated with project activities (during operation) in Wind - Solar Hybrid Power Projects are identified as follows:

- **Electrocution/ Electrical Shocks:** These may occur when the skin comes in contact with live power lines etc. The severity of the burn depends on voltage, current, time of contact etc.
- Firing due to short-circuit.
- Possible injuries associated with working at height.
- Diseases due to unhygienic condition

The impact significance can be taken as **Moderate**.

Mitigation Measures:

- Provide and ensure wearing of personal protective equipment's viz., gloves, helmets, ear plug, safety belt etc.
- Ensure effective work permit system for critical activities such as electrical work and working at height.
- Prepare emergency communication system and emergency preparedness plan.
- Ensure proper sanitation facilities.
- Drinking water needs during the construction phase will be met via local tankers/approve vendors. In operational phase, packaged drinking water will be made available for the drinking purpose.
- SBE will implement Environmental Social Management System (ESMS). Following that an Emergency Preparedness Plan to deal with health and safety issues during project life cycle of a Wind - Solar Hybrid Power Project will be built.
- SBE will ensure that they abide by the policy of safeguarding all issues regarding the health and safety of the workers who are working under the Projects.
- Emergency Preparedness and Plan for On-Site Emergencies: the plan has defined nature of emergencies that can be encountered during operation of a solar farm. Requirements of an Emergency Control Centre (ECC), firefighting facilities and medical facilities has also been detailed out. Roles and Responsibilities of personnel at site, communication channel to be followed, and procedures for different emergencies have also been detailed. SBE should ensure that all its hired contractors should abide by the requirements of plan formulated like undertaking mock drills, identification of first aiders and fire fighters, display of emergency numbers onsite etc.

(C) Community Health & Safety

Construction Phase:

During construction phase, various project components such as transmission cable laying, switchgear, approach roads, internal road network and porta cabin construction require land clearing, levelling, excavation, grading activities, vehicle movement, DG set operation will take place. This will result in an increased level of dust and particulate matter emissions, as well as high traffic load, which in turn will directly and temporarily impact the local community. If improperly managed, there is a risk of nuisance and health effects. Taking the distribution of impact as within site, duration as short and intensity as low, the impact can be considered as "**Low**".

Mitigation Measures

- Identify route for movement of project vehicles which, should not include narrow village road and road passing through cluster of settlements.
- Depute traffic escorts as and when required near project site and major settlements to guide movement of project vehicles.
- Keep limited speed of project vehicles near settlements and within the project site.
- Provide necessary training to the drivers for speed restrictions and on do's and don'ts.

Operation Phase

- **Traffic Movement:** In operational phase, very few (2-3 nos.) of vehicles will be required for commuting from home to site office. Therefore, impact associated with movement of project

vehicles is not anticipated. Besides, there may be impact due to restriction in public access but considering (as informed during interaction) SBE Energy Projects Private Limited will construct strengthen existing roads within the village connecting the main roads and between places with different Project sites.

- **Risk of Electrocutation:** Risk of Electrocutation is anticipated in the operational phase of the project, which could be mitigated through boundary wall and restricted entry in project site.
- Taking all these points in consideration, with distribution buffer area, duration short and intensity low, the significance of impact can be taken as **Low**.

According to IFC EHS guidelines, community health and safety hazards specific to wind energy facilities primarily include the following during the operation phase:

- Shadow flicker;
- Blade throw;
- Electromagnetic interference and radiation; and
- Public access

Shadow Flicker:

Shadow flicker refers to the shadows that a wind turbine casts over structures and observers at times of the day, when the sun is directly behind the turbine rotor from an observer’s position. The shadow flicker effects usually during periods after sunrise and before sunset. During intervals of sunshine, wind turbine generators will cast a shadow on surrounding areas as the rotor blades pass in front of the sun, causing a flickering effect while the rotor is in motion. The light effect caused when the sun is positioned behind a rotating wind turbine has been described as shadow flicker. With the sun in the background, large moving shadows can be produced which some people may find distasteful. The **Table** below shows the approximate sensitivity to shadow flicker at different RPM for three blade turbines, according to Stankovik et. al.

Table 36: Shadow Flicker Sensitivity

Flicker Rate (Hertz)	Human Perception	Equivalent RPM Rate for a 3-Bladed Turbine
< 2.5	Negligible Effect	<50
2.5 - 3	May Affect 0.25% of the Population	50-60
3 - 10	Effect is Perceptible	<200
10 - 25	Greatest Sensitivity	200-500
>50	Continuous Light Source	1000

Source: Stankovik et al., 2009,

Larger turbines generally operate between 18 and 45 RPM, while smaller turbines generally operate below 150 RPM (Stankovik et al., 2009, p.96). So, the effect is expected to be negligible.

It has been stated that “*Flicker effects have been proven to occur only within ten rotor diameters of a turbine*”. The greater the distance between the turbines and the observer the less noticeable the shadow flicker will be (Office of the Deputy Prime Minister, 2004, p.177)¹.

¹ *The Real Truth about Wind Energy, A Literature Review on Wind Turbines in Ontario, June 10, 2011, SIERRA Club Canada.*

Modelling was undertaken using Wind Pro, for shadow flickering using real case scenario. The sensitive WTG locations resulted from the analysis of worst-case scenario outcome will then be used as input in real scenario approach. The outcome of real scenario approach will be in the form of expected hours of shadow flickering on identified receptors. To run the real case scenario for shadow flickering following data have been used in software:

- Annual operational hours estimated for WTGs
- Sunshine hours of project site/nearby location

The real case scenario result will be then analyzed with respect to cumulative impacted receptors and sensitive locations of WTGs. The maximum no. of hours (more than 30 hrs./year²) of shadow flickering occurrence in real scenario will be considered as **significant cumulative impact on the receptors**. The locations of WTGs contributing the significant cumulative impact will be identified and mitigation measures will be delineated for such locations.






SHADOW FLICKERING MODELLING RESULTS AS PER WTG LOCATIONS IDENTIFIED DURING January 2020.



Shadow Flicker Modelling results show that out of 7 identified receptors 3 receptors will receive shadow for more than 30 hours per year from 10 WTGs. However, majority of the receptors identified during site survey are Temporary use structures (Pump house, resting shade, Agricultural storage) located within 300 m radius of WTG's. The modelling results is provided in is provided in Error! Reference source not found. **G**.

WTG profiling of all locations was undertaken based on Ground truthing and desk-based study. Site visit was undertaken to understand the status of receptors, from this study. However as per the WTG profiling carried out on site by SBE and Arcadis, two receptors found to be sensitive SBE 5 R1 and SBE 65 R3 as it is a permanent structure (Government office cum control building, Residential House,). SBE_11_R1 are found to be temporary use (cattle shade). Impacting WTGs with status of receptors are provided in below **Table** .

² Dutch standards of 30 hrs/year was used in analysis of significant impact. In, India shadow flickering standards are not available

Table 37: Shadow Flickering Modelling Results Detailing the Shadow Hours Received at the Receptors wrt to the Nearest WTG Locations

Sr.No	Shadow Receptors	Coordinates Shadow Receptor	Shadow hours per year (h/year)	Impacting WTGs	Distance (m)	Type of Receptor	Google earth Photograph	Site photographs	Site observations
1.	SBE05_R1	717,836 E 2,917,731 N	147:43	SBE05 SBE06 SBE07	155 543 906	Permanent use Structure-			Government office cum control building (Devaka)
2.	SBE65_R3	721,343 E 2,914,129 N	60:15	SBE60 SBE62 SBE65	1893 1363 140	Permanent use Structure		 	Cluster of households (Near Juejo ki Dhani village)

Sr.No	Shadow Receptors	Coordinates Shadow Receptor	Shadow hours per year (h/year)	Impacting WTGs	Distance (m)	Type of Receptor	Google earth Photograph	Site photographs	Site observations
3.	SBE_11_R1	717,958 E 2,916,445 N	47:53	SBE13 SBE12 SBE11 New 3	905 1130 106 839	Temporarily use structure			Abandoned Cattle shed

Mitigation Measures

- Ensuring effective work permit system for critical activities such as electrical work.
- The impact of shadow flicker received by the structure will further be reduced if there is closed wall/opaque structure where in the light/shadow would not penetrate/directly affect the receptor. The source of shadow flicker would be through window's, open roof and doors.
- Provide curtain and blinds in households with open roof, and windows, doors facing WTGs.
- Boundary Wall and restricted entry in project site
- Prepare emergency communication system and emergency preparedness plan should be framed.
- It is recommended that SBE Renewables Ten Pvt. Ltd should formulate a complaint resolution procedure for the local community so that any issues or concerns associated with shadow flicker are reported to the site staff. SBE Renewables Ten Pvt Ltd will ensure that appropriate and timely action is taken in case of receipt of such complaints.
- Undertake plantation to hide shadow flicker near receptors (households) identified with significant impact.

(D) Impact on Cultural/Archaeological Site

Any archaeological monuments or sites as per the Archaeological Survey of India does not exist in project site, hence **No impact** is envisaged both during construction and operation phase.

(F) Corporate Social Responsibility

Construction Phase

To empower the local community through different development and support programmes SBE should take some initiatives for Community Development Plan under their CSR Policy in the project affected village.

SBE have their own CSR Policy in alignment with its CSR vision, principles and values, for delineating its responsibility as a socially and environmentally responsible corporate citizen. The Policy lays down the areas of intervention, principles, and mechanisms for undertaking various programs in accordance with Section 135 of the Companies Act 2013. As per their CSR Policy, SBE is committed to inclusive growth and local stakeholder involvement as a fundamental value and strives to enhance:

- Social wellbeing
- Economic wellbeing
- Environmental wellbeing
- Local community initiatives

The CSR Activities may include:

- Creating provisions for Employment opportunities to the people who are skilled and semi-skilled in project area villages;
- Supporting the Anganwadi Centres by facilitating them with provisions of exclusive Drinking Water, sitting arrangement, power supply and toilet facilities for them in project area villages;
- Facilitating the local schools by providing them with amenities like chairs, benches, fresh drinking water etc.;

- Facilitating in development and creation of health infrastructure in the project area villages, where it is found to be an inadequate.
- Promotion of education, including special education and employment enhancing vocation skills especially among children, women, elderly and the differently abled and livelihood enhancement projects.
- Promoting gender equality, empowering women, setting up homes and hostels for women and orphans, setting up old age homes, day care centres and such other facilities for senior citizens and measures for reducing inequalities faced by socially and economically backward groups etc.

Operation Phase

The CSR activity may continue during operation phase to comply with the need and requirement of the areas development and to avoid any conflict during that phase.

6.3. Cumulative Impacts

SBE will be been allotted approximately 1100 Hec. of government revenue land by RRECL on sublease basis for Hybrid power project. The project would be established on unused, fallow and barren land. Agricultural practice was observed in the surrounding area, and this agricultural practice is based on bore well (ground water) and rainfall. Also, the land is barren in nature during the site visit.

For total 450 MW Hybrid power project, water will be required for construction phase and only for domestic use during operation phase. Robotic cleaning techniques are proposed to use for cleaning of PV cells. Water for the entire project will be provided by authorized local vendors for which necessary approvals will be obtained.

The project also has a positive impact in terms of employment generation for the local people during entire project lifecycle. One of the cumulative effects is solar reflections known as Glint and Glare. Glare impacts can be minimized by the inherent design qualities of the PV panels, which reduces reflectivity and the potential for visual discomfort or impairment.

Cumulative impacts associated with decommissioning of the proposed project would include the removal of all project components, including Gen-tie Line structures and wiring, as well as all towers, wiring, PV panels, and inverter structures. Decommissioning would temporarily impact the proposed project's contribution to local and regional cumulative impacts on visual resources. The project sites are void of highly scenic views or aesthetically unique or distinctive landscape and impacts to aesthetics would remain be less than significant.

Mitigation Measures

- To curb with the low ground water resources in the area Sourcing of water tanker from authorized/SOCB registered vendors/ tankers should be considered by EPC contractor.
- Wherever feasible client can support the rainwater harvesting/ water conservation initiatives in nearby villages. Building of catchment area to store water during extreme drought seasons.
- Follow applicable national norms and international guidelines for Wind & Solar project development, wherever feasible.

Table 38: Overall Project Risk Assessment

Environment and Social Parameters	Impact During Construction Phase	Impact during Operation Phase
Livelihood	Low	No impact

Environment and Social Parameters	Impact During Construction Phase	Impact during Operation Phase
Laying of Transmission Lines	Moderate	Low
Employment generation	(Positive) High	(Positive) Moderate
Air Quality	Moderate	Low
Noise Quality	Low	Low
Ground Water Quality and Quantity	Moderate	Low
Surface Water Quality and Quantity	Low	No impact
Soil Contamination	Moderate	Low
Topsoil Loss	Low	No impact
Impact on Wildlife other than avifauna	Moderate	Moderate
Impact on avifauna	Low	Moderate
Visual Effects	Low impact	Moderate
Occupational Health and Safety	Moderate	Moderate
Unnatural Events like Earthquake, floods etc.	Low	Low

6.4. Conclusion

The proposed 450 MW Hybrid Power Project will have minor as well as short term impact during construction phase. Minor impact due to generation of dust and fugitive emissions are expected during construction phase only. Minor impact is expected on resource utilization like land and socio-economic conditions of project area villages. Land for the proposed project is totally government land which is being leased for the period of 30 years. Rest of the impacts on environment and social parameters is assessed to be minor during construction and operation phase of the proposed project.

Overall impact anticipated due to generation of noise and shadow flicker from the operating WTGs is anticipated as Low and moderate respectively. This could go higher due to two WTG's being in close proximity.

The project also has a positive impact in terms of employment generation for the local people during entire project lifecycle. The impacts identified both during construction and operation phase can be minimized and mitigated by adopting suitable mitigation measures as suggested in the ESIA report. Based on the conclusion drawn from the ESIA study the kind of impacts of the project on environment, resources, biodiversity, labours and community, this project is expected to have limited adverse environment and social impacts which can be mitigated by adopting suitable mitigating measures.

7. ENVIRONMENTAL & SOCIAL MANAGEMENT PLAN

The Environment and Social Management Plan specifies measures for addressing the limited negative risks and impacts and for enhancing the beneficial impacts. In addition, organizational capacity and training requirements, required to check and ensure effectiveness of the plan throughout the lifecycle of the project, have also been discussed.

SBE is committed to implement an effective Environmental and Social Management System (hereinafter referred as ESMS) to continuously manage and communicate the potential social and environmental impacts and risks imposed on the project employees (direct and indirect) and the local communities residing in the immediate vicinity of the project area. The outcomes of the Environmental and Social Impact Assessment of the project have been used to formulate an Environment and Social management & Management Plan, presented below. The Plan specifies measures for addressing the limited negative risks and impacts and for enhancing the beneficial impacts. In addition, organizational capacity and training requirements, required to check and ensure effectiveness of the plan throughout the lifecycle of the project, have also been discussed.

7.1. Training of Personnel & Contractors

SBE should ensure that the job specific training and EHS Induction training needs are identified based on the specific requirements of ESMS and existing capacity of site and project personnel (including the contractors and sub-contractors). Special emphasis shall be placed on traffic management, stakeholder's engagement and grievance redressal. General environmental awareness shall be increased among the project's team to encourage the implementation of environmentally sound practices and compliance requirements of the project activities. This will help in minimizing adverse environmental impacts, ensuring compliance with the applicable regulations and standards, and achieving performance beyond compliance. The same level of awareness and commitment shall be imparted to the contractors and sub- contractors prior to the commencement of the project.

An environment and social management training program shall be conducted to ensure effective implementation of the management and control measures during construction and operation of the project. The training program shall ensure that all concerned members of the team understand the following aspects:

- Purpose of action plan for the project activities;
- Requirements of the specific Action Plans
- Understanding of the sensitive environmental and social features within and surrounding the project areas; and
- Aware of the potential risks from the project activities.
- A basic occupational training program and specialty courses shall be provided, as needed, to ensure that workers are oriented to the specific hazards of individual work assignments.
- Training shall be provided to management, supervisors, workers, and occasional visitors to areas of risks and hazards.
- Workers with rescue and first-aid duties must receive dedicated training so as not to inadvertently aggravate exposures and health hazards to themselves or their co-workers.
- Through appropriate contract specifications and monitoring, the employer shall ensure that service providers, as well as contracted and subcontracted labour, are trained adequately before assignments begin.

7.2. Monitoring

To implement the ESMP, the on-site team should adhere to a time-bound and action-oriented Environmental and Social Action Plan to implement the mitigation measures provided for each of the identified environmental and social impacts. This ESMP should be monitored on a regular basis, quarterly or half-yearly and all outcomes would need to be audited in accordance with existing EHS commitments.

The monitoring process should cover all stakeholders including contractors, labourers, suppliers and the local community impacted by the project activities and associated facilities thereby increasing the effectiveness of suggested mitigations measures. SBE should ensure that all the contractors comply with the requirements of conditions for all applicable permits, suggested action plans and scheduled monitoring. The inspections and audits should be carried out by an internal trained team and external agencies/experts. The entire process of inspections and audits shall be documented and key findings of which should be implemented by the proponent and contractors in their respective areas.

7.3. Documentation & Record Keeping

Documentation and record keeping system must be established to ensure updating and recording of requirements specified in ESMP. Responsibilities must be assigned to relevant personnel for ensuring that the ESMP documentation system is maintained, and that document control is ensured. The following records should be maintained at site:

- Documented Environment Management System;
- Legal Register;
- Operation control procedures;
- Work instructions;
- Incident reports;
- Emergency preparedness and response procedures;
- Training records;
- Monitoring reports;
- Auditing reports; and
- Complaints register and issues attended/ closed

Table 38: Environment Management Plan

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
CONSTRUCTION PHASE							
A	Physical Environmental Management Plan						
1	LANDSCAPE AND VISUAL	Visual and landscape impacts due to presence of elements typical of a construction site such as equipment and machinery.	LOW	<ul style="list-style-type: none"> Ensure the construction site is left in an orderly state at the end of each workday Construction machinery, equipment, and vehicles not in use should be removed in a timely manner to the extent possible Proper handling of waste streams 	NO IMPACT		Contractor under the supervision of SBE's Personnel
2	WATER RESOURCES AND QUALITY	<ul style="list-style-type: none"> Possibility of contaminated runoff from the site entering ground though very limited. Domestic water runoff from the portable toilets into the ground water can lead to degradation of water quality. 	MODERATE	<ul style="list-style-type: none"> During construction phase, water is being sourced from tanker through vendor as reported. Construct rainwater harvesting pit to recharge the ground water Periodic monitoring shall be carried out to ensure that the wastewater is not finding its way into ground or surface water. Conserve water at all project locations and ancillary facilities and if possible, recycle and reuse water utilizing every opportunity. Approval/NOC from competent authority (CGWB/CGWA) will be 	LOW	Maximum efforts should be made to reuse and recycle water to reduce water consumption.	Project Developer/ Contractor under the supervision of SBE's Personnel

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>obtained if bore well is installed for ground water extraction</p> <ul style="list-style-type: none"> • Paved impervious surface and secondary containment to be used for fuel storage tanks • Adequate drainage of road based on road width, surface material, compaction and maintenance • Leak-proof holding tanks for sanitary wastewater to protect the shallow ground water level. • Wastewater holding tanks / septic tank to be located at more than 500 m away from bore wells or any other underground water holding tanks. 			
3	AIR QUALITY	<ul style="list-style-type: none"> • Fugitive Dust due to movement of project vehicles and site clearance • Emission from Diesel Generators 	MODERATE	<ul style="list-style-type: none"> • Vehicles speed to be restricted to 20-30 km/hr. on unpaved road. This will reduce dust emission • Raw material should be covered with tarpaulin sheet during transportation and in storage area • Practices water sprinkling wherever required on unpaved area but ensure use of tanker water purchased from authorized vendor only • All the project vehicles shall have valid PUC certificate • Ensure regular maintenance of project vehicles during 	LOW	Six monthly monitoring for air quality	Project Developer/ Contractor under the supervision of SBE's Personnel

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>construction and operational phase</p> <ul style="list-style-type: none"> • Turn off the DG sets & machineries which are not in use • DG sets preferably should be placed away from settlement area. • It will be ensured that exhaust emissions of construction equipment adhere to emission norms as set out by MoEF&CC/ CPCB. 			
4	SOIL QUALITY	<p>Topsoil Loss (though topsoil is very less due to the arid and desertic land in the project area)</p> <p>Soil Contamination</p>	LOW	<ul style="list-style-type: none"> • Provide appropriate storage of topsoil in an isolated and covered area if any. • Allow only covered transportation of topsoil within project site. • Use topsoil at the time of plantation on the approach road. • Re-vegetation shall be done in the area after the completion of construction, in order to reduce the risk of soil erosion <ul style="list-style-type: none"> • In case of any accidental spill, the soil will be cut and stored securely for disposal with hazardous waste. • Store hazardous material (like used oil) in isolated room with impervious surface. 	LOW	<ul style="list-style-type: none"> • The workforce shall be sensitized to handling and storage of hazardous substances viz. fuel oil, machine oil/fluid etc. • The workers engaged in handling hazardous substances shall be briefed about the possible hazards and the need to prevent contamination. 	<p>Project Developer/ Contractor under the supervision of SBE's Personnel</p>

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<ul style="list-style-type: none"> Filling and transfer of oil to and from the container shall be on impervious surface. Waste disposal grounds that are in use by the local people should be identified and permission from local administration for use of the same needs to be obtained for disposing domestic wastes. 			
5	NOISE LEVEL	<ul style="list-style-type: none"> Disturbance to habitants Vehicular noise from heavy vehicles utilized to deliver construction materials and solar plant parts Noise from DG sets Construction noise from using mobile equipment, and concrete mixing 	Moderate	<ul style="list-style-type: none"> Regular maintenance of construction machinery and equipment shall be carried out to ensure noise emissions are maintained at design levels. Integral noise shielding to be used where practicable and fixed noise sources to be acoustically treated, for example with silencers, acoustic louvers and enclosures. Keep stationary source of noise such as DG sets (during construction phase) at farthest point from the settlements Restrict major noise generating activities during night time 10:00 pm to 6:00 am Provide personal protective equipment to workers working near DG sets and other high noise source. Local communities need to be informed about the vehicular movement before start of heavy 	LOW	Noise emissions of construction equipment adhere to emission norms as set out by MoEF&CC/ CPCB to ensure the compliance.	Project Developer/ Contractor under the supervision of SBE's Personnel

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>vehicle carrying materials and machines to site. Sensitive locations should be identified and avoided as far as possible from the route and if unavoidable, drivers should be informed to restrict speed at those locations.</p> <ul style="list-style-type: none"> • Diesel generator sets, if used; will adhere to noise standards of MoEF&CC. 			
6	SOLID WASTE	Contamination of land	MODERATE	<ul style="list-style-type: none"> • Distribute appropriate number of properly contained litter bins and containers properly marked as "Municipal Waste". • Domestic and construction waste like recyclables viz. paper, plastic, glass, scrap metal waste etc. will be properly segregated and stored in designated waste bins/containers and periodically sold to local recyclers 	LOW	Periodic EHS audits should be conducted to monitor the same	Project Developer/ Contractor under the supervision of SBE's Personnel
7	CHANGE IN LOCAL TOPOGRAPHY	Alteration in natural drainage pattern	MODERATE	<ul style="list-style-type: none"> • Don't allow the considerable alteration of contour level • Provide alternatives to collect surface runoff from the project site during the monsoon period • Don't allow exit of runoff from the project site in the adjacent areas. • Design storm water drain considering the natural contour level wherever required 	LOW	The drainage patterns of the area will be maintained.	SBE design team

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<ul style="list-style-type: none"> Site preparation activities should be designed to avoid any significant elevation of the land or blocking or altering natural drainage channels in the project site. Site preparation and development shall be planned only after a detailed drainage plan has been prepared for site. 			
B Ecological Environmental Management Plan							
9	ECOLOGY	<ul style="list-style-type: none"> The construction activities will lead to loss of vegetation resulting in displacement of terrestrial species Disturbance to local livestock population Man -Animal conflict 	MODERATE	<ul style="list-style-type: none"> All project activities shall be undertaken with appropriate noise mitigation measures to avoid disturbance to human as well as faunal population in the region. Activities generating high noise shall be restricted to day time and will be mitigated to minimize the noise level outside the site boundary. Recovery of ground story (mostly grasses and herbs) vegetation under the PV panels and in other places that do not need to remain cleared shall be encouraged to grow. Movement of construction and transport vehicles shall be restricted to dedicated paths to 	LOW	Periodic EHS audits should be conducted to monitor the same	Project Developer/ Contractor under the supervision of SBE's Personnel

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>minimize any harm to small mammals/reptiles within the site.</p> <ul style="list-style-type: none"> • Transportation of construction material shall be restricted to day time hours in order to minimize noise and disturbance to fauna in the area. • General awareness training regarding wildlife shall be enhanced through putting signage, posters, among the staff and labourers. • Waste shall be collected in a manner that it does not attract wild animals. • Temporary barriers shall be installed on excavated areas. • The footprints of the construction activities shall be kept to minimum to reduce disturbance to flora and fauna. • Planting native, fast growing trees on access roads and/or in nearby barren areas/ schools/ Panchayat office which may also give an alternate habitat to the faunal species especially the bird species and maintain the ecological balance. • The site clearance for tower erection, access road and ancillary facilities should be restricted to the necessary footprint area around WTG. 			

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<ul style="list-style-type: none"> The crane staging area, intervening areas, overhead clearance for suspended turbine components should be planned in such a way that minimum tree felling is required; Contractors should ensure that labour colonies are not set up in the regions where faunal species are commonly found. Sign boards on the roadside should be installed and strict regulations on speed limits should be imposed to control the road kills of animals during transportation of materials 			
C Social Management Plan							
1	ENGAGEMENT OF LOCAL AND MIGRANT LABOUR	Conflicts between labour and contractor	MODERATE	<ul style="list-style-type: none"> Employment will be provided to local people wherever possible, especially as unskilled construction workers and security guards. SBE will include clause or provisions related with non-engagement of forced and child labour, gender equity, non-discrimination on employment and opportunity and freedom to express their view in contractor's agreement and HR policy SBE through its contractors shall ensure that labour is being adequately paid by contractors. Also ensure that wages are being 	LOW	<p>Periodic EHS audits should be conducted to monitor the vendor practices</p> <ul style="list-style-type: none"> Construction contractors should adhere to social obligations, labour laws and international commitments SBE through contract agreement, should ensure that the contractor should 	Developer/Contractor under the supervision of SBE personnel Project

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>paid as per the requirement of minimum wages act</p> <ul style="list-style-type: none"> • SBE shall include clause to ensure access of necessary basic amenities and facilities such as drinking water, kitchen, toilet and crèches (for female workers children) • SBE shall conduct internal audits as when required to monitor the performance of contractor. • SBE through the contractor inform the labour about emergency preparedness plan and communication system to be followed during emergency • SBE through contractor should ensure that labour receive training on health and safety issues involved in the project. • IFC guidance note on “Labour and working condition” shall be followed by project developers and contractors. • SBE shall prepare Labour engagement plan in line with IFC guidance manual and include in contractors agreement. 		<p>provide the migrant workers adequate information on expected social behavior and hygiene practices to be followed at site</p> <ul style="list-style-type: none"> • Water usage should be monitored and controlled to minimize the wastewater generation • SBE to ensure that all site personnel and migrant labourers avoid using any community infrastructure facilities like water bodies, electricity etc., without prior permission from the Panchayats 	
2	LABOUR ACCOMMODATION (Inside or outside the plant premises)		MODERATE	<ul style="list-style-type: none"> • As reported by SBE, the labours will be engaged by sub-contractor for construction purpose. Unskilled labours will be hired locally, and the technical work will be undertaken by the 	LOW	<ul style="list-style-type: none"> • SBE through contract agreement, should ensure that proper health and safety measures should be taken, (to 	

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>skilled personnel who will stay in rented accommodation nearby to the site area village. As reported by SBE, two labour camps will be established near the site.</p> <ul style="list-style-type: none"> The camp will have all the basic physical and social infrastructure facility and as per the national guidelines. 		<p>provide the basic amenities) for the labors those who will be staying in labour camp and nearby villages)</p>	
3	LAND LEASE	<ul style="list-style-type: none"> Loss of Land/ Livelihood/ Obstruction to places of relevance/ Manhandling Natural Resources of Utility 	LOW	<ul style="list-style-type: none"> Project will be set up on government revenue land parcel measuring approximately 1100 Ha. Land allotted to SBE is on sub lease basis. Process of Land procurement – Since this is entirely Revenue Land, SBE are required to make an application to RRECL which then recommends for allotment of the said project land to District Collector for allotment. After obtaining necessary NOCs and approvals from relevant govt. departments allotment order is issued by District collector and lease deed is signed. It should be ensured that maximum employment is given to the locals w.r.t their capacity and skills. Implement the recommended complaint resolution procedure (Grievance Redress Mechanism) to assure that any complaints regarding project related 	LOW	<ul style="list-style-type: none"> SB Energy will procure land through Rajasthan government land lease Policy. 	<ul style="list-style-type: none"> Developer/ Contractor under the supervision of SBE's Personnel Social Management team for grievance handling

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>components are promptly and adequately investigated and resolved</p> <ul style="list-style-type: none"> • Provide some alternate way/road so that project should not obstruct the villagers access. • The layout for access roads and transmission lines should consider minimum land requirement and should avoid procurement of agricultural land. • Any waste generated during the construction phase should not be accumulated near the religious structure as this might affect the sentiment of the locals. 			
4	IMPACT INDIGENOUS PEOPLE	ON <ul style="list-style-type: none"> • Unrest among the community due to dislocation of any structure or thing of cultural belief Impact on indigenous people due to land intake from ST people and use of village resources 	Low	<ul style="list-style-type: none"> • Though very few Bhil tribal populations are residing in the study area villages however, no tribal land and livelihood are getting impacted because of the project. • They are hopeful that the project will bring employment opportunities for them 	LOW	<ul style="list-style-type: none"> • SBE should formulate further assessment may be undertaken to ensure the need of Indigenous People. 	SBE

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
5	IMPACT ON ARCHEOLOGICALLY IMPORTANT SITES		No Impact	<ul style="list-style-type: none"> There is no archaeological important site in the study area. 	No Impact		
4	COMMUNITY ENGAGEMENT	<ul style="list-style-type: none"> Community Empowerment 	MODERATE	<ul style="list-style-type: none"> Given the short duration of the Project construction phase efforts will be made to engage with the community through the Panchayat Raj Institution representatives and key identified leaders of the community. 	LOW	<ul style="list-style-type: none"> Continuously throughout the project lifecycle. Grievance Redressal Mechanism should be followed, and grievance register should be maintained onsite. 	Contractor under the supervision of SBE's Personnel / PRI representatives
5	OCCUPATIONAL HEALTH AND SAFETY	<ul style="list-style-type: none"> Material handling and storage Possible injuries associated with working with transmission line laying Other occupational hazards 	MODERATE	<ul style="list-style-type: none"> All material will be arranged in a systematic manner with proper labelling and without protrusion or extension onto the access corridor. Loading and unloading operation of equipment should be done under the supervision of a trained professional All work at height to be undertaken during daytime with sufficient sunlight Proper PPEs should be provided to workers handling welding, electricity and related components. Fire extinguishing equipment should be provided in adequate 	LOW	<ul style="list-style-type: none"> The labour engaged for working at height should be trained for temporary fall All the workers should be made aware of the possible occupational risks/hazards by the way of an OHS training/awareness programmed An accident reporting and monitoring record should be maintained 	Contractor under the supervision of SBE's Personnel

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				number on site to handle any possible fire outbreaks <ul style="list-style-type: none"> • An accident reporting and monitoring record should be maintained • Display of phone numbers of the city/local fire services, etc. at site should be done • The labour engaged for working at height should be trained for temporary fall protection devices 			
OPERATION PHASE							
A. Physical Environment Management Plan							
1	HAZARDOUS WASTE MANAGEMENT	Contamination of land and soil	MODERATE	<ul style="list-style-type: none"> • Broken solar panels, which will be collected in closed containers and then will be delivered to approved vendors for disposal or reuse. 	LOW	Periodic EHS audits should be conducted to monitor the same	Project Developer
2	SOLID WASTE MANAGEMENT	Contamination of land	MODERATE	<ul style="list-style-type: none"> • Distribute appropriate number of properly contained litter bins and containers properly marked as "Municipal Waste". The waste generated should be disposed as per The Municipal Solid Wastes (Management and Handling) Rules, 2000. as amended till 2016. • Domestic waste will be composted and recyclables viz. paper, plastic, glass, scrap metal 	LOW	Periodic EHS audits should be conducted to monitor the same	Project Developer

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				waste etc. will be properly segregated and stored in designated waste bins/containers and periodically sold to local recyclers.			
3	GROUNDWATER ABSTRACTION	Ground water depletion if extracted during operation phase (permission must be obtained from statutory authority). Robotic cleaning has been proposed	MODERATE	<ul style="list-style-type: none"> Ensure optimal usage of water viz., storage and reuse water. Rain water harvesting to be practiced. 	LOW	Periodic EHS audits should be conducted to monitor the same	Project Developer
4	WASTEWATER MANAGEMENT PLAN	Degradation of ground and surface water quality	MODERATE	<ul style="list-style-type: none"> Ensure that construction of septic tanks during operation a phase. Ensure that septic tanks are emptied and collected by contractor at appropriate intervals to avoid overflowing 	LOW	Periodic EHS audits should be conducted to monitor the same	Project Developer
5	ECOLOGY & BIODIVERSITY	Impact to the local avifauna	MODERATE	<ul style="list-style-type: none"> Project proponent should follow all the directions of regulatory agencies as prescribed from time to time by the Federal Government/state government / court orders. As WLPA, 1972 Any accidental death due to species listed in the schedule will lead to legal action against the responsible party 	MODERATE to LOW	Periodic avian surveys should be carried out along with consultations with the stakeholders in the nearby areas	S B Energy

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility		
				<p>irrespective of the location where the incident occurred.</p> <ul style="list-style-type: none"> The power pole configuration should be designed to minimize avian electrocution risk Bird diverter should be installed in transmission line which the client will be complying with respect to the sensitive areas as suggested by the study undertaken by Bombay Natural History Society (BNHS) Flash lamps on the WTGs should be installed to reduce collision risk to birds & bats at night 					
6	AMBIENT LEVELS	NOISE		<ul style="list-style-type: none"> Noise generation due to operation of wind turbines. Wind turbines produce noise through mechanical and aerodynamic sources. 	Moderate	<ul style="list-style-type: none"> Wind turbines should be designed in accordance with the international acoustic design standards Proper and regular maintenance of the WTG's Implement the recommended complaint resolution procedure (Grievance Redress Mechanism) to assure that any complaints regarding operational noise are promptly and adequately investigated and resolved. Operating turbines in reduced noise mode. 	Low	<p>Undertake ambient noise level monitoring on in order to understand the increase in noise levels due to the project operation</p>	SB Energy

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<ul style="list-style-type: none"> • Building natural barriers like plants/usage of appropriate noise barriers around potentially affected structures, if complaints on the same are received • Shifting WTG's to few meters out of setback distance 270m . • Regular maintenance of WTG would be carried out to make sure the parts have been well oiled to reduce friction between parts and generate excess noise. • All nearby community will be informed about the GRM and the grievance would be addressed on priority bases. • Plantation would be initiated around the turbine base area to absorb the noise generated by the turbines. • In case of any complaint related to noise, appropriate measures should be taken to manage the same. 			

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
7	SHADOW FLICKER AND BLADE THROW HAZARD	<ul style="list-style-type: none"> Disturbance to nearby community due to shadow flickering caused by wind turbines Injury due to accidental blade throw 	Moderate	<ul style="list-style-type: none"> During site selection of the project, measures are taken to select the WTGs location at least 300 m from all the temporary and/or permanent structures. However, if the settlements are located within the narrow bands (200m), each dweller will be informed about possible negative impacts i.e. noise, shadow flicker, blade throw etc. If the owner is willing to relocate, the structure will be dismantled with agreement and appropriate compensation will be provided as per local/national regulations and in line with IFC PS' physical and/or economic displacement requirements. Regularly maintain the wind turbine. The impact of shadow flicker received by the structure will further be reduced if there is closed wall/opaque structure where in the light/shadow would not penetrate/directly affect the receptor. The source of shadow flicker would be through window's, open roof and doors. It is recommended that SBE Renewables Ten Projects Pvt Ltd should formulate a complaint resolution procedure for the local community so that 	Low	Necessary procedure will be followed, and records will be maintained for consultations, essential documents, compensation benefits etc.	S B Energy

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				<p>any issues or concerns associated with shadow flicker are reported to the site staff.</p> <ul style="list-style-type: none"> SBE Renewables Ten Projects Pvt Ltd will ensure that appropriate and timely action is taken in case of receipt of such complaints. Usage of curtain and blinds in households/structures with open roof, and windows, doors facing WTGs would cut out the impact of shadow flicker. Landscape features, such as trees could also be used to prevent or limit the potential for shadow flicker. Micro siting can be reconsideration, if feasible. Use warning signs to alert the public of risk. 			
B	Social Management Plan						
1	CORPORATE SOCIAL RESPONSIBILITY	Community Empowerment	MODERATE	<ul style="list-style-type: none"> Employment will be provided to local people wherever possible, especially as unskilled construction workers and security guards Improvement of the physical & social infrastructure facilities in the study area villages Opportunities for contributing to the economic and developmental 	Low	<p>CSR Activities should be documented</p> <p>Should be conducted continuously through the project cycle.</p> <p>Should be conducted continuously through the project cycle.</p>	<p>SBE's Personnel</p> <hr/> <p>SBE's Personnel</p> <hr/> <p>SBE's Personnel</p>

SN	Aspect	Impact	Impact Intensity without mitigation	Action	Impact Intensity with mitigation	Monitoring/training Requirement	Responsibility
				needs of villagers through skill training will be explored.			
2	OCCUPATIONAL HEALTH AND SAFETY OF WORKERS	Electrocution Firing due to short-circuit Possible injuries associated with working at height Diseases due to unhygienic condition	MODERATE	<ul style="list-style-type: none"> • Provide and ensure wearing of personal protective equipment's viz., gloves, helmets, ear plug, safety belt etc. • Ensure effective work permit system for critical activities such as electrical work and working at height. • Prepare emergency communication system and emergency preparedness plan • Ensure proper sanitation facilities. 	LOW	Periodic EHS audits	Project Developer's / SBE's Personnel

7.4. Environmental Monitoring Plan

The Environmental Monitoring Plan is formulated to ensure and demonstrate compliance with the regulatory and Institutional Agency’s EHS requirements. Monitoring of environmental and social parameters and comparing them with benchmarks set by regulatory and institutional authorities will help SBE assess in the environmental performance and identify gaps or non-conformance (if any) ensuring immediate actions to bring it into compliance. To ensure the same, the following environmental parameters will be monitored. The Environment Monitoring Program is depicted in **Table-**.

Table-39: Environment Monitoring Program

A. Environmental Quality Monitoring Program

EQI No	Environmental Quality Indicator (EQI)	Monitoring Parameter	Location	Period & Frequency
A. CONSTRUCTION & OPERATION PHASE				
A1	Ambient Air Quality	Monitoring of PM ₁₀ , PM _{2.5} , SO ₂ , NO _x , CO		Once during construction phase
A2	Ambient Noise quality	Measurement of Noise Pressure Level in dB(A)		Once during construction phase and other during operation phase near permanent receptors close to WTG
A3	Ground Water quality	IS 10500 parameters		Once during construction phase
A4	Surface Water quality	IS 10500 parameters		Once during construction phase
A5	Soil Quality	Soil parameters viz. pH, SAR, Water holding capacity, Conductivity, Organic Carbon, NPK		Once during construction phase

7.5. Environmental Management Plans

The ESMP is comprised of some site-specific management plans viz. Emergency Preparedness and Response Plan, Waste Management Plan, Storm Water Management Plan, Environmental Monitoring Plan, Road Safety and Traffic Management Plan and Occupation Health and Safety Management Plan for this Hybrid power project. The management plans will be executed through Environmental Social Management System.

7.5.1. Emergency Preparedness and Response Plan

Purpose

SBE, should develop a site-specific Emergency Management Plan for implementation at the entire project location, In the event of an emergency so that the loss of life and damage to the properties & natural resources are minimized. This plan outlines a series of emergency actions that will be executed by SBE & its Contractors to ensure preparedness and response to emergency situations throughout the life cycle of the project.

Definition(s)

Emergency - Any unplanned situation, which presents a threat to the safety of workers and/or damage to the properties and other natural resources deemed valuable at the project site.

Emergencies

The emergency situations that are probable to occur at the site and the probable causes are listed below:

- Fire at site during temporary construction phase which cannot be doused by fire extinguishers; Also fire due to short circuit at the plant and equipment during both construction & operation phase.
- Collapse of any structure
- Outbreak of endemic disease among a large section of construction workers due to contaminated drinking water, unhygienic conditions that have developed at workplace.
- Protests by the local community or other stakeholders at any point of the project lifecycle due to grievances.
- Serious injury or death of employee or sub-contracted worker at work, due to non-work-related illness or work-related accident.
- Onset of any natural disaster like earthquake.

Emergency Management

The following steps should be taken to ensure proper management of emergency or crisis situations:

- The nearest civil hospitals, private health care centres or practitioner clinic should be identified and an agreement should be made with the aforesaid medical centres/practitioners to provide prompt health care services (including ambulance services) in the event of an emergency situation at site.
- A list of important telephone numbers such as fire brigade, health care facility/practitioner, police station, EHS and Social Coordinator, project office, head offices should be displayed at all the prime locations at site.
- Regular liaising with the police, Gram Panchayats, district administrations should be carried out to ensure that prompt assistance is readily available in the event of an emergency.
- An Emergency Management (including Disaster Management) team comprising of 4-6 professionals both from the developer and contractors' side, during construction phase and 2-3 professionals during operation of the project; should be formed to combat any emergency situation and ensure safety of the life and property at site. For this purpose, 2-3 personnel employed in the plant during operation phase should be trained on Emergency scenarios and their management measures including their roles and responsibilities in case of an emergency situation.
- The workers (staff & contractual workers from both SBE & their appointed contractor/s) should be trained on their duties and emergency preparedness during an emergency. In case of an emergency, all site personnel should be trained to follow the communication lines given below:
 - Personnel at site affected by the emergency situations immediately inform the project office and the external agencies (such as police, fire brigade, ambulance services); In case, project office cannot be reached, the coordinator will be informed directly.

- The Social, Environment, Health & Safety Coordinator (SEHS) on being informed about the emergency by project offices or by the employee directly; reaches site if necessary, and also follows-up with the aforesaid external agencies for aid.
- The SEHS Coordinator takes charge of the emergency response and direct further action and co-ordination, including escalating the matter to the higher authority as required.

Responsibilities

The SEHS Coordinator will be responsible for implementing this procedure, which includes

- Ensuring that the emergency preparedness measures are in place.
- Providing training to the personnel at site regarding reporting of the emergencies, and to site office personnel regarding response to emergency calls from the site personnel,
- Direct action-and co-ordination at the time of an emergency

Community health and safety hazards specific to solar energy facilities primarily include the following:

Setback:

The project sites may alter the contour levels and natural drainage pattern which can cause local flooding in the area therefore adequate measures such as storm water drainage, rain water harvesting, etc. may result to local flooding. Though the possibility of flooding is rare due to drought prone area.

Transmission Line:

Transmission Line should be routed in such a way that it causes least disruption to local communities.

Public Access:

Safety issues may arise with public access to Solar & Wind Plants (e.g., unauthorized entry to the Plants). Any public rights of way located within and close to the Solar & Wind Plants should be identified prior to construction to establish any measures that may be required to ensure the safety of their users. Prevention and control measures to manage public accesses include:

- Use gates on access roads.
- Where public access is not promoted to the site or there are no rights of way across the site, consider fencing the solar energy facility site to prohibit public access to the site.
- Provide fencing of an appropriate standard around the sub-station with anti-climb paint and warning signs.
- Post information boards about public safety hazards and emergency contact information.

Community health and safety hazards specific to wind energy facilities primarily include the following:

Electromagnetic Interference and Radiation: Wind turbines could potentially cause electromagnetic interference with telecommunication systems (e.g., microwave, television, and radio). This interference could be caused by path obstruction, shadowing, reflection, scattering, or re-radiation. The nature of the potential impacts depends primarily on the location of the wind turbine relative to the transmitter and receiver, characteristics of the rotor blades, signal frequency receiver characteristics, and radio wave propagation characteristics in the local atmosphere. Suitable mitigation measures to enhance the quality of the television signal and lower the impact of wind turbine on telecommunication need to be adopted.

Public Access: Safety issues may arise with public access to wind turbines (e.g., unauthorized climbing of the turbine) or to the wind energy facility substation. Any public rights of way located within and close to the wind energy facility site should be identified prior to construction to establish any measures that may be required to ensure the safety of their users. Prevention and control measures to manage public accesses include:

- Use gates on access roads.
- Where public access is not promoted to the site and/or there are no current rights of way across the site, consider fencing the wind energy facility site, or individual turbines, to prohibit public access to the turbine.
- Provide fencing of an appropriate standard around the sub-station with anti-climb paint and warning signs.
- Prevent access to turbine tower ladders
- Post information boards about public safety hazards and emergency contact information.

Blade Throw: A failure of the rotor blade can result in the “throwing” of a rotor blade, or part thereof, which may affect public safety. The overall risk of blade throw is extremely low. Blade throw risk management strategies include:

- Establish setback distances between turbines and populated locations. The IFC EHS Guidelines for Wind Energy (August 7, 2015) recommends the minimum setback distance is 1.5 x turbine height (tower + rotor radius),³ although modelling suggests that the theoretical blade throw distance can vary with the size, shape, weight, and speed of the blades, and the height of the turbine. It is therefore recommended that the minimum setback distances required to meet noise and shadow flicker limits be maintained with respect to sensitive residential receptors to provide further protection
- Minimize the probability of a blade failure by selecting wind turbines that have been subject to independent design verification/certification (e.g., IEC 61400-1), and surveillance of manufacturing quality.
- Ensure that lightning protection systems are properly installed and maintained.
- Carry out periodic blade inspections and repair any defects that could affect blade integrity.
- Equip wind turbines with vibration sensors that can react to any imbalance in the rotor blades and shut down the turbine if necessary.

7.5.2. Community Liaison Plan

The Community Liaison Plan is a critical element of the overall Social Management Plans. Regular transparent communication between both the project and the communities and vice versa is crucial in building positive relationships between the two parties. This relationship should be crucial for managing unexpected situations which might arise during the project. This plan should be read with other social management plan because the liaison which needs to be done for the individual plan is detailed within the plan. The communication plan mainly focuses on the communication issues during the construction stage however it also includes some community Liaison measures for the operation phase as well.

³ https://www.ifc.org/wps/wcm/connect/2c410700497a7933b04cf1ef20a40540/FINAL_Aug+2015_Wind+Energy_EHS+Guideline.pdf?MOD=AJPERES

Objectives: The Performance Standards mandates continuous communication between project and the different stakeholders e.g. workers, local community. The onus of initiating the process of communication rests on the project proponent. The project proponent should ensure that disclosure of relevant project information that would help the affected communities understand the risks, impacts and opportunities of the project. The Community Liaison Plan is developed to ensure a clear communication channel between the project and the local community. The focus of the plan is primarily on communication with the community areas where there are likely interactions between the community and the Contractors. The community liaison plan would concentrate on the following aspects

Communication with the Community: As mandated in the Performance Standards of IFC, SBE had already disclosed the project details prior to lease of land parcels from the villagers to make the community aware of the important features of the project.

7.5.3. Waste Management Plan

The Waste Management Plan (WMP) will be applicable to the wastes arising during commissioning and operation of the Wind - Solar Hybrid Power Project of SBE. Major waste streams from the project include non-hazardous solid waste, wash water generated from sewage. WMP is intended to serve as a guideline for SBE and the contractor(s) to manage wastes effectively during the project life cycle. The WMP describes how wastes will be managed during the project life cycle and how the project will:

- Minimize the potential to cause harm to human health and the environment.
- Comply with Indian environmental regulation and guidelines following the IFC Performance Standards.
- Reduce operational costs and reduce any potential liabilities which may arise from waste handling operations.

This plan also ensures that every waste stream and solid waste materials from the main plant site and bracketed facilities will be managed effectively.

The EPC contractors will manage the waste generated during construction phase like construction debris, packing material, paint containers and filters. The management measures of the solid wastes and the hazardous wastes are discussed in detail below:

- The recyclable and non-recyclable non-hazardous solid waste generated onsite should be collected and stored in a temporary waste storage facility from where all wastes will be sent for recycling and disposal to appropriate facilities.
- The reusable wastes like wooden waste and cardboards from packing materials, empty cement bags, construction debris, etc. can also be given to locals for their use or give it back to original equipment manufacturer (OEM).
- Hazardous waste will be disposed or delivered to the approved agency.

7.5.4. Storm Water Management Plan

The purpose of Storm Water Management Plan (SWMP) is to ensure prevention and control of any adverse impact caused by un-regulated storm water runoff from the main plant to the nearby natural drainage channels, surface water bodies, public and private properties though the possibility of heavy rain is very rare in this climatic zone.

Following measures will be taken as part of the Storm Water Management Plan:

- The peripheral drains will be provided outside the plant boundary during construction phase, which will prevent the silt contaminated surface run-off from site to enter into the adjoining lands.
- No surface run-off from within the Wind - Solar Hybrid Power Project site will be directly discharged into any nallah/water body.
- Rainwater collected from the project site will be used to recharge the ground water through onsite rainwater harvesting tank/pits.
- Avoidance of disturbance of flows into natural watercourses i.e. provision should be made for temporary or permanent measures that allow for attenuation, control of velocities and capturing of sediment upstream of natural watercourses.
- Do not divert flows out of their natural flow pathways, thus depriving downstream watercourses of water.

7.5.5. Community Property Resource

During the project construction phase, there might be some sharing of resources by the villagers and the workers working on the project site. To an extent feasible this should be avoided to prevent potential conflicts between the project and the community. The movement of heavy vehicles and machineries might lead to conditions like disruption of electric wires and telephone wires in the project area and along transportation routes. All these damage utilities should be repaired/replaced to normal conditions, at the earliest. An account of the damage to the community resource should be documented and the root cause analysis carried out. The findings of the root cause analysis should also be documented and discussed with the agency/agencies found responsible for the incident. No water should be extracted from surface water bodies which are used by the community for drinking or domestic purpose. Any vacant or barren land, not assigned for project, should not be used for storage of fill/construction material, wastes, etc.

Responsibility: SBE would take responsibility for construction of the road before the existing road is diverted / closed for use by villagers. SBE (through the implementing agency/contractors) should start the process of dialogue with the community to decide on the alignment of the road and also fix up the likely timeline for the construction.

SBE contractors should ensure that the sharing of community resource is minimized by organizing necessary support infrastructure/facilities within premises. However, in case where sharing would be essential SBE and/ or their contractors should have an agreement with the Gram Panchayats for the sharing of the resource. In case of damage to community property SBE including its contractors should ensure that it is repaired or replaced to the satisfaction of the community at the earliest. SBE should maintain documentation of all incidents of damages to the community property. All cost for repair/replacement should be borne by SBE.

As part of the Environmental and Social Management System, a system should also be developed for recording such incidents and tracking the incident till it is closed to the satisfaction of the community.

7.5.6. Occupation Health and Safety Management Plan

The Occupational Health and Safety (OHS) of the employee and contractual labours will be maintained at the work sites during both construction and operation phase. The OHS Management measures should comply with the Indian Regulatory requirements under OHSAS and the Factories Act 1948, amended 1954, 1970, 1976 and 1987.

Construction Phase: The following occupation health and safety measures will be adopted during the construction phase:

- Provide and ensure wearing of personal protective equipment's viz., gloves, helmets, ear plug, safety belt etc.
- Prepare emergency communication system and emergency preparedness plan.
- Ensure provision and maintenance of drinking water and sanitation facilitation for construction workers in accordance with the provision of Contract Labour Act and Building and Other Construction Workers Act.
- Periodic cleaning of work areas will be undertaken and supervised by the contractors to ensure hygienic conditions on site.
- Workers will stop working in extreme natural climatic conditions i.e. heat wave, heavy rain etc.
- Ensure effective work permit system for critical activities such as electrical work and working at height
- All workplaces will have adequate fire alarms and firefighting equipment's to handle any outbreak of fire in O& M.
- Adequate drinking water will be supplied at workplace for workers onsite and water quality meets drinking water quality standards. SBE needs to ensure it through its contractors.
- Sufficient light and ventilation will be provided for workers working in confined space.
- Periodic health check-up camps for workers onsite will be organized to ensure prevention of occupational health hazards.
- Work/Construction signage all along construction area.
- Health and Safety training for all workers and awareness.
- All work areas should have First Aid kits to manage injuries occurring in the area.
- The switchyard building will be provided with fire extinguishers and sand buckets at all strategic locations to deal with any incident of fire.

Operational Phase: Although no significant occupational health and safety risks are identified during operations, the following mitigation measures need to be adopted:

- Operators are provided with adequate PPEs depending upon nature of the operation and occupation health and safety risks associated with it viz. electrical maintenance activities, replacement solar PV panel components etc.
- Special emphasis on electrical safety will be laid and all employees will be trained in electrical safety and First Aid
- Standard Operation Procedures (SOPs) will be developed for operational activities likely to have potential occupational health and safety risks
- Periodic medical examination will be undertaken for workers including contractor and subcontractor of the plant.
- Periodic inspections will be carried out to ensure all the above are implemented and any non-conformances will be recorded along with grievance related to OHS issues.
- An EHS coordinator will effectively implement and monitor the OHS Management System and ESMP.

7.5.7. Grievance Redressal Mechanism (GRM)

SBE should incorporate a GRM Policy mentioning the procedures for lodging of grievances, processing of grievances, resolving grievances and closing of grievances. Following the GRM Policy in the ESMS of SBE and the IFC guidelines issues raised through grievance redressal system should be addressed with remedial measures on site. Grievance redressal framework for onsite implementation should also be formulated for the purpose.

However, it must be ensured that:

- The grievance mechanism should be scaled to the risks and adverse impacts of the project.
- It should address affected people's concerns and complaints promptly, using an understandable and transparent process that is gender responsive, culturally appropriate, and readily accessible to all segments of the affected people at no costs and without retribution.
- The mechanism should not impede access to the country's judicial or administrative remedies.
- The affected people will be appropriately informed about the mechanism.

SBE will follow their grievance mechanism to ensure that grievances from affected communities are addressed and necessary mechanisms exist for catering to external communications from others. If the client anticipates ongoing risks to or adverse impacts on affected communities, the client will establish a grievance mechanism to receive and facilitate resolution of the affected communities' concerns and grievances about the client's environmental and social performance. The grievance mechanism should be scaled to the risks and adverse impacts of the project. It should address concerns promptly, using an understandable and transparent process that is culturally appropriate and readily accessible to all segments of the affected communities, and at no cost and without retribution. The mechanism should not impede access to judicial or administrative remedies. The client will inform the affected communities about the mechanism in the course of its community engagement process. The decision on the grievance would be communicated to the aggrieved person within a timeframe.

7.5.8. Community Development Plan under CSR

SBE have their own CSR Policy. Following the guidelines of MNRE of Govt. of India and Companies Act, 2013 it is mandatory to undertake developmental activity for the community of the project affected area. The same has been suggested in Environmental Management Plan.

Companies Act, 2013 has introduced mandatory Corporate Social Responsibility Regulations which are effective from 1st April 2014. Section 135 of the Companies Act, 2013 ('the Act'), read with Companies (Corporate Social Responsibility Policy) Rules, 2014 ('CSR Rules') requires every company having:

- net worth of Rs.500 crore or more; or
- turnover of Rs. 1,000 crore or more; or
- net profit of Rs.5 crore or more

As per the MNRE guidelines, a certain percentage of the total investment made on development of Solar Park (excluding investment on evacuation) and that for setting up of Solar power projects in the solar park may be kept aside for the affected area development.

In line with the CSR Regulations, SBE has developed their own CSR Policy in alignment with its CSR vision, principles and values, for delineating its responsibility as a socially and environmentally responsible corporate citizen. The Policy lays down the areas of intervention, principles and

mechanisms for undertaking various programs in accordance with Section 135 of the Companies Act 2013.

SBE should take some initiatives for Community Development Plan under their CSR Policy in the project affected village as suggested below:

- Employment opportunities to the people who are losing their lands in a manner that is affecting their livelihood resource in project area villages;
- Creating provisions for employment opportunities to the people who are skilled and semi- skilled in project area villages;
- Supporting the Anganwadi Centres by facilitating them with provisions of exclusive drinking water, sitting arrangement, power supply and toilet facilities for them in project area villages;
- Facilitating the village schools by providing them with amenities like chairs, benches, drinking water facilities, sports goods etc.;
- Facilitating in development and creation of health infrastructure in the study area villages
- Promotion of education, including special education and employment enhancing vocation skills especially among children, women, elderly and the differently abled and livelihood enhancement projects;
- Promoting gender equality, empowering women, setting up homes and hostels for women and orphans, setting up old age homes, day care centres and such other facilities for senior citizens and measures for reducing inequalities faced by socially and economically backward groups etc.

Under their CSR Policy, SBE should create provisions for the abovementioned matters and/ or any other pertinent issues. Recommendation under CSR Policy.

7.5.9. Road Safety and Traffic Management Plan

Scope and Purpose

The plan encompasses the address of community safety related impacts that may arise from the increased vehicular traffic due to movement of heavy equipment/machineries and vehicles along the site access and approach roads particularly during construction phase. The plan will be regularly updated by the contractor with the project progress and as vehicle movement requirements are identified in detail. Designated traffic coordinator will be responsible for overall coordination of traffic management.

During Construction Phase

The following mitigation measures will be implemented during this phase:

- Project vehicular movement will be restricted to defined access routes.
- Proper signage will be displayed at important traffic junctions along the vehicular access routes to be used by construction phase traffic. The signage will serve to prevent any diversion from designated routes and ensure proper speed limits are maintained near residential areas.
- Any road diversions and closures will be informed in advance to the project vehicles accessing the above route. Usage of horns by project vehicles will be restricted near sensitive receptors viz. schools, settlements etc. Though, no such chances are seen so far. Because, the project location is absolutely located in isolation.

- Traffic flows will be timed wherever practicable during period of increased commuter movement in the day.
- Temporary parking facilities should be provided within the work areas and the construction sites to avoid road congestion.
- Vehicular movement to be controlled near sensitive locations viz. schools, colleges, hospitals identified along designated vehicular transportation routes.
- Routine maintenance of project vehicles will be ensured to prevent any abnormal emissions and high noise generation.
- Adequate training on traffic and road safety operations will be imparted to the drivers of project vehicles. Road safety awareness programs will be organized in coordination with local authorities to sensitize target groups viz. school children, commuters on traffic safety rules and signage.
- The SBE / contractor(s) should frame and implement a “No Drug No Alcohol” Policy to prevent road accidents/incidents.

During Operational Phase

Since limited vehicular movement is anticipated during operational phase considering only the daily movement of project personnel any impacts arising from the same can be effectively addressed through implementation of mitigation measures as discussed during the construction phase. In addition, the following measures will be emphasized.

- Use of horns near the villages along the access road to villages, main plant and internal roads should be restricted.
- The vehicular movements along the access roads and highways should be restricted during the night-time.
- All the vehicles entering the access roads and plant should have Pollution under Control (PUC) certificates.
- The speed limit in the internal roads should be restricted to 25 km/hr. Proper warning signs and road safety awareness posters should be displayed to create road safety awareness among the personnel accessing the site.
- Periodic Road Safety and Traffic Management campaigns and awareness sessions should be carried out among the villagers and the plant workers/personnel to develop road safety awareness among the people likely to be impacted by the project.
- An emergency road safety plan should be framed by the Proponent to combat any emergency conditions/accidents along the highways, access roads and within plant area.
- SBE should frame and implement a “No Drug No Alcohol” Policy to prevent road accidents/incidents.
- The drivers should be given an induction on road safety and traffic management policy.
- A permanent parking lot should be provided within the main plant site (in individual work areas) and the associated facilities.
- Use of seat belts for both drivers and passengers should be made compulsory to minimize death & injuries in the event of an accident.

7.5.10. Ecological Management Plan

Construction phase

The following measures should be considered in the project design to mitigate the impact during construction phase due to the project:

- Project proponent should plan to build an appropriate level of fencing with lighting as a preventive measure to prevent man animal conflict
- All project activities shall be undertaken with appropriate noise mitigation measures to avoid disturbance to faunal population (herpetofauna) in the region.
- Activities generating high noise shall be restricted to daytime and will be mitigated to minimize the noise level outside the site boundary.
- Movement of construction and transport vehicles shall be restricted to dedicated paths to minimize any harm to small fauna within the site.
- Night-time movement of project related vehicles must be restricted along the highway.
- Transportation of construction material shall be restricted to daytime hours in order to minimize noise and disturbance to fauna in the area.
- General awareness regarding natural resource conservation shall be enhanced through trainings, posters, etc. among the staff and labourers.
- Kitchen waste shall be collected and disposed in a manner that it does not attract scavenging animals.
- Temporary barriers shall be installed on excavated areas.
- The footprints of the construction activities shall be kept to minimum so as to reduce disturbance to flora and fauna.
- Forest department must be informed in case of any wildlife sighting or any incident involving wildlife.
- If any nests of ground dwelling birds are found the Forest Department is to be notified so that the birds don't get displaced.

Operational phase

- Vegetation clearing through brush cutting for maintenance activities shall be done manually wherever possible (not applicable in this site, as there is absence of any green vegetation and land is barren)
- Any areas without vegetation cover shall be re-vegetated with locally occurring species and monitored to ensure recovery is taking place.
- Vegetation that needs to be reduced in height shall be mowed or brush-cut to an acceptable height, and not to ground level except where necessary (not applicable in this site, as there is absence of any green vegetation and land is barren)
- General awareness regarding wildlife and natural resource conservation shall be enhanced through trainings, posters, etc. among the staff and labourers.
- Solar panels shall have an anti-reflective coating to minimize the light reflecting off of the panels so that there is very less impact due to glare from the panels.

- Moreover, to minimize “Lake effect”, visual frightening techniques may be considered to frighten any bird trying to land on panels and prevent birds from landing.
- Fencing and lighting along the project boundary must be properly maintained all through the project lifecycle.
- All transmission lines need to have bird reflectors due to the movement of Raptors in the area.
- Project proponent should follow all the directions of regulatory agencies as prescribed from time to time by the Federal Government/state government / court orders.
- As WLPA, 1972 Any accidental death due to species listed in the schedule will lead to legal action against the responsible party irrespective of the location where the incident occurred.
- The power pole configuration should be designed to minimize avian electrocution risk
- Flash lamps on the WTGs should be installed to reduce collision risk to birds & bats at night

For selection of the optimum route, the following points should be taken into consideration:

- The route of the transmission lines avoids or minimizes passage through human habitations.
- No monument of cultural or historical importance is affected by the route of the transmission line.
- Ensuring that the route of transmission line does not create any threat to the survival of any community with special reference to tribal community.
- Ensuring that the proposed route of transmission line does not affect any public utility services like playgrounds, schools, other similar establishments.
- Shortest possible length and favorable ground profile.
- Avoidance of reserve forest zones which are quite significant in area in this project; also avoidance of any archaeological and other sensitive areas and unstable ground feature.
- Minimizing no. of crossing of major rivers / railway lines, national and state highways;
- Avoidance of rocky stretches and areas reserved for planned and future development.
- Restricted areas such as civil and military air field should be avoided.
- Routing should be kept away from large habitations, densely populated areas, reserve forests and hydrocarbon pipelines to the extent possible.
- Forests should be avoided to the maximum extent possible. When it is not possible, a route is selected in consultation with the Divisional Secretaries that causes minimum damage to existing plantation/forest resources.

7.5.11. Stakeholder Engagement Plan (SEP)

SBE shall develop broad level Stakeholder Engagement Plan to guide stakeholder engagement across the lifecycle of the project, demonstrating Company’s commitment towards its stakeholders while also addressing the requirements of the International Finance Corporation (IFC) Performance Standards (PSs). SEP is the process of developing appropriate management strategies to effectively engage stakeholders throughout the lifecycle of the project, based on the analysis of their needs, interests and potential impact on project success. This plan provides details on the general principles for SBE

stakeholder engagement which shall be used for implementing, monitoring and evaluating stakeholder engagement activities. The main objectives of the SEP are to:

- Enable management to develop effective stakeholder management strategies for the proposed project to build longer term relationships so as to ensure smooth functioning of the projects;
- To define and standardize the processes that the projects will use to communicate with respective stakeholders;
- To ensure regular and timely sharing of information with project teams to spruce up their understanding and skills of engaging with the stakeholders;
- Ensuring coordination in approach and message to be shared with the community regarding the company and the projects;
- To assess the efficiency of the communication process in meeting the objectives of the Stakeholder Engagement Plan and ensuring the project's 'Social License to Operate'

Stakeholder Identification, Mapping & Analysis

“Stakeholder mapping” is a process of examining the relative influence that different individuals and groups have over a project as well as the influence of the project over them. Effective stakeholder mapping is done by identifying the people/groups that have stakes/ interests in the Project either directly or indirectly and the way both can mutually benefit from each other.

Categorization of Stakeholders

A stakeholder is “a person, group, or organization that has a direct or indirect stake in a project/organization because it can affect or be affected by the Project/organization’s actions, objectives, and policies”. Stakeholders thus vary in terms of degree of interest, influence and control they have over the project. While those stakeholders who have a direct impact on or are directly impacted by the project are known as **Primary Stakeholders** (land sellers, local labourers, sub-contractors and Gram panchayat), those who have an indirect impact or are indirectly impacted are known as **Secondary Stakeholders as in the following table.**

Stakeholder Groups	Primary Stakeholders	Secondary Stakeholders
Community	Sub-contractors Contractual Labourers Landowners, land users, agricultural Labourers (if applicable) Local Communities where project is located Project Affected Families Agricultural Labours Vulnerable Community (if any)	Local community outside the immediate impact zone of the project Non-government organizations, interest groups or other civil society groups
Institutional Stakeholders	Project Developer Project investors /Lender Gram Panchayat	District schools/colleges Village Institutions (schools, health Anganwadi etc.)
Government Bodies	Regulatory Authorities. Gram Panchayats/Gram Shaba	District Administration

	Relevant government bodies and other regulators	
Other Groups		Other industries/projects Other external influences

Overall Stakeholder Engagement Strategy

The overall stakeholder strategy will be cognizant of the requirement of the various stakeholders and the level at which communication is presently being undertaken by the project.

Table 40: Stakeholder Engagement Strategy

Sl. No.	Particular	Responsibility
1	Regulatory Authorities	The regulatory authorities will be coordinated directly by SBE legal team via OEMs/developers, or project-based team. These consultations are in relation to the Power purchase agreement, power evacuation arrangements; Consent to establish related permits, revenue land allotment, or other requirements required for the wind power projects. The copy of the permits and communication will be made available to SBE at various levels. SBE team at the corporate level will be responsible for driving the timely fulfilment of the project level regulatory compliances. After completion, a copy of the relevant permits and compliances will be provided to the corporate team from all the projects, for records.
2	Community around the project	The project liaison officer of each site will be solely responsible for interaction with the community members residing near each project, through village meetings and other platforms. The minutes of the meetings will be shared with the respective site in-charge as well as the corporate liaising team in standard reporting formats in pre-decided time intervals.
3	NGOs, Civil Society, Political leaders and Media	SBE ESG head along with the developers CSR team will be accountable for any communication with local NGOs, civil society members, political leaders and media. The details of any such communication concerning the projects will be made available to the SBE corporate team in the form of stakeholder engagement records. Nobody apart from designated the SBE corporate liaising in-charge will be responsible for communication with the above-mentioned stakeholder.

Organizational Structure & Roles and Responsibilities

During the construction stage, owing to the interplay of the various actors involved, it is important to have a system in place which ensures that the community as one of the key stakeholders is aware about the Stakeholder engagement as well as the communication protocol including the grievance mechanism.

Engagement Methods

The methods of communication can be either verbal or written, based on the purpose of communication and the target stakeholder group. Some of the key methods of communication are as follows:


Meetings and Discussions: Meetings and discussions are an essential component of any communication exercise. The corporate CSR team of SBE will have regular interface with their counterparts in the project to review the current engagement with local community. These discussions are will be to communicate specific information to the target stakeholders and allow for the collective opinion of the groups to be captured and assessed.

Reports and Notices: Information disclosure is an important process of communication with the local stakeholders and is part of the applicable reference framework for the project. A mandatory

communication from the corporate team will guide project teams for the forthcoming meetings in each project. The process of disclosure of information to the communities at the project will involve the provisioning of information in an accessible manner (a manner which allows for easy understanding, such as in the local language) to the various stakeholders in a project. There will be visits of the designated members of corporate team at regular intervals to each project.

7.5.12. Provisions for ESMP Implementation

Environmental and social management plan will not be successful without a proper designated team and financial support for the same. The proposed team for environmental & social management plan is as follows:



Adequate budgetary provision will be made by the SBE for execution of environmental management plan.

8. CONCLUSION AND RECOMMENDATION

The ESIA study based on the conclusion drawn from the IFC performance standards, Equator Principles and World Bank Group's EHS Guidelines and applicable sector guidelines with respect to the intensity of impacts due to project activities on environment, resources, biodiversity, labours and community, the project is categorized as **Category B** (as per IFCs categorization of projects). This specifies that this project is expected to have limited adverse environment and social impacts, which can be mitigated by adopting suitable mitigating measures.

Selection of **Category B** is based on similar reasoning:

- **Potentially limited risks/impacts and reversible:** Environmental and social impacts of the project are anticipated during the construction phase and will encompass changes in land-use, increased noise levels, changes in air quality, use and changes in water quality, impacts on terrestrial ecology, occupational health & safety, etc. Further, there is no physical displacement. Thus, most of these impacts are limited to the project sites and their immediate vicinity and can be minimized through application of mitigation measures as proposed in the ESMP.
- **Unprecedented:** Development of Hybrid power projects is occurring in large numbers in the last decade and therefore several such projects are located across India. A Hybrid power project can therefore not be considered an unprecedented activity.
- **Limited adverse impacts on the baseline:** Solar based energy development is a non-polluting source of energy and thus is not likely to lead to any adverse impacts on the baseline environment during the operation phase. In terms of social impacts, the land required is private agricultural land; but the site location of the project does not involve any anticipated settlements and physical displacement.
- As the land parcels for the project (for both wind & solar) are yet to be demarcated, existence of private land parcel (in solar site) and vicinity of village settlement, land allotment/ procurement may result in economic or physical displacement. Hence, after allotment of land and its subsequent demarcation, further study should be undertaken to ensure the need of Resettlement Action Plan (in case of physical and economic displacement) and Livelihood Restoration Plan (in case of economic displacement).
- **Noise:** In India, there are no specific guidelines for wind power project noise levels. As per IFC's General EHS Guidelines: Environmental, Noise Management Noise, noise impacts should not result in a maximum increase in background levels of 3 dB at the nearest receptor location off-site.
- **Ecology:** The project area is plain land with sparse vegetation as reported. Chinkara, Nilgai, Indian Peafowl were observed during the site visit. As mentioned in the Late Winter Season Final Report - Bird surveys at the proposed hybrid project sites in Rewari and Devaka, Rajasthan by Bombay Natural History Society 4th May 2020 there are several high-flying birds reported. Therefore, there is a possibility of mortality of birds due to collision with the WTGs. The client shall be emphasizing to minimize the adverse impact through adequate mitigation measures during operation phase. Mitigation like daytime visual markers, visibility enhancement objects such as marker balls, bird deterrents, or diverters shall be installed on wires and transmission lines to enhance visibility of towers/transmission lines for bird to avoid avian collision.
- As reported in the Late Winter Season Final Report by Bombay Natural History Society 4th May 2020 During surveys, Great Indian Bustard *Ardeotis nigriceps* was not seen. While two unconfirmed sightings of GIB were reported by local people in year 2017–18 at Negarda (26.280847°, 71.143286°) and in between Khyala and Rewari (26.469018°, 71.052508°) which are westernmost part of the study area. Rasla enclosure, Desert National Park (DNP) is 30 km North-East from one

of the edges of project area and birds might not be using the site regularly. Footprints and feathers of migratory bird MacQueen's Bustard *Chlamydotis macqueenii* (or Asian Houbara) were seen at the Rasla area. Further studies carried out by BNHS will help in understanding the extent of movement of these birds for suggesting appropriate mitigations.

- Estimated noise generated during operation phase was calculated using Windpro software. These ambient noise levels at village level were observed to be within permissible limits specified for Residential area as per Noise Pollution (Regulation and Control) Rules, 2000 (without project), However the increment in ambient noise level due to WTG operations is anticipated to increase up to a range of 1.7 to 3.8 dB(A), in night time during the operational phase of the project.
 - Out of 7 Identified receptors SBE_11_R1 and SBE 18 (1) are temporary structures and SBE05_R1 is found to be Government office hence very limited mobility expected during day time and hence it is interpreted that there will no impact to these receptors during operation phase of the project.
 - However, for permanent Structures such as SBE 39(1), SBE65_R1, SBE65_R2, SBE65_R3 following mitigation measures suggested in this report shall be followed.
- **Shadow Flicker:** Shadow Flicker Modelling results show that out of 7 identified receptors 3 receptors will receive shadow for more than 30 hours per year from 10 WTGs. However, majority of the receptors identified during site survey are Temporary use structures (Pump house, resting shade, Agricultural storage) located within 300 m radius of WTG's. The modelling results is provided in Appendix. G.
- WTG profiling of all locations was undertaken based on Ground truthing and desk-based study. Site visit was undertaken to understand the status of receptors, from this study. However as per the WTG profiling carried out on site by SBE and Arcadis, two receptors found to be sensitive SBE 5 R1 and SBE 65 R3 as it is a permanent structure (Government office cum control building, Residential House,). SBE_11_R1 are found to be temporary use (cattle shade). Impacting WTGs with status of receptors are provided in **Table 8**.
- The project will improve the socio-economic conditions of the surrounding areas. Job opportunity will improve significantly in the project area and its surrounding. The project will create many jobs to the local population both during construction and operation phase with corresponding increase in income. Other associated business activities like transport, hotels, consumer goods etc., will also be benefited.
- To conclude, with the proper implementation of the Environmental and Social Management Plans (ESMP) and undertaking the recommendations, the proposed project should be in comply with the IFC Performance Standards, other lender(s) requirements.

8.1. Impacts Assessment

ESIA was focused on interactions between the Project activities and various resources/receptors that could result in significant impacts. During construction and operation phase of the project environmental management plan shall be followed mentioned in **Table 41**. The table below presents the outcomes of the comprehensive assessment of identified impacts as a result of the various phases of the Project.

Table 41: Impact Assessment Summary

Impact Description	Significance	
	Without mitigation	With mitigation

Construction phase

Landscape and visual	Low	No impact
Water resources and quality	Moderate	Low
Air quality	Moderate	Low
Soil quality	Low	Low
Noise level	Moderate	Low
Solid waste	Moderate	Low
Change in local topography	Moderate	Low
Ecology	Moderate	Low
Engagement of local and migrant labour	Moderate	Low
Labour accommodation	Moderate	Low
Land lease	Low	Low
Impact on indigenous people	Low	Low
Impact on archeologically important sites	No impact	No impact
Community engagement	Moderate	Low
Occupational health and safety	Moderate	Low
Operation phase		
Hazardous waste management	Moderate	Low
Solid waste management	Moderate	Low
Groundwater abstraction	Moderate	Low
Wastewater management plan	Moderate	Low
Ecology & biodiversity	Moderate	Moderate
Corporate social responsibility	Moderate	Low
Occupational health and safety of workers	Moderate	Low

8.2. Level of compliance and gap with Applicable IFC Standards

A gap assessment against the requirements of IFC environmental and social performance standards has been made, to determine to what extent the findings related to the project management systems and performances are aligned with the intended requirement of the IFC reference framework.

ESIA identifies the sustainability of the project in pre-construction phase which more precisely helps to the proponent towards project's viability with respect to the environment & social aspects. During execution phase of the project ESDD shall be conducted which will mainly emphasizes to finding the gaps of ESMP/ESAP as recommended in ESIA report. During construction/operation phases Identified gaps /deviation of the recommendation along with principles/performance standards can be highlighted.

In this section, IFC performance standard, compliance to all environmental, health, safety and social regulation together with all sub-requirements are presented next to a gap assessment, recommendations and references to the actions in the Environmental & Social Action Plan (ESAP).

Table 42: Environmental and Social Action plan

Sr. No	Requirement	Applicability	Status/ Observations	Recommendations	Responsibility	Timeline
Performance Standards						
1.	Performance Standard (PS) - 1 Assessment and Management of Environmental and Social Risks and Impacts	Applicable	The project will have environmental and social impacts due to generation of onsite air emissions, noise, domestic wastes from site office and rest rooms, and generation of hazardous wastes from the construction site.	SBE is required to fulfil the following requirements: <ul style="list-style-type: none"> • Environmental and social action plan; • Identification of risks and impacts; • Management program; • Organizational capacity and competency; • Training for security and safety workers; • Emergency preparedness and response; • Stakeholder engagement/ grievance redressal; and Monitoring, reporting and review.	SBE and its contractors	To be Followed during construction and operation phase

Sr. No	Requirement	Applicability	Status/ Observations	Recommendations	Responsibility	Timeline
2.	PS 2: Labour and Working Conditions	Applicable	<p>As reported about 2900 labourers are estimated to be deployed in the peak construction phase.</p> <p>The contractor's workforce will comprise of skilled, semi-skilled and unskilled labours, which may be sourced from the nearby village settlements depending on their skills and capabilities.</p>	<p>The worker accommodation standards as laid down by ILO is presented in Error! Not a valid result for table. of the document.</p> <p>IFC guidance note on "Labour and working condition" shall be followed by project developers and contractors.</p> <p>SBE shall prepare Labour engagement plan in line with IFC guidance manual and include in contractors agreement.</p> <p>The company, as a part of oversight procedures will need regular monitoring of compliance to the aforesaid guidelines/requirements and ensure that these are met at all the project sites. Internal audits and follow up on corrective actions will also need to be undertaken to assess efficacy of the oversight system at all the said project sites</p>	SBE and its contractors	To be Followed during construction and operation phase
3.	PS 3: Resource Efficiency & Pollution Prevention	Applicable	The project involves use of resources like land and water. Improper handling of broken and damage solar panel, other waste may result contamination.	Recommendations given in Table 3 -2 and Table 7-1 shall be followed in order to reduction in pollution.	SBE and its contractors	To be Followed during construction and operation phase
4.	PS 4: Community Health, Safety and Security	Applicable	Heavy vehicles would use the existing village roads. several staff will remain involved during the operation period. The generated electrical energy will be transmitted through high voltage power line, thereby exposing the	<p>SBE and contractors will ensure proper stakeholder consultations, grievance redressal mechanism, communication to workers and other stakeholders to avoid any conflict between migrant labour and local community.</p> <p>Construction of boundary wall may result in restriction of access/ increased</p>	SBE and its contractors	To be Followed during construction and operation phase

Sr. No	Requirement	Applicability	Status/ Observations	Recommendations	Responsibility	Timeline
			<p>staff and community to electrical injury cannot be ignored.</p> <p>For Solar plant, SBE shall deploy 15-20 person and EPC shall deploy Appx. 200 personals as security guard</p> <p>For Wind: Dove Resources Private Limited, Will deploy as per site requirements</p>	<p>distances from common property. Interaction of community with project staff especially security staff would occur.</p>		
5.	PS 5: Land Acquisition and Involuntary Resettlement	Not Applicable	As reported, the proposed project is falling in government revenue land and it will not result in any economic or physical displacement and no CPRs are envisaged for the proposed project.	-	SBE	To be Followed during construction and operation phase
6.	PS 6: Biodiversity Conservation and Sustainable Management of Living Natural Resources	Applicable	<p>The project area is not located within any notified ecologically sensitive area</p> <p>As WLPA, 1972 Any accidental death due to species listed in the schedule will lead to legal action against the responsible party irrespective of the location where the incident occurred.</p>	<ul style="list-style-type: none"> - The power pole configuration should be designed to minimize avian electrocution risk - Bird diverter should be installed in transmission line which the client will be complying with respect to the sensitive areas as suggested by the study undertaken by Bombay Natural History Society (BNHS) - Follow the DOs & DON'Ts as applicable, attached in Appendix 	SBE and its contractors	To be Followed during construction and operation phase
7.	PS 7: Indigenous Peoples	Not Applicable	No impact on tribal community has been envisaged for the proposed hybrid project.	Engage local tribal people in the construction & development of the project to the extent feasible where skills are matched	SBE	To be Followed during construction and operation phase

Sr. No	Requirement	Applicability	Status/ Observations	Recommendations	Responsibility	Timeline
8.	PS 8: Cultural Heritage	Not Applicable	As reported during consultations, there is no designated archaeological or cultural heritage site within 10 Km radius of the study area village.	-	-	-
Environmental, Health, Safety and Social Regulations						
9.	Consent to Establish from Rajasthan Pollution Control Board (RSPCB) under Water (Prevention & Control of Pollution) Act, 1974 and the Air (Prevention & Control of Pollution) Act. 1981	Not Applicable	-	As per CPCB notification No. B-29012/ESS(CPA)/2015-16; dated March 07, 2016 Hybrid power project falls in White category and therefore white category industries do not require to obtain consent of the board, an intimation to the RSPCB shall suffice (APPENDIX A).	SBE	To be Followed before operation phase
10.	Hazardous Waste authorization as per Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016	Applicable	Required For storage, transfer & recycling of transformer waste/used oil.	Agreement with Authorized vendor shall be made. During construction phase EPC contractor will be responsible and during operations, it will be under O&M contractor scope	SBE and its contractors	To be Followed during construction and operation phase

Sr. No	Requirement	Applicability	Status/ Observations	Recommendations	Responsibility	Timeline
11.	NOC from Village Panchayat	Applicable	In process	NOC from Gram Panchayat shall be obtained if applicable; with Govt land allotment and NOC issued by DC for lease signing, GP NOC may not be required	SBE	To be obtained before construction phase
12.	Factory License under factories act 1948	Applicable	Need to be obtained	With reference to the factories act 1948, the same is applicable because this solar plant generating, transforming, or transmitting electrical energy and more than 10 workers are employed/working at site.	SBE and its contractors	Do to obtained during Commissioning Phase.
13.	Power Purchase agreement	Applicable	Obtained	-	SBE	To be Followed during construction and operation phase
14.	Approval for extraction of ground water	If required needs to be obtained	If required needs to be obtained	Central Ground Water Board (CWGB) approval for extraction of groundwater requires to be obtained in case project proponent intends to install bore wells/dug wells for ground water extraction during construction and operation phase As reported by SBE, water required for construction and operation phase will be met by vendor from the safe and approved sources.	SBE and its contractors	To be Followed before construction and operation phase
15.	Land Lease	Applicable	In process	Land sub lease for both Wind & Solar project site needs to be obtained.	SBE	To be obtained before

Sr. No	Requirement	Applicability	Status/ Observations	Recommendations	Responsibility	Timeline
						construction phase

Brief Assessment of Project:


- **Location of project site w.r.t ecologically sensitive area:** The project area is not located within any notified ecologically sensitive area
- Project proponent should follow all the directions of regulatory agencies as prescribed from time to time by the Federal Government/state government / court orders.
- **Source of Pollution:** The Hybrid power project is based on clean technology and is not likely to cause any significant pollution. Further, the project will help to reduce GHG emissions.
- **Resettlement:** No resettlement and rehabilitation involved in the project as the proposed project land is Rajasthan state government land.
- **Project Benefit:** The produced electricity will be evacuated to the state electricity grid and will help to cater the energy requirement
- **CSR plan:** The CSR plan focused on community development will be implemented by the SBE.



The project will have number of positive impacts which are:



- Agriculture in the area is majorly dependent on rain and large portion of the land remains barren most part of the year; The project will generate more employment to local community.
- Various CSR activities will be implemented in the study area village.
- During the construction phase, local populations often supply manpower for services such as those of drivers, vehicle vendors, contractors, watchmen etc.




Complaints received through Grievance Redressal Mechanism (GRM) procedures shall be addressed by SBE in line with the procedure formulated in ESMS. This will overcome public inconvenience during the proposed project activities. Based on the environmental and social assessment and surveys conducted for the project, the potential adverse environmental impacts can be mitigated to an acceptable level by implementing adequate mitigation measures identified in the ESMP, whereas project will improve the socio-economic conditions of the surrounding areas.





APPENDIX A: WTG PROFILING




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE01	719078	2919317	286	Barr en	undula ted	Mat i ka Gol	203	-	-	-	-	Inter nal villa ge road	-		


WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE02	718303	2918516	304	Barren	undulated	Devka	-	-	-	-	-	Internal village road	-	 	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE03	718713	2918491	297	Barr en	undula ted	Dev ka	N/A	-	346	-	-	Inter nal villa ge road	-		
SBE04	717483	2917871	322	Barr en	undula ted	Dev ka	-	-	-	-	-	Inter nal villa ge road	-		



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE05	717990	2917759	318	Barren	undulated	Devka	-	159m	-	-	Internal village road	-	  		



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
															
SBE06	718361	2917600	304	Barren	hillock, undulated	Devka	-	-	267	-	-	-	-		 




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE07	718632	2917298	298	Barr en	hillock, undulated	Dev ka	-	-	553	118	-	-	-	  	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE09	720135	2917217	269	Barr en	Flat	Dev ka	390	-	-	-	-	-	400		






WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE10	717562	2916811	313	Barr en	hillock	Dev ka	-	150	-	-	-	Internal villa ge road	-	  	



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE11	717871	2916504	307	Barr en	Flat	Dev ka	N/A	-	105	-	-	-	-	 	






WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE12	716854	2916185	306	Barren	undulated	Devka	-	-	-	-	-	-			



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE13	717203	2915944	319	Barr en	hillock	Dev ka	-	-	-	-	-	-		 	


WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE15	716551	2915398	303	Barr en	Flat	Dev ka	270	-	-	-	-	-		 	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE16	716771	2914847	306	Barr en	Flat	Bhe rup ura	-	-	-	-	-	-		 	
SBE17	716990	2914594	301	Barr en	Flat	Bhe rup ura	450	-	-	-	-	-			




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE18	717339	2914403	285	Barr en	Flat	Bhe rup ura	600	-	198	-	-	-	-	-	
															




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE19	718470	2913813	274	Barr en	Flat	Bhe rup ura	300	-	-	-	-	-	578		 
SBE20	717113	2913662	279	Barr en	Flat	Bhe rup ura	-	-	-	-	-	-	-		



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE21	717421	2913430	280	Barr en	Flat	Bhe rup ura	-	270	-	-	-	-			



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE24	714991	2911701	300	Barr en	undula ted	Bhe rup ura	-	-	-	-	-	-			




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE25	715203	2911325	294	Barr en	undula ted	Bhe rup ura	-	-	340	330	-	-	-	  	



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE26	715505	2911015	295	Barr en	undula ted	Bhe rup ura	-	-	310	-	-	-	-	-	  




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE27	716324	2910963	268	Barr en	Flat	Bhe rup ura	240	-	360	-	-	-	-	  	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE28	716895	2910198	277	Barr en	undula ted	Bhe rup ura	350	-	-	-	-	-	-	 	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE31	715295	2909278	279	Barr en	Flat	Had wa	-	-	-	-	-	-			


WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE32	715985	2910171	295	Barr en	undula ted	Bhe rup ura	560	-	520	-	-	-	-	  	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE33	716107	2909265	287	Barren	Flat	Bherapura	400	-	-	-	-	-			




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE37	714917	2908360	271	Barr en	Flat	Had wa	-	-	306	-	-	-	-	  	






WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE38	714080	2908756	283	Barr en	Flat	Had wa	-	-	376	-	-	-	-		
SBE39	715183	2908005	272	Barr en	Flat	Had wa	120 (Single phase supply line)	-	273	-	-	-	-		


WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE40	715890	2906447	287	Barr en	undula ted	Had wa	450	-	267	-	-	-	-	  	



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE42	716825	2907233	263	Barr en	Flat	Had wa	435	-	-	-	-	Internal Villa ge road	-		



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE43	719040	2908281	273	Barr en	undula ted	Ma nih ari	55 (11kv line)	-	379	-	-	-	264 (NH 15)		
SBE44	718414	2909089	275	Barr en	undula ted	Ma nih ari	263	-	-	-	-	-	750		



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE47	719619	2911831	289	Barr en	undula ted	Ma nih ari	226	-	-	211	-	36 (Kat cha road)	-	  	




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE49	719825	2912937	295	Barr en	Flat	Manihari	270	-	-	-	-	70	-		
SBE55	716078	2913232	281	Barr en	Flat	Bherupura	-	-	-	-	-	-	-		 




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE56	716249	2912987	304	Barr en	Flat	Bhe rup ura	400	-	560	-	-	-	-		





WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE57	716224	2912150	274	Barren	undulated	Bherupura	394	-	-	-	-	Internal village road	-		
SBE58	716915	2911433	289	Barren	Flat	Bherupura	320	-	-	-	-	-	-		




WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE60	719621	2913340	291	Barr en	undula ted	Jun ejo ki dha ni	550	-	398	-	-	-	-	 	



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE61	720236	2912644	288	Barren	undulated	Manihari	208	-	-	-	-	-			



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE62	719949	2914086	293	Barr en	Flat	Jun ejo ki dha ni	430	-	450	-	-	-	-	  	



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE63	720365	2916562	278	Barr en	undula ted	Dev ka	217	-	-	-	-	-	400	  	



WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE65	721480	2914167	292	Barren	undulated	Junjokidhani	-	-145 (west), 296 (east)	-	-	160	-			
SBE67	717912	2918710	301	Barren	undulated	Devka	-	-	-	-	-	-			


WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
SBE68	715590	2906694	281	Barr en	undula ted	Had wa	120(11kV line)	-	217	-	-	-	-		 

WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
															
SBE081	719145	2910278	281	Barr en	undula ted	Ma nih ari	-	-	373	-	-	-	225		

WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
NEW6	717344	2915191	326	Barren	undulated	Devka	-	-	-	-	-	-			

WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
NEW5	719433	2912280	298	Barr en	undula ted	Dev ka	-	-	-	-	-	150	-		
NEW4	717041	2912137	276	Barr en	Flat	Bhe rup ura	420	-	-	-	-	-	-		

WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
new 2	717446	2915761	327	Barren	undulated	Devka	-	-	-	-	-	-			

WTG Locations				Land Cover	Topography	Name of the Village	Nearest Structure			Water Body (m)	Religious Structure (m)	Roads		Google Earth image (3.8.2019)	Site visit photographs
Location	Easting	Northing	Elevation (m)				Distance from EHV (m)	Permanent Str (m)	Huts (m)			Village Road (m)	National Highway (m)		
new3	717140	2916244	325	Barr en	hillock	Dev ka	-	-	-	-	-	-			

APPENDIX B: ILO GUIDELINES

No.6

ILO HELPDESK

ASSISTANCE@ILO.ORG



International
Labour
Organization

Workers' housing

Housing provided to workers as part of the employment contract should meet certain minimum specifications in respect of the nature and standard of the accommodation and facilities to be made available.

The following guidance is based on international labour standards. National or state regulation will often set baseline specifications as part of housing, labour, health or even fire safety regulations; they should be checked and followed. National employers and workers organizations may also be a good source of information on national law, collective bargaining agreements and customs pertaining to housing for workers; or may be able to refer you to the appropriate statutory authority.

Guiding principles

➔ In providing worker¹ housing, the objective should be to ensure "adequate and decent housing accommodation and a suitable living environment"² for workers. This includes upkeep, improvement and modernisation of housing and related community facilities.³

It is "generally not desirable that employers should provide housing for their workers directly".⁴ Employers are encouraged to help their workers to obtain housing through autonomous private agencies, public housing

schemes, or cooperatives.⁵ This is because workers living at the work site on property owned or controlled by the employer tend to be less integrated into the local community, and more dependent on the employer. However, certain circumstances, such as when an undertaking is located far from normal centres of population, or where the nature of the employment requires that the worker should be available at short notice may require the employer to provide housing for his or her workers.⁶

If housing is provided by the employer "the fundamental human rights of the workers, in particular freedom of association, should be recognised."⁷ Arrangements where accommodation and communal services are provided as payment for work should take care to ensure that the interests of the workers are protected. If rent is charged, it should not cost the worker more than a reasonable proportion of his or her income.⁸

Siting and construction

➔ The housing and related community facilities should be of durable construction, taking into account local conditions, such as liability to earthquakes.⁹

The location of workers' housing should ensure that workers are not affected by air pollution, surface run-off or sewage or other wastes.¹⁰

Housing Standards

➔ Housing should ensure "structural safety and reasonable levels of decency, hygiene and comfort".¹¹ The undertaking should ensure the following:

- a) a separate bed for each worker;
- b) adequate headroom, providing full and free movement, of not less than 203 centimetres;
- c) the minimum inside dimensions of a sleeping space should be at least 198 centimetres by 80 centimetres;
- d) beds should not be arranged in tiers of more than two;
- e) bedding materials should be reasonably comfortable;
- f) bedding and bedframe materials should be designed to deter vermin;
- g) separate accommodation of the sexes;
- h) adequate natural light during the day-time and adequate artificial light;
- i) a reading lamp for each bed;
- j) adequate ventilation to ensure sufficient movement of air in all conditions of weather and climate;
- k) heating where appropriate;
- l) adequate supply of safe potable water;
- m) adequate sanitary facilities (see below);
- n) adequate drainage;
- o) adequate furniture for each worker to secure his or her belongings, such as a ventilated clothes locker which can be locked by the occupant to ensure privacy;
- p) common dining rooms, canteens or mess rooms, located away from the sleeping areas;
- q) appropriately situated and furnished laundry facilities;
- r) reasonable access to telephone or other modes of communications, with any charges for the use of these services being reasonable in amount; and

¹ Workers' Housing Recommendation, 1961 (No. 175). The section entitled "Suggestions concerning methods of application," Part I, paragraph 5, encourages "equality of treatment between migrant workers and national workers". Therefore, this guidance applies equally to migrant workers and national workers.

² R. 115, General Principles, Part II, paragraph 2.

³ R. 115, paragraph 3.

⁴ R. 115, Part IV, paragraph 12(2).

⁵ R. 115, Part IV, paragraph 12(1).

⁶ R. 115, Part IV, paragraph 12(2).

⁷ R. 115, Part IV, paragraph 12(3a).

⁸ R. 115, Part II, paragraph 4, Part IV, paragraph 12(3c) and (4).

⁹ R. 115, Suggestions Concerning Methods of Application, Part I, paragraphs 10-11.

¹⁰ R. 115, Suggestions Concerning Methods of Application, Part IX, paragraph 43.

¹¹ R. 115, paragraph 19.

APPENDIX C: SAMPLE QUESTIONNAIRE FOR COMMUNITY CONSULTATION

<i>Name of the village</i>		<i>Panchayat</i>			
<i>Taluka/Block</i>		<i>District</i>			
<i>Respondent</i>					<i>Date:</i>
<i>Total Population</i>		<i>Total Male</i>		<i>Total Female</i>	<i>HH No.</i>
<i>Religion</i>	<i>Name</i>	<i>%</i>	<i>Name</i>	<i>%</i>	
<i>Caste/Group</i>	<i>Name</i>	<i>%</i>	<i>Name</i>	<i>%</i>	
	<i>Name</i>	<i>%</i>	<i>Name</i>	<i>%</i>	
<i>Education Level</i>	<i>Illiterate %</i>	<i>Primary %</i>	<i>Secondary %</i>	<i>H.S. %</i>	<i>Graduate %</i>
<i>Occupation</i>	<i>Agriculture %</i>	<i>Business %</i>	<i>Service %</i>	<i>Labor %</i>	<i>Other %</i>
<i>Source Drinking water facility</i>	<i>Tube well</i>	<i>Dug well</i>	<i>Stream</i>	<i>Piped water</i>	<i>Hand pumps</i>
<i>Sanitation facility</i>	<i>Pit latrine %</i>	<i>Sanitary latrine %</i>	<i>Open defecation %</i>	<i>Other %</i>	
<i>Electricity (Available %)</i>			<i>Electricity availability in HH</i>		
<i>Village road type/transport facility</i>					
<i>Schools (distance)</i>	<i>Primary</i>	<i>Middle</i>	<i>H. S.</i>	<i>College</i>	<i>Anganwadi</i>

Health Facility (distance)	Health sub Centre	Primary	Hospital	Others				
Major diseases								
Major crops cultivated	Name	Period	Yield (q/acr)	Rate/q	Name	Period	Yield (q/acr)	Rate/q
Irrigation Facility	Ponds	River	Groundwater	Others				
Average land holding size								
Land rights								
Livestock	Cow	Buffalo	Goat	Pig	Fowl			
	Duck	Others						
Grazing areas								
Cooking medium and source	Fuel Wood	Kerosene	Cow Dung Cake	Crop Residue	LPG			
	Others							
Common Property Resources (CPR)	Religious and Cultural Places	Sacred Places	Community Hall	Community Ponds	Cremation Ground			
	Streams	Canal	River	Others				

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

Major rituals and festivals	Name	Period	Name	Period	
Fishing area		Name of the			
Forest	Wood	Timber	NTFP	Others	
Any Vulnerable Groups like- landless/homeless- people, Women headed HH, Orphans etc.					
Any program related to child / women health care program					
Any employment generation program					
HH & Cottage industries in the village / area					
Any Scheme / Program related infrastructure / any amenities					
Occurrence any Natural Calamities / industrial / anthropogenic Hazard					

APPENDIX D: ATTENDANCE SHEET OF STAKEHOLDERS CONSULTATION

Meeting with Sarpanch & Locals

S.No.	Name	Occupation	Village	No.	Seg.
1.	Jalam Singh	Sarpanch	Rivdi	9828484962	
2.	Aman Singh	Farmer	Rivdi	9001660599	
3.	Sawai Singh	Farmer	Rivdi	7014813185	
4.	Dilip Singh	Farmer	Rivdi	7014813185	
5.	Latif Khan	Business	Rivdi	9413254962	
6.	Lalit Kumar	"	Rivdi	9079255520	
7.	Aidan Singh	"	Rivdi	9982071402	
8.	Mana Ram	Farmer	Rivdi	9828623524	


Meeting with School Teacher

Name	Occupation	Village
1. Raju Ram Sultana	Govt. Teacher / B.L.O Rivdi	PS. Bhujaia
	No.	Signature
	8003603205	
2. Rishmel Dan		7665680221
	Rivdi School (H.S).	

Meeting with Forest Ranger

Name	Occupation	Village
Sunder Singh	Forest Guard	Rivdi


No. 9950961651

Signature


Meeting with Irrigation official

Name	Occupation	Village
Nakhta Ram	Irrigation Supervisor	Sajit


No. 7340597131

Signature


Meeting with ~~Angambadi~~ ^{ANM} ~~Workers~~

Name	Occupation	Village
Anita Singh	ANM	SC, Sajit

No. 9314090139

Signature


Teejo ANM, Rivdi 9024027582

Meeting with Revenue official (Wind)

Bheru Singh	Patwari	Bherupura Hadwa
-------------	---------	--------------------

No. 6377362542

Signature *Bheru Singh*

Meeting with Sarpanch of Hadwa (Wind)

Anoop Singh	Sarpanch	Hadwa, Bherupura, Mankhari
-------------	----------	----------------------------------

No. 8118878433

Signature *Anoop Singh*

Meeting with Revenue official (Solar)

Name	Occupation	Village
Kishna Ram Bhadu	Patwari	Rewdi

No. 9784692365

Signature *Kishna Ram Bhadu*

Meeting With Anganbadi Worker.

Name	Occupation	Village
Geeta Dori	Anganbadi Worker	Sajit

No.
~~7340 74246788~~
7424886726

Signature.
[Signature]

APPENDIX E: SUMMARY OF STAKEHOLDERS CONSULTATION

Stakeholder Group	Village/ Department/ Designation	Name	Methodology	Findings
Project Proponent SBE	<ul style="list-style-type: none"> Representatives SBE Renewables Ten Pvt Ltd 	<ul style="list-style-type: none"> Mr. Abhishek (Project Head) Mr. Anil Mishra (Rajasthan Project head) 	<ul style="list-style-type: none"> Telephonic interaction 	<ul style="list-style-type: none"> The background of the 450 MW Hybrid Power Project One of the first Hybrid project by SECI. The project was awarded in Jan 2019 and thereon it took seventh months for PSA and it got amended in October - November 2019. After that PPA was signed in December 2019. 7 May 2021 has been given the timeline for commissioning of project. Considering the covid-19 crisis Ministry of Renewable Energy has given a general guideline to extend the date for commissioning for the period of lockdown plus 30 more days for remobilisations. August 2021 would be the timeline for commissioning of project. Foundation work for wind project will start during July and august 2020 and it will get operation by November December. The construction work for Solar project will start a bit late in next year Jan-Feb, 2021 and commissioning will be in July & August 2021. Transmission line work is under Kintech scope of work and it will a mix of government & private land. As reported by SBE, there is no hurdle/challenge in land procurement for transmission line. There is no plantation, any vegetation and no agriculture activities on the proposed land. Kintech will start working on transmission line which is 30 km from wind PSS to Solar PSS and 50 km from solar PSS to PGCIL GSS NOC from Gram Panchayat is under process as reported. All the project land is on lease basis for 30 years and it is revenue land. It was also mentioned that no economic & social displacement involved in land procurement for the project.
Land Aggregator	<ul style="list-style-type: none"> Kintech Energy Private Limited 	<ul style="list-style-type: none"> Mr. Jigar Saha 	<ul style="list-style-type: none"> Telephonic Interaction 	<ul style="list-style-type: none"> Proposed project is falling on Government Land which is approx. 2700 Acres Land is allotted on lease basis to SBE for 30 Year DLC rate is Rs. 30000 per bigha and @ 5% yearly increment There is no private land procured for the land. The 450 MW Hybrid project are divided as 420 MW for solar project and 105 MW for wind project are mostly continuous land.

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

Stakeholder Group	Village/ Department/ Designation	Name	Methodology	Findings
				<ul style="list-style-type: none"> As per the government land categorization, it is waste land and as per government norm it is allotted for Renewable Energy Project. There is no encroachment and settlement on the land. No CPRs are reported on the land. It's basically sand dunes which is locally called as Barani land. there is no dependency of local on the revenue land at present.
Irrigation Department, Jaisalmer	Irrigation Officer	Dept. Mr. Ram Ji	Naksha • Telephonic Interaction	<ul style="list-style-type: none"> There is severe shortage of water No government schemes for irrigation in the area Main source of irrigation is old pond/well Drip irrigation mechanism is not practised in the region Main food crops are jwar, bajara, mung and til
Panchayat Members	Harwa Panchayat	Gram • Dhapo Kanwar(Panchayat Head) • Mr. Anoop Singh Rathor (Panchayat Secretary)	• Telephonic Interaction	<ul style="list-style-type: none"> 5 villages falling in Harwa Panchayat namely Hadwecha, Harwa, Bheroopura, Manihari and Check Harwa. Village is resided by 200 swarna caste mainly Brahmin & Rajputs households, 300 OBCs households and 250-300 and 50 households of SCs & STs respectively. There are 150 muslim Voters are there in Harwa village. 30% houses are pacca and 70 % are kuccha houses. 70 % of the families have moved to Dhani or on farms land and set up a house there with their cattle. Hadwa & Hadwecha is only connected with pucca road rest of the villages are only having kuccha road. NO irrigation facilities available in the village Agriculture and animal husbandry are the main source of livelihood of people. Almost 90 % of the locals are dependent on animal husbandry like cows, sheep, goats etc. Average per family land holding size is 25 bigha. Gochar land is available in all the Harwa GP villages except Bheroopura.. As reported village has a primary health centre facility and anganwadi center in Hadwa village. Most of the households in the village has toilet facilities 70 % Villagers use firewood, Cow dung, and biogas as a fuel for cooking purpose and around 30 % families are using LPG. Tubewell is the main source of water for drinking purpose

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

Stakeholder Group	Village/ Department/ Designation	Name	Methodology	Findings
				<ul style="list-style-type: none"> • Village has two schools one is primary school and one secondary school. • Power supply is available only for 7- 8 hrs • There are 5 schools in Hadwa Panchayat, 2 primary schools in Harwa and Manihari, 1 senior secondary school in Hadwecha, 1 senior school and primary school in Harwa and 1 upper primary in Manihari. • Separate toilet facilities are available in all schools as reported during consultation • For higher education parents send their children to Seo town which is 7 Km from Harwa. • No community toilets available in the village. • Transport and communication facilities are poor, and no government buses run. Locals use personal vehicle or taxies available for commutation. • Village secretary have expressed his view to have a separate schools for girls, skill development program for women and young girls, provisions for another tubewell, road in Hadwa, community hall for villagers and separate hall for local artists and employment opportunities for youth.
Circle Office, Land procurement	Bhairoopura, Patwari	• Bhairo Singh, Patwari	• Telephonic Interaction	<ul style="list-style-type: none"> • The region is unirrigated and mostly barren land are there. And no irrigation facilities available. • Locals are mostly dependent on Barani food crops • Many Solar projects are coming in the area and providing job opportunities to local youth. • Per hectare production is very less as compared to land holding per households • Location is good for solar & wind projects are people are happy to give their land for power plants • Explained the land procurement process for lease of land. source of drinking water is personal tubewell/wells. • Government has provided pipeline facility to few households for supply of drinking water. Few use tankers and personal tubewell for domestic purpose.

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

Stakeholder Group	Village/ Department/ Designation	Name	Methodology	Findings	
Primary Health Centre	sub Sajid Center	Health	Ms. Anita Singh (ANM)	Telephonic Interaction	<ul style="list-style-type: none"> As informed by ANM no sufficient medicines are available in the centre. Health centre has 6 rooms and no bed available. Electricity and water supply are not available in the centre. Routine check-up and immunization happens in the centre. As of now Malaria was the major disease reported in the area. Average 10-15 patients visit the health centre daily. Major area of concern is labour room and storage room unavailability.
Land revenue department	Reevadi Village, Seo Tehsil	Krishan Bhadu	Ram	Telephonic conversation	<ul style="list-style-type: none"> Land procurement process is in initial stage. Survey of the land has been completed. There are no mining activities on the land. It's a continuous land and its mostly barren land and no irrigation facility. Sangad is the main source for water supply in nearby areas. No legal cases and pending grievances reported yet. Land is barren and non- agriculture. No legal and any local grievances yet reported from the villagers. Currently land identification & land procurement process is going on. Land is free of any encroachments.
Forest Range office	Forest Barmer	Guard,	Mr. Jalan Singh	Telephonic Interaction	<ul style="list-style-type: none"> The area where the project is proposed is a 'banjar' (Fallow) land. The project area and nearby area is devoid of any vegetation and has sparse vegetation. There are a very few wild animals seen in the area-mainly Dessert fox, Chinkara and Nilguy. But these animals are rarely seen. He mentioned that the Desert National Park is located about 45kms from the project site and there are no Great Indian bustard enclosures around the project and in the immediate vicinity of the project. There is no forest land located nearest to the project site.
Primary School & Secondary School	Harwa Village	Mr. Palivani (Principle)	Prakash	Telephonic mostInteraction	<ul style="list-style-type: none"> Government senior secondary school, Harwa village. Project area is located around 3km from the school. Toilet, drinking water, electricity facilities are available.

Stakeholder Group	Village/ Department/ Designation	Name	Methodology	Findings
				<ul style="list-style-type: none"> School buses are not available. Students commute to school with bicycle or by walking. Playground is available but it needs to be developed properly. Major area of concern is RO maintenance, Insufficient Chair and table.
Anganwadi Center	Reevadi Village	<ul style="list-style-type: none"> Ms Geeta (Assistant) Meena (AASHA worker) Puja (Worker) 	<ul style="list-style-type: none"> Telephonic Interaction 	<ul style="list-style-type: none"> This village has 1 anganwadi centre. There are 4 rooms with boundary wall but no toilet facilities Around 100 kids and 50 women are enrolled. Health check-up is carried out by ANM 2 times in a month for kids and pregnant women. Major area of concern is no electricity, no sitting arrangements and water supply is through nearby tanka. No major engagement activities for women in the village They wanted some for skill development programs or provide Sewing machine for them Demanded Swings and TV for kids in anganwadi
Villagers	Reevadi Village	<ul style="list-style-type: none"> Jalan Singh, Sarpanch Aman Singh Sawai Singh Dilip Singh Latez Khan Lalit Kumar Aidaan Khan Mana Ram 	<ul style="list-style-type: none"> Telephonic Interaction 	<ul style="list-style-type: none"> Village is resided by mix of communities like Swarn castes like Brahmin, Rajput, OBCs and STs & SCs communities. Animal Husbandry and agriculture as the main source of livelihood. As reported village has a primary health centre facility. Most of the households have toilet facilities LPG is used as a fuel for cooking food. Village has two primary schools and one secondary school. Tubewell is used for drinking purpose. Electricity is available 6-7 hrs Villagers are aware about the project. People are looking forward for the employment generation due to this project.

Stakeholders Consultations during Site Visit

Consultation with patwari

- kishana Ram Bhadu - Patwari – Phone: 9784692365
- The project is spread over in an area of approx. 2100 Acre.
- It is proposed on govt waste land. Villagers are aware of the project and they are happy about it.
- The land had been taken on lease basis from govt for a period of 30 years, which can extendable by another 10 years if required.

- No cultural heritage site or temples are there within 10km radius. There is a temple named Kapooria Math temple that is about 15-20km away from the site and it comes under Kapooria village.
- There is no temple or common property resources inside the site or its periphery.
- Rewari is having 1 crematorium and 1 graveyard.
- There is a water reservoir which is situated within 2km distance from the site.
- There is no grazing land. There are no encroachers in the site.
- The land allotment by revenue department is yet to be done and land demarcation is to be done after the allotment.
- Kintech is handling the land allotment process, which is SB's professional aggregator for land, substation, boundary and transmission line.
- Education Facility: Rewari is having – 1 anganwadi, primary school, Senior secondary school. Schools are almost 2-3 km away from the site. Colleges are there in Jaisalmer and Barmner.
- SC: there are 100 SC families and their caste is Meghwal.
- ST: there are 8-10 families and they are basically Bhil tribes who are mostly engaged as daily labours and agricultures.
- Few STs stay with the mainstream population. There is no as such discrimination between them.
- Health Centre: There is one Sub Centre which is having only ANM and doesn't have any doctor. PHC is in Fathegadh which is 15km away from Rewari. Better hospital facilities are there in Jaisalmer and Barmer.
- There is a small stone cutting firm in Fathegarh with only 4-5 workers.
- Women: 50% women are into household work only and rest into agriculture and labour.
- Literacy rate is low.
- Vegetables such as Bajra and gawar are cultivated. Agriculture is rain fed.
- Fatehgarh is having 0.5 MW solar plant which is 14/ 15 km away from the rewari plant.
- Villagers are mostly involved in agriculture.
- Job preference will be given to locals.
- water in the area is said to be heavy, not good for usage. water is supplied to houses as per govt water supply yojana which is from Indira Gandhi canal. Electricity is also available via govt supply scheme.
- Mostly villagers' own cow, sheep, goat. only 5% owns camel which are Raika caste- Devashi- OBC.

Consultation with Sarpanch

- Jalam Singh- Sarpanch – Phone: 9828484962
- Voters- 2500, SC- 20%, ST- 7%
- Agriculture is based on rainfall; production is very low. Mostly bajra n gawar are grown.
- about the site which is fully on govt land; private land exists in between govt land.
- The land type is govt waste land.
- Rewari is having 1 crematorium and 1 graveyard.
- The locals are aware of the project and the awareness about the same was given through gram sabha in presence of SBE contractors.
- wild animal is very rare.
- DNP is approx. 30 km away from solar site.
- NOC to be provided by collector from DNP & DDP prior to allotment of govt land for any project.
- GIB habitation has been found around 40 km from the solar site.
- GIB arc- institute of Dehradun has made a study about the movement of the GIB. as reported the allotted land doesn't fall under their movement area.

Consultation with Villagers

- Tarachand Paliwal – General caste – Phone: 9983450402
Grocery store owner, as well as into agriculture. He agrees to have a solar plant in the area.
- Hari Singh – OBC – Phone: 9828490647, he is into agriculture.
- Parbat Singh, Phone: 9950138682, he is into agriculture.
- Nar Singh Rao, Phone: 8890641519, he is into agriculture.
- Bhima Ram, Phone: 7877374950, he is into agriculture.
- Satta Ram – ST- Phone: 9571452092, he is into agriculture.
- Chala Ram – SC- Phone: 7665295761, he is into agriculture.

- As observed and reported there is no discrimination with SC & ST people. They get along with the main stream people as observed and reported
- It was reported that 70% women are into agriculture and 30% are household.
- Literacy rate is very low 40-45% girls and boys are going to school.
- Schools are not having benches, electricity, toilets and supply water connection is there in school.
- There is a pond in rewari which also used by the villagers for drinking and other purpose.
- There are approx. 150 houses in the village.

WIND SITE (Consultation with Sarpanch)

- Anup Singh- Sarpanch – Phone: 8118878433
- It is proposed on govt waste land. Villagers are aware of the project and they are happy about it.
- He is looking forward to employment for the villagers and different kind of CSR development in the area.
- SC population 25%, ST population (5-10) %

SC is meghwal, ST is Bheel

ST-100 families for all villages. There is no discrimination. They stay with mainstream people.

- Education Facility: Devka – Middle school

Rajdal – Senior Secondary School

Mattika gol – Primary School

Hadvecha – Senior Secondary

Hadwa – Senior School

Behrupura – Primary School

Manihari – Upper Primary School

Junejuki Dhani – Primary School

For higher studies people goes to Shew College in Barmer district which is 65km from Harwa.

10th, 11th and 12th have benches but others are not having; midday meal kitchen facility is there but in poor condition; senior secondary school is having RO but others are not having RO facility; wash rooms are there but still few more washrooms are required; manihari is having less no.of class rooms; electricity is there.

Harwa panchayat is having senior school, senior secondary, primary and middle school.

- Anganwadi – behrupura – there is anganwadi but dedicated building is not there.

Manihari – 2 anganwadis – one anganwadi is having dedicated building whereas another is not having a dedicated building.

Rest all villages are having one anganwadi each.

- Health Facility: Harwa/ Harvecha/ Devka/ Manihari/ Rajdal is having sub centres with ANM and there is no doctor; Gunga is having PHC which is 7km away from Harwa; for better treatment people travel to hospitals in Barmer.
- Harwa and Harvecha is having supply water facility; in rest of the villages water is provited through tankers; Rs 500 for 4000lts.
- Almost all villages are having 100% toilet facilities.
- Drainage is mostly open.
- All villagers are into agriculture, 80% of the women are into agriculture and few in sewing.
- Vegetables such as Bajra and gawar are cultivated. Agriculture is rain fed.
- Temple: There is one Surya mandir in Devka.
- Behrupura/ Harwa/ Harvecha is having 1 crematorium and 1 graveyard in Harwa

Devka/ Rajdal/ Matti Ka Gol – having crematorium in Rajdal

Juneju Ki Dhani is having 1 graveyard.

Consultation with ST

- Fakira Ram – Phone: 9549612494; bheel caste- Devka Village
- 10 members in family
- He is labour by occupation.
- He is aware of the project.
- There is no discrimination, children are allowed in school, they are allowed in hospital and temples without any discrimination.
- Access are commonly used by all.


Consultation with Women

- Samda Devi – ST – Devka Village
- She is into household work and agricultural work as well
- Girl child goes to school no discrimination is there.

Consultation with Villager

- Rasul Khan – Village – Juneju Ki Dhani – Phone: 9660117593.
- He is aware of the project and happy about it.
- He is into agriculture.
- There are 4 members in the family.
- he is having 75 acres of land which is waste land.

APPENDIX E: POWER PURCHASE AGREEMENT (SAMPLE)

INDIA NON JUDICIAL	
Government of National Capital Territory of Delhi	
e-Stamp	
 सत्यमेव जयते	
Certificate No.	: IN-DL01150281042227R
Certificate Issued Date	: 26-Dec-2019 11:33 AM
Account Reference	: IMPACC (IVY) d1857503/ DELHI/ DL-DLH
Unique Doc. Reference	: SUBIN-DL01150281042227R
Purchased by	: SOLAR ENERGY CORPORATION OF INDIA LIMITED
Description of Document	: Article 5 General Agreement
Property Description	: Not Applicable
Consideration Price (Rs.)	: 0 (Zero)
First Party	: SOLAR ENERGY CORPORATION OF INDIA LIMITED
Second Party	: Not Applicable
Stamp Duty Paid By	: SOLAR ENERGY CORPORATION OF INDIA LIMITED
Stamp Duty Amount(Rs.)	: 300 (Three Hundred only)

.....Please write or type below this line.....

This Power Purchase Agreement is made on the 31st Day of December of 2019 at New Delhi.

Between

SBE Renewables Ten Projects Private Limited, a Company incorporated under the Companies Act 1956 or Companies Act 2013, having its registered office at 1st Floor, Worldmark-2, Asset

HPD-ISTS-T1-SBERTPL-P1-150KA

Page 1 of 67

Statutory Alert:
1. The authenticity of this Stamp Certificate should be verified at "www.shelastamp.com". Any discrepancy in the details on this Certificate and as available on the website renders it invalid.
2. The onus of checking the legitimacy is on the users of the certificate.
3. In case of any discrepancy please inform the Competent Authority.

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

to refund the proceeds to the "Lessee" after recovering the entire sum due to him/it from the Lessee.

(xvi) The "Lessee" shall abide by all the terms and conditions prescribed in the Lease Deed and direction Issued by the State Government and RREC from time to time.

(xvii) The "Lessee" shall adhere to the policy for promoting generation of electricity through Non-Conventional Energy Sources.

(xviii) The "Lessee" shall abide by all the provisions of the Rajasthan Land Revenue (Allotment of Land for setting up of Power Plant based on Renewable Energy Sources) Rules, 2007 and Amended Rules, 2007 Notification No.F-6(28)Rev.5/2014/9 Jaipur dated. 04/08/2014 of the Revenue Department (Group 6), Rajasthan, Jaipur as amended from time to time.

4. The cost and expenses incidental to the preparation and execution and registration of this lease including stamp duty shall be borne and paid by the "Lessee".

In witness whereof the parties hereto have set their respective hands on the dates mentioned against their signatures.

1. Witness	1. Signed for and on behalf of The Governor of Rajasthan (Lessor)
2. Witness	2. For _____ (Lessee). Authorized Signatory

APPENDIX G: SHADOW FLICKER MODELLING

Project:
450 MW Hybrid_at Rajasthan_SB

Licensed user:
ARCADIS INDIA Pvt Ltd
RMZ Titanium, 4th Floor, No 135 Old Airport Road
IN-560001 Bangalore

Calculated:
04-06-2020 21:55/3.3.274

SHADOW - Main Result

Calculation: 450 MW Hybrid_Rjasthan

Assumptions for shadow calculations

Maximum distance for influence
Calculate only when more than 20 % of sun is covered by the blade
Please look in WTG table

Minimum sun height over horizon for influence 3 °
Day step for calculation 1 days
Time step for calculation 1 minutes

Sunshine probability S (Average daily sunshine hours) [JODHPUR]
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
8.71 9.25 8.52 9.17 10.09 8.60 6.53 6.37 8.38 9.44 9.14 8.61

Operational time
N NNE ENE E ESE SSE S SSW WSW W WNW NNW Sum
497 703 609 403 299 256 440 1,938 2,226 800 300 248 8,719


A ZVI (Zones of Visual Influence) calculation is performed before flicker calculation so non visible WTG do not contribute to calculated flicker values. A WTG will be visible if it is visible from any part of the receiver window. The ZVI calculation is based on the following assumptions:
Height contours used: Elevation Grid Data Object: 450 MW Hybrid_at Rajasthan
Obstacles used in calculation
Eye height for map: 1.5 m
Grid resolution: 1.0 m

All coordinates are in
UTM (north)-WGS84 Zone: 42

WTGs

Row data/Description	Easting	Northing	Z [m]	WTG type			Power, rated [kW]	Rotor diameter [m]	Hub height [m]	Shadow data	
				Valid	Manufact.	Type-generator				Calculation distance [m]	RPM
1	714,917	2,908,360	268.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
2	714,080	2,908,756	276.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
3	715,183	2,908,005	267.7	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
4	715,590	2,906,694	272.8	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
5	719,078	2,919,317	285.6	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
6	718,303	2,918,516	295.5	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
7	718,713	2,918,491	291.2	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
8	717,483	2,917,871	316.1	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
9	717,990	2,917,759	309.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
10	718,361	2,917,600	293.6	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
11	718,632	2,917,298	286.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
12	720,135	2,917,217	268.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
13	717,562	2,916,811	306.3	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
14	717,871	2,916,504	293.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
15	716,854	2,916,185	304.9	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
16	717,204	2,915,931	322.9	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
17	716,551	2,915,398	296.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
18	716,771	2,914,847	297.8	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
19	716,990	2,914,594	295.7	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
20	717,340	2,914,403	283.7	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
21	718,470	2,913,813	273.9	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
22	717,113	2,913,662	279.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
23	714,991	2,911,701	285.6	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
24	715,203	2,911,325	280.4	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
25	715,505	2,911,015	284.9	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
26	716,324	2,910,963	267.9	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
27	716,895	2,910,198	269.8	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
28	715,295	2,909,278	268.8	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
29	715,985	2,910,171	283.8	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
30	716,107	2,909,265	278.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
31	716,825	2,907,233	260.9	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
32	716,078	2,913,232	276.3	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
33	716,249	2,912,987	285.1	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
34	716,224	2,912,150	272.7	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
35	716,915	2,911,433	278.0	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0

To be continued on next page...



ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

Project:
450 MW Hybrid_at Rajasthan_SB

Licensed user:
ARCADIS INDIA Pvt Ltd
RMZ Titanium, 4th Floor, No 135 Old Airport Road
IN-560001 Bangalore

Calculated:
04-06-2020 21:55/3.3.274

SHADOW - Main Result

Calculation: 450 MW Hybrid_Rjasthan

...continued from previous page

	Easting	Northing	Z	Row data/Description	WTG type			Power, rated [kW]	Rotor diameter [m]	Hub height [m]	Shadow data	
					Valid	Manufact.	Type-generator				Calculation distance [m]	RPM
36	717,041	2,912,137	273.7	New 4	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
37	717,912	2,918,710	293.5	SBE-67	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
38	715,890	2,906,447	275.5	SBE40	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
39	718,414	2,909,089	268.7	SBE44	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
40	719,145	2,910,278	272.7	SBE-81	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
41	719,619	2,911,831	281.6	SBE47	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
42	719,825	2,912,937	284.3	SBE49	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
43	719,621	2,913,340	287.4	SBE60	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
44	720,236	2,912,644	284.1	SBE61	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
45	719,949	2,914,086	288.9	SBE62	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
46	720,365	2,916,562	270.4	SBE63	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
47	717,344	2,915,191	306.6	New 6	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
48	717,421	2,913,430	276.2	SBE 21	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
49	717,446	2,915,761	311.0	New 2	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
50	717,140	2,916,244	329.0	New 3	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
51	721,480	2,914,167	283.6	SBE65	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
52	719,040	2,908,281	267.0	SBE43	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0
53	719,433	2,912,280	288.1	New 5	No	VESTAS	V 120-2,200/2,200	2,200	120.0	118.0	2,500	0.0

Shadow receptor-Input

No.	Name	Easting	Northing	Z	Width	Height	Elevation a.g.l.	Degrees from south cw	Slope of window	Direction mode	Eye height (ZVI) a.g.l.
		[m]	[m]	[m]	[m]	[m]	[m]	[°]	[°]		[m]
A	SBE 18 (1)	717,475	2,914,208	278.3	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0
B	SBE 39(1)	714,960	2,907,845	263.6	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0
C	SBE05_R1	717,836	2,917,731	308.8	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0
D	SBE65_R1	721,313	2,913,969	282.1	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0
E	SBE65_R2	721,255	2,914,102	285.9	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0
F	SBE65_R3	721,343	2,914,129	285.1	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0
G	SBE_11_R1	717,958	2,916,445	289.3	1.0	1.0	1.0	0.0	90.0	Fixed direction	2.0

Calculation Results

Shadow receptor

No.	Name	Shadow, worst case		Shadow, expected values	
		Shadow hours per year [h/year]	Shadow days per year [days/year]	Max shadow hours per day [h/day]	Shadow hours per year [h/year]
A	SBE 18 (1)	17:18	60	0:27	6:35
B	SBE 39(1)	2:40	23	0:10	1:00
C	SBE05_R1	147:43	217	1:29	57:56
D	SBE65_R1	3:48	25	0:13	2:11
E	SBE65_R2	9:40	57	0:20	4:49
F	SBE65_R3	60:15	125	1:14	24:57
G	SBE_11_R1	47:53	116	0:43	26:43

Total amount of flickering on the shadow receptors caused by each WTG

No.	Name	Worst case [h/year]	Expected [h/year]
1	SBE37	0:00	0:00
2	SBE38	0:00	0:00
3	SBE39	0:00	0:00
4	SBE-68	0:00	0:00
5	?SBE01	0:00	0:00
6	SBE02	0:00	0:00
7	SBE03	0:00	0:00
8	SBE04	0:00	0:00
9	SBE05	72:04	28:47
10	SBE06	44:40	16:23
11	SBE07	30:52	11:34
12	SBE09	0:07	0:02

To be continued on next page...

Project:
450 MW Hybrid_at Rajasthan_SB

Licensed user:
ARCADIS INDIA Pvt Ltd
 RMZ Titanium, 4th Floor, No 135 Old Airport Road
 IN-560001 Bangalore

Calculated:
 04-06-2020 21:55/3.3.274

SHADOW - Main Result

Calculation: 450 MW Hybrid_Rjasthan

...continued from previous page

No.	Name	Worst case [h/year]	Expected [h/year]
13	SBE10	0:00	0:00
14	SBE11	1:21	0:22
15	SBE12	10:14	5:16
16	SBE13	23:00	14:26
17	SBE15	0:00	0:00
18	SBE16	0:00	0:00
19	SBE17	0:00	0:00
20	SBE18	0:00	0:00
21	SBE19	16:17	6:10
22	SBE20	0:00	0:00
23	SBE24	0:00	0:00
24	SBE25	0:00	0:00
25	SBE26	0:00	0:00
26	SBE27	0:00	0:00
27	SBE28	0:00	0:00
28	SBE31	0:00	0:00
29	SBE32	0:00	0:00
30	SBE33	0:00	0:00
31	SBE42	2:40	1:00
32	SBE55	0:00	0:00
33	SBE56	0:00	0:00
34	SBE57	0:00	0:00
35	SBE58	0:00	0:00
36	New 4	0:00	0:00
37	SBE-67	0:00	0:00
38	SBE40	0:00	0:00
39	SBE44	0:00	0:00
40	SBE-81	0:00	0:00
41	SBE47	0:00	0:00
42	SBE49	0:00	0:00
43	SBE60	11:08	6:07
44	SBE61	0:00	0:00
45	SBE62	6:51	2:45
46	SBE63	0:00	0:00
47	New 6	0:00	0:00
48	SBE 21	0:00	0:00
49	New 2	0:00	0:00
50	New 3	17:47	9:02
51	SBE65	50:41	20:17
52	SBE43	0:00	0:00
53	New 5	0:00	0:00

Total times in Receptor wise and WTG wise tables can differ, as a WTG can lead to flicker at 2 or more receptors simultaneously and/or receptors may receive flicker from 2 or more WTGs simultaneously.

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan


Project:
450 MW Hybrid_at Rajasthan_SB

Licensed user:
ARCADIS INDIA Pvt Ltd
RMZ Titanium, 4th Floor, No 135 Old Airport Road
IN-560001 Bangalore

Calculated:
04-06-2020 21:55/3.3.274

SHADOW - Map

Calculation: 450 MW Hybrid_Rjasthan



Map: EMD OpenStreetMap , Print scale 1:200,000, Map center UTM (north)-WGS84 Zone: 42 East: 716,600 North: 2,913,120
 ▲ New WTG 📍 Shadow receptor
 Flicker map level: Elevation Grid Data Object: 450 MW Hybrid_at Rajasthan_SB_EMDGrid_0.wpg (1)

APPENDIX H: NOISE MODELLING

Project:

450 MW Hybrid_at Rajasthan_SB

Licensed user:

ARCADIS INDIA Pvt Ltd
RMZ Titanium, 4th Floor, No 135 Old Airport Road
IN-560001 Bangalore

Calculated:

06-07-2020 19:02/3.3.274

DECIBEL - Main Result

Calculation: 450 MW Hybrid Rajasthan_1

Noise calculation model:

ISO 9613-2 General

Wind speed (in 10 m height):

8.0 m/s

Ground attenuation:

General, Ground factor: 1.0

Meteorological coefficient, CO:

0.0 dB

Type of demand in calculation:

2: WTG plus ambient noise is compared to ambient noise plus margin (FR etc)

Noise values in calculation:

All noise values are mean values (Lwa) (Normal)

Pure tones:

Pure tone penalty is subtracted from demand

User: 5.0 dB(A)

Height above ground level, when no value in NSA object:


0.0 m; Don't allow override of model height with height from NSA object

Uncertainty margin:

0.0 dB; Uncertainty margin in NSA has priority

Deviation from "official" noise demands. Negative is more restrictive, positive is less restrictive.:

0.0 dB(A)



WTGs

Easting	Northing	Z [m]	Row data/Description	WTG type		Power, rated [kW]	Rotor diameter [m]	Hub height [m]	Noise data		Wind speed [m/s]	Status	Lwa_ref [dB(A)]	Pure tones	
				Valid	Manufact.				Type-generator	Creator					Name
1	714917	2908.360	268.0 SBE37	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
2	714080	2908.756	276.0 SBE38	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
3	715183	2908.005	267.7 SBE39	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
4	715590	2906.694	272.8 SBE68	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
5	719078	2919.317	285.6 SBE01	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
6	718303	2918.516	295.5 SBE02	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
7	718713	2918.491	291.2 SBE03	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
8	717483	2917.871	316.1 SBE04	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
9	717990	2917.759	309.0 SBE05	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
10	718361	2917.600	293.6 SBE06	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
11	718632	2917.298	286.0 SBE07	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
12	720135	2917.217	280.0 SBE09	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
13	717562	2916.811	306.3 SBE10	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
14	717871	2916.504	293.0 SBE11	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
15	716854	2916.185	304.9 SBE12	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
16	717204	2915.931	322.9 SBE13	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
17	716551	2915.398	296.0 SBE15	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
18	716771	2914.847	297.8 SBE16	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
19	716990	2914.594	295.7 SBE17	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
20	717340	2914.403	283.7 SBE18	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
21	718470	2913.813	273.9 SBE19	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
22	717113	2913.662	279.0 SBE20	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
23	714991	2911.701	285.0 SBE24	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
24	715203	2911.325	280.4 SBE25	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
25	715505	2911.015	284.9 SBE26	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
26	716324	2910.963	267.9 SBE27	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
27	716895	2910.198	269.8 SBE28	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
28	715295	2909.278	268.8 SBE31	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
29	715985	2910.171	283.8 SBE32	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
30	716107	2909.265	278.0 SBE33	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
31	716825	2907.233	289.0 SBE42	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
32	716078	2913.232	276.3 SBE55	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
33	716249	2912.987	285.1 SBE56	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
34	716224	2912.150	272.7 SBE57	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
35	716915	2911.433	278.0 SBE58	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
36	717041	2912.137	273.7 New 4	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
37	717912	2918.710	293.5 SBE67	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
38	715890	2906.447	275.5 SBE40	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
39	718414	2909.089	268.7 SBE44	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
40	719145	2910.278	272.7 SBE81	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
41	719619	2911.831	281.6 SBE47	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
42	719825	2912.937	284.3 SBE49	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
43	719621	2913.340	287.4 SBE60	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
44	720236	2912.644	284.1 SBE61	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
45	719949	2914.086	288.9 SBE62	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
46	720365	2916.562	270.4 SBE63	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
47	717344	2915.191	306.6 New 6	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
48	717421	2913.430	276.2 SBE 21	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
49	717446	2915.761	311.0 New 2	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
50	717140	2916.244	320.0 New 3	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
51	721480	2914.167	283.6 SBE65	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
52	719040	2908.281	267.0 SBE43	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a
53	719433	2912.380	288.1 New 5	No	VESTAS	V 120-2,200/2,200	2200	120.0	118.0	USER	Runtime input	8.0	Generic data based on turbine power (very uncertain)	105.9	No a

Calculation Results

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan

Project:
450 MW Hybrid_at Rajasthan_SB

Licensed user:
ARCADIS INDIA Pvt Ltd
RMZ Titanium, 4th Floor, No 135 Old Airport Road
IN-560001 Bangalore

Calculated:
06-07-2020 19:02/3.3.274

DECIBEL - Main Result

Calculation: 450 MW Hybrid Rajasthan_1

Sound level

No.	Name	Easting	Northing	Z	Immission height	Ambient noise	Demands Additional exposure	Sound level		Additional exposure	Distance to noise demand	Demands fulfilled ?	
								Ambient+WTGs	From WTGs				
					[m]	[dB(A)]	[dB(A)]	[dB(A)]	[dB(A)]	[dB(A)]	[m]	Noise	
A	SBE 18 (1)	717,475	2,914,208	278.3	0.0	43.8	0.0	45.0	42.3	46.1	2.3	101	No
B	SBE 39(1)	714,960	2,907,845	263.6	0.0	43.8	0.0	45.0	40.7	45.5	1.7	132	No
C	SBE05_R1	717,836	2,917,731	308.8	0.0	43.8	0.0	45.0	45.2	47.6	3.8	-9	No
D	SBE65_R1	721,313	2,913,969	282.1	0.0	43.8	0.0	45.0	40.3	45.4	1.6	144	No
E	SBE65_R2	721,255	2,914,102	285.9	0.0	43.8	0.0	45.0	41.1	45.7	1.9	124	No
F	SBE65_R3	721,343	2,914,129	285.1	0.0	43.8	0.0	45.0	44.6	47.3	3.5	35	No
G	SBE_11_R1	717,958	2,916,445	289.3	0.0	43.8	0.0	45.0	46.6	48.4	4.6	-27	No

Distances (m)

WTG	A	B	C	D	E	F	G
1	6383	517	9815	8507	8552	8636	8638
2	6423	1267	9729	8916	8948	9034	8612
3	6613	274	10081	8553	8605	8686	8884
4	7747	1312	11263	9256	9326	9401	10034
5	5355	12189	2014	5796	5651	5661	3083
6	4387	11182	913	5453	5310	5337	2100
7	4458	11288	1160	5216	5072	5094	2181
8	3663	10339	380	5468	5332	5376	1503
9	3588	10367	157	5040	4902	4942	1314
10	3506	10331	541	4680	4540	4576	1223
11	3300	10141	906	4274	4135	4170	1087
12	4016	10706	2356	3455	3310	3316	2310
13	2604	9336	960	4706	4580	4636	539
14	2330	9135	1227	4275	4150	4207	105
15	2072	8552	1832	4979	4869	4937	1134
16	1744	8392	1908	4553	4445	4514	913
17	1507	7719	2663	4972	4879	4957	1754
18	951	7232	3074	4626	4545	4628	1991
19	620	7048	3249	4368	4293	4378	2089
20	237	6977	3365	3997	3927	4012	2133
21	1071	6924	3969	2847	2800	2890	2681
22	655	6203	4133	4211	4165	4256	2908
23	3529	3856	6667	6717	6708	6800	5595
24	3671	3488	6926	6658	6659	6750	5814
25	3752	3217	7109	6516	6526	6617	5958
26	3443	3403	6935	5825	5845	5934	5720
27	4052	3046	7592	5809	5852	5936	6337
28	5390	1472	8827	7630	7668	7753	7646
29	4303	2542	7783	6543	6575	6661	6577
30	5129	1825	8641	7016	7064	7147	7415
31	7005	1963	10547	8094	8174	8244	9281
32	1704	5502	4830	5287	5250	5341	3723
33	1730	5301	5002	5158	5129	5220	3857
34	2408	4487	5809	5404	5396	5488	4632
35	2831	4086	6365	5077	5095	5184	5119
36	2116	4770	5650	4648	4650	4741	4405
37	4523	11259	982	5835	5693	5723	2265
38	7921	1679	11451	9273	9348	9421	10210
39	5204	3671	8661	5676	5762	5829	7370
40	4270	4841	7567	4281	4368	4434	6280
41	3201	6131	6164	2728	2799	2873	4904
42	2672	7042	5190	1811	1844	1930	3974
43	2315	7206	4740	1805	1803	1894	3522
44	3173	7132	5625	1707	1779	1852	4431
45	2477	7990	4213	1369	1306	1395	3087
46	3727	10257	2786	2761	2616	2622	2410
47	992	7723	2587	4153	4060	4138	1396
48	780	6103	4321	3929	3892	3984	3062
49	1553	8297	2008	4262	4155	4225	854
50	2063	8677	1642	4753	4639	4705	842
51	4005	9082	5097	259	234	142	4194
52	6130	4103	9526	6125	6228	6285	8235
53	2748	6299	5680	2527	2577	2658	4418

ESIA of 450 MW Hybrid Wind-Solar Power Project at Devaka and Rewri villages in Rajasthan


Project:
450 MW Hybrid_at Rajasthan_SB

Licensed user:
ARCADIS INDIA Pvt Ltd
 RMZ Titanium, 4th Floor, No 135 Old Airport Road
 IN-560001 Bangalore

Calculated:
 06-07-2020 19:02/3.3.274

DECIBEL - Map 8.0 m/s

Calculation: 450 MW Hybrid Rajasthan_1



Map: EMD OpenStreetMap , Print scale 1:100,000, Map center UTM (north)-WGS84 Zone: 42 East: 717,780 North: 2,912,882
 New WTG Noise sensitive area
 Noise calculation model: ISO 9613-2 General. Wind speed: 8.0 m/s
 Height above sea level from active line object

APPENDIX I: DO'S AND DON'T'S FOR WILDLIFE

DOs

- The developer should intimate the District Forest Officer about the project activity prior to the starting of the project.
- Awareness programs should be conducted for all contractors and their workers regarding the presence of the species in the region and their conservation status.
- The presence of the Indian Blue Bull, Indian Dessert Fox need to be managed both during the construction and operation phase of the project
- The movement of vehicles through access road (day and nighttime) needs to be monitored constantly for presence of Chinkara herds in and around the road.
- Signage's showing the Indian Blue Bull should be placed within the project site and near to the approach roads for generating awareness amongst the vehicle drivers and labors.
- Signages prohibiting the hunting or killing of the Indian Blue Bull should also be placed in and around the project site.
- The construction area location needs to be temporally barricaded to prevent the grazing animals from entering the area while the work is on.
- If pits are dug on the ground for any project activity it should be suitably barricaded and closed permanently after construction so that the animals are prevented from falling in the pit.
- If the construction site is close to any water pit or water channel then special precautions should be taken to keep the Indian Blue Bull away from the construction site as they may visit the water source for drinking.
- The area around the construction site should not be used for any other purposes other than the work specified both during and operation phase of the project.
- The equipment with associated facilities like generator, cables and transformer should be properly fenced to prevent accidental electrocution of the Nilgai and Chinkara.
- About 50 m around the project site should be kept free of grasses and shrubs to keep the grazing animals away from nearing the project boundary.
- During operation phase the security guards should be periodically trained regarding the management of the Indian Blue Bull.
- Record should be maintained about the presence of the Indian Blue Bull, Indian Dessert Fox in and around the project area in all seasons during operation phase.

Don'ts

- Hunting or killing of wild animals is totally prohibited under Wildlife Protection Act
- No construction activity should start without an awareness program regarding the presence of the Indian Blue Bull and their management.
- The workers should not be allowed to throw stones or wood or any other weapon to ward off the Indian Blue Bull from the site.
- DG sets without acoustic cover should not be used during project construction phase.
- No pits should be left uncovered near the project boundary or within the project site during construction and operation phase of the project.
- Fencing of the area should be properly insulated so that electrocution can be avoided.
- No electric cables should be loosely hanged or left above the ground during operation phase of the project.
- Construction activity should preferably continue during daytime and should not be allowed during night time.

Arcadis India Private Limited

3rd Floor, Tower B,
Logix techno Park,
Plot No.5, Sector 127 Noida
T: (0120) 4368 400

[Arcadis.com](https://www.arcadis.com)

