



Preparatory Survey on Patna Metro Rail Project

Draft Final Report

October 2022

Japan International Cooperation Agency

Oriental Consultants Global Co., Ltd.

Nippon Koei Co., Ltd.

Padeco Co., Ltd.

**Japan International Consultants for
Transportation Co. Ltd**

Contents

	page
1. Background and Objectives	1-1
1.1 Metro Construction Project in Tier-2 Cities	1-1
1.2 Significance of Metro Construction Project in Bihar State	1-1
1.3 Goals to be Archived by Patna Metro Rail Project	1-1
1.4 Overview of this Survey.....	1-2
1.5 Government Approval.....	1-1
1.5.1 Detailed Project Report (DPR).....	1-1
1.5.2 Approval of Patna Metro Rail Project by GoI.....	1-1
2. Overview of Patna City and Bihar State	2-1
2.1 Natural Features.....	2-1
2.1.1 Geography.....	2-1
2.1.2 Geological Structure.....	2-1
2.1.3 Climate.....	2-2
2.2 Social Environment.....	2-3
2.2.1 Population	2-3
2.2.2 Economy	2-3
2.2.3 Industry	2-4
2.2.4 Traffic	2-5
2.2.5 Politics	2-5
2.2.6 Culture	2-6
2.2.7 Air pollution.....	2-6
3. Review of Urban Development Policy	3-1
3.1 Urban Development Plan	3-1
3.1.1 Patna Urban Development Characteristics and Traffic Growth	3-1
3.1.2 Current Transportation Development in Patna.....	3-5
3.1.3 Other Infrastructure Projects and Projects Supported by Other Donors	3-9
3.2 Review of Public Transport Development Plan in Bihar	3-10
3.2.1 Patna Master Plan (PMP) 2031	3-10
3.2.2 Comprehensive Mobility Plan Patna (CMP2018).....	3-12
3.2.3 Relevant Policy the Metro Project.....	3-13
3.3 Needs of Metro Development in Tier-2 Cities.....	3-1
3.3.1 Needs of Metro Development in Tier-2 Cities in India	3-1
3.3.2 Needs of Metro Development in Patna.....	3-1
3.3.3 Priority of Metro Development among Tier-2 Cities.....	3-1
4. Travel Characteristics and Demand Estimates.....	4-1
4.1 Overview of Existing Studies	4-1
4.1.1 Methodology and Data Collection.....	4-1
4.1.2 Results of CMP2018.....	4-4

4.2	Reviews of Existing Studies	4-5
4.2.1	Review of DPR Demand Forecast.....	4-5
4.2.2	Demand Forecast for Patna Metro by DPR.....	4-5
4.2.3	Revision of Demand Forecast by JST.....	4-7
4.2.4	Estimation of Traffic Impact during Metro Construction Period	4-10
5.	Civil Engineering and Alignment.....	5-1
5.1.1	Route Plan.....	5-1
5.1.2	Overview of Existing Studies.....	5-4
5.1.3	Reviews of Existing Studies and Proposals for Improvement	5-16
5.2	Track Structure	5-29
5.2.1	Overview of Existing Studies.....	5-29
5.2.2	Reviews of Existing Studies and Proposals for Improvement	5-31
5.3	Engineering Survey.....	5-33
5.3.1	Overview of Existing Survey	5-33
5.3.2	Reviews of Existing Surveys and comments	5-36
5.4	Civil Engineering.....	5-49
5.4.1	Overview of Civil structure plan and design concept.....	5-49
5.4.2	Reviews of Existing Studies and Proposals for Improvement	5-70
6.	Station Planning.....	6-1
6.1	Overview of Existing Studies	6-1
6.1.1	Outline of Station Planning.....	6-1
6.1.2	Outline of Station Design Criteria	6-3
6.2	Reviews of Existing Studies and Proposals for Improvement.....	6-3
6.2.1	Location of Stations.....	6-3
6.2.2	Facility of Stations.....	6-4
6.2.3	Guideline for Evaluation of Emergency Evacuation	6-9
6.2.4	Interchange Stations	6-9
6.2.5	Disaster control	6-11
7.	Inter-Modal Integration.....	7-1
7.1	Overview of Existing Studies	7-1
7.2	Reviews of Existing Studies and Proposals for Improvement.....	7-2
8.	Train Operation Plan.....	8-1
8.1	Overview of Existing Studies	8-1
8.1.1	Operation Philosophy	8-1
8.1.2	Concept of Train Operation Plan.....	8-1
8.1.3	Train Formation.....	8-1
8.1.4	Future Prediction of Operation Plan	8-2
8.2	Reviews of Existing Studies and Proposals for Improvement.....	8-2
8.2.1	PHPDT by Demand projection.....	8-2
8.2.2	Influence of Car Width Reduction.....	8-4

8.2.3	In/Out Depot Trains on Corridor 2	8-5
8.2.4	Concerns for “3 and 6 Cars” Mixed Operation	8-6
8.2.5	Quantity of Rolling Stock	8-7
8.2.6	Rescue Operation on Maximum Gradient.....	8-7
8.2.7	Hourly Train Operation Plan.....	8-8
8.2.8	Operation Distance of Trains and Cars	8-9
9.	Signaling and Telecommunication	9-1
9.1	Overview of Existing Studies	9-1
9.1.1	Signaling Facilities	9-1
9.1.2	Telecommunication Facilities	9-4
9.2	Reviews of Existing Studies and Proposals for Improvement.....	9-6
9.2.1	Signaling Facilities	9-6
9.2.2	Telecommunication Facilities	9-13
10.	Fare Collection System.....	10-1
10.1	Overview of Existing Studies	10-1
10.1.1	AFC System Facilities	10-1
10.1.2	Others.....	10-1
10.2	Reviews of Existing Studies and Proposals for Improvement.....	10-2
10.2.1	Conformity Review with International Standards/Regional Standards and Appropriateness Review of Facility Plan.....	10-2
10.2.2	Appropriateness Review of Facility Plan suitable for the transportation capability based on traffic demand forecasts	10-6
10.2.3	Procurement Feasibility Review from India and other countries (including Japan), Procurement Feasibility Review over the medium-to-long term	10-6
10.2.4	Appropriateness Review of Facility Flexibility and Stability	10-6
10.2.5	Proposals for Improvement.....	10-6
11.	Rolling Stock.....	11-1
11.1	Overview of Existing Studies	11-1
11.1.1	Route and Rolling Stock Plan	11-1
11.1.2	Technical Details	11-1
11.1.3	Salient Features	11-3
11.1.4	Others.....	11-4
11.2	Reviews of Existing Studies and Proposals for Improvement.....	11-4
11.2.1	Corridor and Rolling Stock Plan	11-4
11.2.2	Technical Features	11-4
11.2.3	Main Characteristic	11-5
11.2.4	Cooling for CI and APS	11-5
11.2.5	Preparation for Conversion of Train Configuration.....	11-5
12.	Power Supply and Traction.....	12-1
12.1	Overview of Existing Studies	12-1

12.1.1 Power Supply Facilities	12-1
12.1.2 Mechanical Facilities.....	12-10
12.2 Reviews of Existing Studies and Proposals for Improvement.....	12-14
12.2.1 Power Supply Facilities	12-14
12.2.2 Mechanical Facilities.....	12-21
13. Depot	13-1
13.1 Track Layout.....	13-1
13.2 Issues identified by alignment review.....	13-1
13.3 Depot Planning	13-5
13.4 Workshop Facilities.....	13-6
14. Environmental Impact Assessment (EIA)	14-1
14.1 Condition of Natural Environment	14-1
14.1.1 Land use.....	14-1
14.1.2 Geology and Topography.....	14-5
14.1.3 Climate.....	14-6
14.1.4 Natural Disasters	14-7
14.2 Legal System Regarding Environmental Considerations in India	14-9
14.2.1 Laws and Regulations Regarding Environmental Considerations in India.....	14-9
14.3 Comparative study of alternatives (Including No project)	14-14
14.3.1 Corridor 1.....	14-15
14.3.2 Corridor 2.....	14-21
14.3.3 Depot	14-28
14.3.4 Issues from a train operation perspective.....	14-33
14.4 Screening and Draft Scoping pertaining to Environmental and Social Considerations	14-33
14.4.1 Screening	14-34
14.4.2 Scoping	14-34
14.4.3 Method of Environmental baseline Survey and Analysis	14-38
14.5 The result of the EIA survey.....	14-42
14.5.1 Air Pollution.....	14-42
14.5.2 Water Pollution.....	14-45
14.5.3 Waste	14-51
14.5.4 Soil contamination.....	14-52
14.5.5 Noise and Vibration	14-54
14.5.6 Ground Subsidence.....	14-65
14.5.7 Offensive odor.....	14-65
14.5.8 Protected Area	14-66
14.5.9 Ecosystem	14-69
14.5.10 Hydrology	14-78
14.5.11 Geology and Topography.....	14-79
14.5.12 Land Acquisition/ Resettlement	14-79
14.5.13 Poverty.....	14-79

14.5.14 Indigenous and ethnic people.....	14-79
14.5.15 Local economy such as employment and livelihood, etc.....	14-79
14.5.16 Land use, utilization of local resources and ecosystem services.....	14-80
14.5.17 Water usage and its rights	14-80
14.5.18 Existing social infrastructures and services	14-81
14.5.19 Maldistribution of benefit and damage.....	14-81
14.5.20 Local conflict of interest	14-81
14.5.21 Cultural Heritage	14-82
14.5.22 Landscape	14-82
14.5.23 Gender	14-83
14.5.24 Children's right.....	14-83
14.5.25 Health (Infectious diseases such as HIV/AIDS, etc.)	14-83
14.5.26 Labor environment including labor safety	14-83
14.5.27 Accidents	14-84
14.5.28 Cross-border impact and Climate change	14-84
14.6 Impact Assessment.....	14-84
14.7 Environmental Management Plan.....	14-91
14.7.1 Retroactive verification of EMP for the section under construction	14-91
14.7.2 Environmental Management Plan for the section to be constructed.....	14-95
14.8 Environmental Monitoring Plan	14-104
14.8.1 Retroactive verification of EMoP for the section under construction.....	14-104
14.8.2 Environmental Monitoring Plan for the section to be constructed	14-106
14.9 Project Implementation System.....	14-119
14.9.1 Mitigation Measures and Monitoring Plan	14-119
14.9.2 Grievance Redress Mechanism	14-119
15. Social Impact Assessment (SIA)	15-1
15.1 Baselines of Social Environment.....	15-1
15.1.1 GDP and Industry	15-1
15.1.2 Population, Language, Castes, Indigenous Peoples and Ethnic Minorities	15-2
15.1.3 Literacy and Education	15-4
15.1.4 Number of Earning Members per Household	15-5
15.1.5 Activity Status/ Occupation	15-5
15.1.6 Female Labour Force Participation	15-6
15.1.7 Income Distribution.....	15-6
15.1.8 Poverty Line and Multidimensional Poverty Index (MPI)	15-7
15.1.9 Sanitation and Health.....	15-10
15.1.10 Vehicles Owned per Household	15-11
15.1.11 Household Monthly Expenditure on Transport.....	15-11
15.1.12 Trip Purpose	15-12
15.1.13 Traffic and Transportation in Patna	15-12
15.2 Necessity of Land Acquisition and Resettlement	15-15

15.3 Legal Framework for Land Acquisition and Resettlement.....	15-15
15.3.1 Land Acquisition Act (2013).....	15-16
15.3.2 Bihar Rules (2014)	15-18
15.3.3 Metro Railways (Operation and Maintenance) Act, 2002	15-19
15.3.4 JICA Guidelines	15-19
15.3.5 World Bank OP 4.12.....	15-20
15.3.6 Gap with JICA Guidelines Regarding Land Acquisition and Relocation of Residents and Countermeasures.....	15-20
15.4 Summary of Land Acquisition, Resettlement and Relocation.....	15-25
15.5 Scale and Extent of Land Acquisition.....	15-29
15.5.1 Update of Scale and Extent of Land Acquisition	15-29
15.5.2 Profile of Project affected Landowners	15-31
15.6 Scale and Extent of Resettlement	15-39
15.6.1 Update of Scale and Extent of Resettlement.....	15-39
15.6.2 Profile of Project affected Households	15-45
15.7 Eligibility and Entitlements for Compensation, Rehabilitation, and Resettlement.....	15-52
15.7.1 Eligible PAHs/PAPs.....	15-52
15.7.2 Cut-Off Dates	15-52
15.7.3 Entitlement Matrix.....	15-53
15.8 Institutional Arrangement.....	15-56
15.8.1 PMRCL/ DMRCL	15-57
15.8.2 Department of Revenue and Land Reforms.....	15-57
15.8.3 Office of the District Land Acquisition Collector	15-58
15.8.4 Social Management Unit (SMU).....	15-58
15.8.5 Grievance Redressal Committee	15-59
15.9 Implementation Schedule.....	15-60
15.9.1 Project Preparatory Stage (Pre- Implementation Stage)	15-60
15.9.2 Land Acquisition Implementation Stage.....	15-61
15.9.3 Monitoring and evaluation phase	15-61
15.9.4 RAP Implementation Schedule	15-61
15.10 Cost and Budget.....	15-63
15.10.1 Cost Estimate and Budget.....	15-63
15.11 Monitoring and Evaluation.....	15-64
15.11.1 Internal Monitoring	15-64
15.11.2 Independent Evaluation	15-66
15.11.3 Reporting Requirements	15-66
15.12 Consideration on Impacts on Existing Transportation Industry	15-67
15.12.1 Observation of Existing Urban Transportation in Patna	15-67
15.12.2 Case Study	15-68
15.12.3 Interview Survey	15-70
15.12.4 Proposals for Development of Urban Transportation Network.....	15-72
15.13 Survey on Necessity of Indigenous Peoples Plan	15-72

15.14 Consideration on Gender.....	15-73
15.14.1 Analysis	15-73
15.14.2 Proposals for Gender-Responsive Activities.....	15-76
15.14.3 Gender Indicators for Monitoring of Gender Integration	15-77
15.15 Differently Abled Persons	15-78
15.15.1 Policies, Laws, and Programs Related to Differently Abled Persons	15-78
15.15.2 Already Incorporated Measures	15-79
15.15.3 Newly Proposed Measures.....	15-81
16. Public Consultation.....	16-1
16.1 1 st Public Consultation	16-1
16.1.1 Overview of PCs implemented by PMRCL.....	16-1
16.1.1 Implementation method and approach of PC held by PMRCL, and summary of results	16-1
16.2 2 nd Public Consultation.....	16-4
16.2.1 EIA	16-4
16.2.2 SIA.....	16-7
17. Detailed Project Cost Estimates (N/A)	17-1
18. Transit Oriented Development (TOD) Plan	18-1
18.1 Overview of Existing Studies	18-1
18.2 Reviews of Existing Studies and Proposals for Improvement.....	18-3
18.3 TOD in Japan.....	18-6
18.4 Recommendation from JST	18-7
19. Digital Transformation (DX).....	19-1
19.1 Overview of Existing Studies	19-1
19.1.1 AFC System	19-1
19.1.2 Building Information Modelling (BIM).....	19-2
19.2 Reviews of Existing Studies and Proposals for Improvement.....	19-3
19.2.1 Smart card in India	19-3
19.2.2 DX, MaaS in India.....	19-4
19.2.3 Japanese start-up in India.....	19-6
19.2.4 Cases in Japan	19-7
19.3 Recommendation from JST	19-10
20. Non Fare Box Revenue.....	20-1
20.1 Overview of Existing Studies	20-1
20.2 Reviews of Existing Studies and Proposals for Improvement.....	20-3
20.3 Cases in Japan.....	20-7
20.4 Recommendation from JST	20-9
21. Financial Analysis.....	21-1
21.1 Overview of Existing Studies (N/A)	21-1
21.2 Applied Preconditions and Methodology for this Study (N/A)	21-1

21.3 Financial Structure of Borrowers.....	21-1
21.3.1 Financial Capacity Analysis of the Central and State Governments	21-1
21.3.2 Financial Structure of PMRCL.....	21-8
21.4 Project Evaluation Indicators.....	21-13
21.4.1 Quantitative Evaluation Indicators (N/A).....	21-13
21.4.2 Qualitative Evaluation Indicators	21-13
21.4.3 Internal Rate of Return (IRR).....	21-14
22. Economic Analysis	22-1
22.1 Overview of Existing Studies (N/A)	22-1
22.2 Reviews of Existing Studies and Proposals for Improvement (N/A).....	22-1
22.3 Quality of Life (QOL) Indicators.....	22-1
22.4 Clean Development Mechanism (CDM).....	22-2
22.4.1 What is CDM?.....	22-2
22.4.2 Activities in Delhi Metro	22-2
22.4.3 Applicability in Patna Metro	22-3
22.5 Environmental Social Governance (ESG) Investment.....	22-4
22.5.1 Trends and Applicability in India	22-4
22.5.2 Information Disclosure on ESG Investments.....	22-5
23. Implementation Plan.....	23-6
23.1 Tender Packages (N/A)	23-6
23.2 Procurement Plan for Materials, Machines, and Equipment (N/A)	23-6
23.3 Project Implementation Schedule (N/A)	23-6
23.4 Responsibility of Project Executing Agency	23-6
23.4.1 Construction Safety Management	23-6
23.4.2 Land Acquisition	23-6
23.4.3 Transferring PAP	23-7
23.4.4 Relocating Obstacles	23-7
23.4.5 Obtaining Permissions	23-8
23.4.6 Empowerment for Women and the Needy	23-8
23.5 Measure against COVID-19	23-8
23.6 Organization during Construction.....	23-9
23.6.1 PMRCL organization structure.....	23-9
23.6.2 Technical support.....	23-12
23.6.3 The necessity of technical support during construction.....	23-12
23.7 Proposed Terms of Reference for Consultant (N/A)	23-12
24. Operation and Maintenance (O&M)	24-13
24.1 Overview of Existing Studies	24-13
24.1.1 Organization Structure.....	24-13
24.1.2 Contents of O&M Service.....	24-13
24.2 Reviews of Existing Studies and Proposals for Improvement.....	24-13
24.2.1 Training.....	24-13

24.2.2 O&M Structure.....	24-18
25. Utilization of Japanese Technologies.....	25-31
25.1 Proposal.....	25-31
25.1.1 Track	25-31
25.1.2 Signaling and Telecommunication	25-31
25.1.3 AFC	25-32
25.1.4 Electrical and Mechanical System/Facilities.....	25-32
25.1.5 Rolling Stocks	25-32
25.1.6 Tunnel Boring Machine (TBM)	25-33

List of Figures

	page
Figure 1-1: Current Status of Patna City.....	1-1
Figure 1-2: Alignment Map of Patna Metro Corridor 1 and 2.....	1-3
Figure 2-1: Geography of Patna	2-1
Figure 2-2: Seismic Hazard Map - Bihar	2-2
Figure 2-3: Major Business Districts in Patna.....	2-4
Figure 3-1: Illustration of Transport Network and Phased Urbanization in Patna.....	3-2
Figure 3-2: Marine Drive and Patna Ring Road.....	3-4
Figure 3-3: Regional Connectivity of Patna.....	3-6
Figure 3-4: Existing Bus Routes in Patna	3-8
Figure 3-5: Modal Share in Patna.....	3-9
Figure 3-6: Metro Map on Patna Master Plan 2031	3-11
Figure 3-7: Proposed Land Use Plan	3-12
Figure 3-8: Income Level of India Cities (2015) and Metro Development	3-4
Figure 4-1: Traffic Analysis Zones	4-1
Figure 4-2: Methodology for Traffic Demand Projection	4-3
Figure 4-3: Modelling of Road Closure for Malahi Pakri Station	4-12
Figure 5-1: Corridor 1: Danapur – Khemni Chak.....	5-2
Figure 5-2: Corridor 2: Patna Station – New ISBT	5-3
Figure 5-3: Route Plan for Future Extension	5-3
Figure 5-4: Corridor 1 and Corridor 2 Alignment	5-4
Figure 5-5: Location map between DANAPUR and PATLIPUTRA.....	5-5
Figure 5-6: Location map between PATLIPUTRA – RUKANPURA	5-6
Figure 5-7: Location map of gas stations near RUKANPURA station.....	5-6
Figure 5-8: Gas station situation near RUKANPURA Station.....	5-7
Figure 5-9: Location map between RUKANPURA – ZOO STATION	5-8
Figure 5-10: Location map between ZOO STATION - PATNA JUNCTION	5-8
Figure 5-11: Location map between PATNA JUNCTION – MITHAPUR	5-9
Figure 5-12: Location map between MITHAPUR - KHEMNI CHAK.....	5-10
Figure 5-13: Location map between PATNA JUNCTION - RAJENDRA NAGAR	5-11
Figure 5-14: Location map between RAJENDRA NAGAR - MALAHI PAKRI	5-12
Figure 5-15: Location map between MALAHI PAKRI – NEW ISBT	5-13
Figure 5-16: Concept of Degree of Curve.....	5-22
Figure 5-17: Location map of proposed improvements	5-24
Figure 5-18: Reverse curve layout between CLC-20 and CLC-21.....	5-26
Figure 5-19: Reverse curve layout between CLC-27 and CLC-28.....	5-27
Figure 5-20: Result of adjusting for conflicts between transition curves and vertical curves	5-27
Figure 5-21: DANAPUR Station Additional Crossover Layout	5-28
Figure 5-22: KHEMNI CHAK Station Additional Crossover Layout	5-28
Figure 5-23: NEW ISBT Station Additional Crossover Layout	5-29

Figure 5-24: NEW ISBT Station Additional Crossover Layout	5-29
Figure 5-25: Cross Section of Plinth Track	5-30
Figure 5-26: Cross-section of Mass-Spring System for Plinth track	5-31
Figure 5-27 : Boring Locations	5-33
Figure 5-28: Boring Locations of the Corridor 1 + 2.....	5-33
Figure 5-29: CAD Data of Underground Utility	5-35
Figure 5-30: High Voltage Power Line (Corridor2 ST12 NEW ISBT STATION)	5-35
Figure 5-31 : Crossing Location between Corridor 2 Elevated Alignment and High Voltage Power Line nearby Corridor2 ST11 Zero Mile	5-35
Figure 5-32: Power Distribution Board (Corridor2 ST04 PMCH STATION)	5-36
Figure 5-33 : Existing Survey Report	5-36
Figure 5-34: Construction Condition of Guide Wall for Diaphragm Wall Construction at Corridor2 ST05 Moin Ul Haq.....	5-39
Figure 5-35: D-Wall Excavation Construction at Corridor2 ST05 Moin Ul Haq.....	5-40
Figure 5-36: Test Digging of Underground Utility at Corridor 2 ST04 PMCH Station	5-40
Figure 5-37: Existing Building along Underground TBM Section nearby Cooridor1 ST06 Raja Bazar	5-41
Figure 5-38: Patna Bridge	5-41
Figure 5-39 : As-build Drawing of Patna Bridge.....	5-42
Figure 5-40: Patliputra Bridge.....	5-43
Figure 5-41 : As-build Drawing of Patliputra Bridge	5-44
Figure 5-42: Feet Road Bridge	5-44
Figure 5-43 : As-build Drawing of Feet Road Bridge	5-45
Figure 5-44: Reinforcement retaining wall embankment of Maharana Pratap Flyover.....	5-46
Figure 5-45: : As- built drawing of reinforcement retaining wall.....	5-47
Figure 5-46: Schematic Diagram of Patna Metro (as of 15 th September 2022).....	5-50
Figure 5-47: Civil Design Specification for Patna Metro Project.....	5-53
Figure 5-48: Typical Structure Type of Viaduct and Pier (1)	5-54
Figure 5-49: Typical Structure Type of Viaduct and Pier (2)	5-54
Figure 5-50: Structure Type of Viaduct and Pier (3).....	5-55
Figure 5-51: Structure Type of Viaduct and Pier (4).....	5-55
Figure 5-52: Structure Type of Viaduct (Truss Bridge) and Pier.....	5-56
Figure 5-53: Corrido2 ST09 Khemni Chak.....	5-56
Figure 5-54: Corridor 2 ST11 Zero Mile	5-56
Figure 5-55: General Arrangement Walkway in Tunnel	5-57
Figure 5-56 : Bored Tunnel General Arrangement of Precast Concrete Lining Regular Section.....	5-58
Figure 5-57 : Cut & Cover Box and Under Ground Ramp	5-59
Figure 5-58: Corridor1 ST05 Rukanpura.....	5-61
Figure 5-59: Corridor1 ST06 Raja Bazar.....	5-63
Figure 5-60: Corridor1 ST07 Patna Zoo	5-65
Figure 5-61 : Corridor1 ST08 Vikas Bhawan.....	5-66
Figure 5-62 : Corridor1 ST09 Vidyut Bhawan	5-67

Figure 5-63: Corridor1 ST10 Patna Junction	5-69
Figure 5-64: Construction Condition of Elevated Section of Corridor2 (2022/5/15)	5-70
Figure 5-65: Monitoring Plan at Partriputra Crossing	5-73
Figure 5-66: Monitoring Plan at Patna Junction Crossing	5-74
Figure 5-67 Monitoring Plan at Rajendra Nagar Crossing.....	5-75
Figure 5-68: Influence Zone by TBM Driving.....	5-75
Figure 5-69: Example of FEM Analysis	5-75
Figure 5-70: Proposed Monitoring Zone at Patna Junction.....	5-76
Figure 5-71 Proposed Monitoring Zone at Rajendra Nagar Crossing	5-76
Figure 5-72: General Assembly Drawing of EPB TBM	5-76
Figure 5-73: The Construction Method of TBM Launching and Retrieval.....	5-77
Figure 5-74 : General Arrangement of Cross Passage without Sump.....	5-80
Figure 5-75 : General Arrangement of Cross Passage with Sump.....	5-80
Figure 5-76 : Examples of Flood Countermeasures in Japan	5-86
Figure 5-77 : Examples of Flood Panel in Japan.....	5-86
Figure 5-78 : Countermeasures for Flooding at Station Entrances	5-87
Figure 5-79: Erection of Superstructure Using a Mobile Crane	5-89
Figure 5-80: Casting Yard for PC-01 Contractor along NH30	5-90
Figure 5-81: U/G Utility Lines at Patna Junction Station	5-91
Figure 5-82: U/G Utility Lines at Vidyut Bhawan Station.....	5-92
Figure 5-83: Railway Lines at Patna Railway Station	5-93
Figure 5-84: Live Railway Lines Crossing at Patna Railway Station.....	5-94
Figure 5-85: Barricade Installation on NH30.....	5-95
Figure 5-86: Elevated Road above Station Footprint at Patna Junction	5-96
Figure 5-87: Plan Drawings of Retrieval Shaft next to Patna Junction	5-97
Figure 5-88: : Section Drawings of Retrieval Shaft next to Patna Junction.....	5-97
Figure 6-1 : PRS MOR Elevated station site plan	6-4
Figure 6-2 : Stack Platform type underground station section	6-5
Figure 6-3: Products of Post-installation PSD.....	6-6
Figure 6-4: Guide block installation example of Delhi Metro	6-8
Figure 6-5: Examples accommodation of Gender and Infant considerations.....	6-8
Figure 6-6: Station exterior design perspective	6-9
Figure 6-7: Section Drawing: Patna Junction Interchange Station.....	6-10
Figure 6-8: Site Plan Drawing: Khemni Chek Interchange Station.....	6-10
Figure 7-1: Patna Junction Railway Station Front.....	7-2
Figure 8-1: Corridor 1 Passenger Demand in 2024 (Lines of Capacity are based on DPR values)	8-5
Figure 8-2: Corridor 1 Passenger Demand in 2024 (Lines of Capacity are based on DPR values)	8-5
Figure 8-3: Existing Plan and Recommendation for Alignment of ChemniChak	8-6
Figure 9-1: Example of Overall signaling Facilities Configuration	9-11
Figure 10-1: International/Regional Standard for NCMC	10-3
Figure 10-2: Fare Media Brands and Features	10-4

Figure 10-3: The letter issued by MoHUA Urban Transport Division to strongly request to adapt to NCMC (Dated:09.05.2022)	10-5
Figure 12-1: The Structure Diagram of Power Receiving Equipment.....	12-2
Figure 12-2: Station Ventilation and Air Conditioning System Scheme.....	12-12
Figure 12-3: Systematic Diagram modeled on Mithapur RSS	12-16
Figure 13-1: Current Layout Plan of New ISBT Depot	13-1
Figure 13-2: Location map of main facilities at New ISBT depot.....	13-2
Figure 13-3: Current route plan between depot and test track	13-3
Figure 13-4: Proposal for improvement of train route between main workshop and test track	13-4
Figure 13-5: Additional storage track near DANAPUR station, Version 1	13-4
Figure 13-6: Additional storage track near DANAPUR station, Version 2	13-5
Figure 14-1: Land Use Condition along Patna Metro.....	14-1
Figure 14-2: Land Use Condition along Patna Metro.....	14-5
Figure 14-3: Köppen Climate Classification for India.....	14-6
Figure 14-4: Weather Condition in Patna.....	14-6
Figure 14-5: Flood Damage Area in August 2016.....	14-7
Figure 14-6: Epicenter of Earthquakes with over M 5.0 in and around India	14-8
Figure 14-7: Route Overview of Corridor 1.....	14-15
Figure 14-8: Route Overview of Alternative 2	14-16
Figure 14-9: Route Overview of Alternative 3	14-16
Figure 14-10: Existing Bus Route	14-20
Figure 14-11: Comparative Figure for the Southern Section of Corridor 1	14-21
Figure 14-12: Overview of Corridor 2 route	14-22
Figure 14-13: Outline of Route for Alternative 2	14-23
Figure 14-14: Outline of Route for Alternative 3	14-23
Figure 14-15: Comparison of Corridor 2	14-28
Figure 14-16: Alternative 2 Aitwarpur Depot Plan.....	14-30
Figure 14-17: Alternative 2 New ISBT Depot Plan.....	14-30
Figure 14-18: Alternative 3 New ISBT Depot Plan.....	14-31
Figure 14-19: Schematic Diagram of the Location of the Khemni Chak Station Connecting Depot...14-33	
Figure 14-20 EIA Survey points and Areas in rainy season.....	14-41
Figure 14-21 Survey Points conducted in dry season	14-42
Figure 14-22 Acceptable Site for Construction Generated Soil and C &D Waste.....	14-51
Figure 14-23: Details of sensitive receptors along Patna metro	14-56
Figure 14-24: Typical Construction Yard Arrangement of PC spun Pile	14-57
Figure 14-25: Prediction procedure for Railway Noise of elevated section.....	14-60
Figure 14-26: Explanation of Noise source, Noise receiving point and Pass difference	14-60
Figure 14-27: Typical elevated cross section	14-62
Figure 14-28: LAeq from Metro passage at the viaduct section with 2 lanes on each side	14-63
Figure 14-29: LAeq from Metro passage at the viaduct section with 3 lanes on each side	14-63
Figure 14-30 Positional Relation between Patna Metro and SGB Park (Patna Zoo).....	14-67
Figure 14-31 Satellite image at Danapur Cantonment area from 2002 to 2022	14-69

Figure 14-32 Photograph of Floral Species.....	14-71
Figure 14-33 Photograph of avifaunal Species.....	14-74
Figure 14-34 Positional Relation between Patna Metro and KBA	14-77
Figure 14-35 Danapur Cantonment KBA on Bally Rd.	14-77
Figure 14-36 Existing land use map	14-80
Figure 14-37 Location Map of Heritage Structure in Patna	14-82
Figure 14-38 Proposed sectional view and current situation.....	14-83
Figure 14-39: Draft Implementation System at Each Phase	14-119
Figure 14-40: Draft Grievance Redress Mechanism at Each Phase	14-120
Figure 15-1: MPI in Bihar and Patna.....	15-9
Figure 15-2: Metro Stations at Major Transport Nodes	15-14
Figure 15-3: Institutional Arrangement of Implementation of Land Acquisition and Livelihood Rehabilitation.....	15-57
Figure 15-4: Stages of Grievance Redressal	15-60
Figure 15-5: Patna Junction Railway Station Front.....	15-67
Figure 15-6: Mumbai Bandra (W) Station Front.....	15-68
Figure 15-7: Last Mile Connectivity Strategy Web Page by Delhi Metro	15-69
Figure 15-8: Delhi Metro Station with Feeder Buses	15-70
Figure 15-9: Interview of Autorickshaw Drivers.....	15-71
Figure 15-10: Organization Structure of PMRCL	15-74
Figure 15-11: Gender Integration Efforts by Other Metro/Rail Projects in India.....	15-76
Figure 15-12 Sample Photos of Barrier-Free Design for Station Facility.....	15-81
Figure 18-1: Survey of TOD around Stations (Corridor 1).....	18-2
Figure 18-2: Survey of TOD around Stations (Corridor 2)	18-3
Figure 18-3: Methods of Land Value Capture (LVC) applied to metro projects	18-4
Figure 18-4: Categorization of TOD in National TOD Policy	18-6
Figure 18-5: Kenkyu-gakuen Sta. of TX, before (2002) and after (2014)	18-7
Figure 19-1: Letter issued by the Ministry of Housing and Urban Affairs (MoHUA)	19-1
Figure 19-2: BIM Model for PMRCL's Basic Design	19-2
Figure 19-3: Installation of EV charging station at Delhi Metro station.....	19-6
Figure 19-4: Installing EV charging facilities at Delhi Metro stations E-Rickshaw and Japanese startup in Patna.....	19-6
Figure 19-5: Functions of SUICA	19-7
Figure 19-6: Ground and vehicle facilities monitoring by commercial trains.....	19-8
Figure 19-7: Example of Digital Twin.....	19-8
Figure 19-8: On-demand bus.....	19-9
Figure 19-9: Real time congestion information (JR East App)	19-9
Figure 19-10: Digital Signage	19-9
Figure 20-1: Planned acquisition land adjacent to ISBT Depot	20-3
Figure 20-2: Planned property development site and plan at Rukanpura Sta.....	20-5
Figure 20-3: Examples of various non-fare box business of metro and railway companies in India	20-7
Figure 20-4: Transitions in JR East's Non-Railway Business Strategies	20-8

Figure 20-5: Utilization of the space under viaduct (JR East).....	20-8
Figure 20-6: Rental business of house and garage integrated residence using the space of viaduct (Kintetsu).....	20-9
Figure 21-1: Fiscal Deficits and Real GDP Growth Rate	21-2
Figure 21-2: Major Expenditure Items.....	21-2
Figure 21-3: Public Debt Composition (2020/21)	21-3
Figure 21-4: Redemption Profile of Public Debt.....	21-3
Figure 21-5: Outstanding External Debt by Creditor (2021)	21-3
Figure 21-6: Total External Debt to GDP Ratio	21-4
Figure 21-7: Debt Service Ratio.....	21-4
Figure 21-8: GFCF Trends in Current Prices	21-4
Figure 21-9: GFCF Breakdown (2019-20).....	21-4
Figure 21-10: Debt Sustainability of Government of Bihar.....	21-5
Figure 21-11: Public Debt of Government of Bihar	21-6
Figure 21-13: Women Only Car at Delhi Metro.....	21-14
Figure 21-14: Woman Employee at DMRC	21-14
Figure 21-15: Station Area Signage at Delhi Metro	21-14
Figure 22-1: Outstanding ESG Investments in India.....	22-4
Figure 23-1: Construction Depot Status for PC-04.....	23-6
Figure 23-2: Muck Disposal Site for PC-01.....	23-7
Figure 23-3: Organization Structure of PMRCL	23-10
Figure 24-1: Exterior View of DMRA	24-16
Figure 24-2: General Organizational Structure of Railway Companies	24-18
Figure 24-3: Organization of DMRC	24-21
Figure 24-4: Organization of O&M Department of BMRCL	24-22
Figure 24-5: Organization of O&M Department of MRTJ	24-23
Figure 24-6: Organizational structure that we propose for PMRCL.....	24-24
Figure 25-1: Use of Composite sleepers	25-31

List of Tables

	page
Table 1-1: Goals to be Achieved by Patna Metro Rail Project	1-2
Table 1-2: Outline of this Survey.....	1-2
Table 2-1: Vehicle Registration in Patna	2-5
Table 3-1: Estimated Existing Vehicle in Patna.....	3-5
Table 3-2: Road Length and ROW in Patna.....	3-6
Table 3-3: Revenue Collection and Number of Passengers Carried by BSRTC (2012-13 to 2018-19)....	3-7
Table 3-4: Major Bus Route in Patna.....	3-8
Table 3-5: Infrastructure Projects Supported by Other Donors	3-9
Table 3-6: Contents of Metro Rail Policy, 2017	3-13

Table 3-7: Top30+ Populated Cities with Metro Development Status.....	3-3
Table 3-8: Per Capita Income/Consumption/Saving for Patna and Bihar Average.....	3-4
Table 4-1: Traffic Demand for Different Scenarios	4-4
Table 4-2: Potential Section with High PHPDT by Road Sections	4-5
Table 4-3: Maximum PHPDT for Metro Corridors	4-5
Table 4-4: PHPDT for Stations of Metro Corridor 1	4-6
Table 4-5: PHPDT for Stations of Metro Corridor 2	4-6
Table 4-6: Daily Trips	4-7
Table 4-7: Revised Daily Ridership for Metro Corridors.....	4-8
Table 4-8: Revised PHPDT for Stations of Metro Corridor 1	4-9
Table 4-9: Revised PHPDT for Stations of Metro Corridor 2	4-9
Table 4-10: Revised Maximum PHPDT for Metro Corridors	4-10
Table 4-11: Projected Modal Share (trip-based).....	4-10
Table 4-12: Expected Road Closure during Construction Period.....	4-11
Table 4-13: Phased Construction Plan	4-12
Table 4-14: Estimation Result of Traffic Impact during Construction Period.....	4-13
Table 5-1: Patna Metro Project Network Study Scope	5-1
Table 5-2: Horizontal Curves	5-13
Table 5-3: Minimum Track Spacing and Rail Level in the Elevated Section	5-14
Table 5-4: Minimum Track Spacing and Rail Level in the Underground Section.....	5-15
Table 5-5: Cant and Transition Curve Length by Curve Radius.....	5-15
Table 5-6: List of locations where the circular curve length is insufficient	5-16
Table 5-7: Proportion of Curve.....	5-17
Table 5-8: Cant and Transition Curve Calculation Results	5-18
Table 5-9: The length of straight section between reverse curves	5-21
Table 5-10 : Curved section platform widening expansion	5-21
Table 5-11: Result of Gradient Correction	5-22
Table 5-12: Location of Conflicts.....	5-23
Table 5-13: Corridor 1 CLC-14 Result of curve specification adjustment.....	5-25
Table 5-14: Corridor 2 CLC-3 Result of curve specification adjustment	5-25
Table 5-15: Corridor 2 CLC-16 Result of curve specification adjustment.....	5-26
Table 5-16: Reverse curve intersection coordinate adjustment result.....	5-27
Table 5-17: Turn-Outs.....	5-30
Table 5-18: The Review Result of the Existing Road Bridges during Construction	5-48
Table 5-19: Structure Type of Corridor 1 (As of 15th September 2022)	5-51
Table 5-20: Structure Type of Corridor 2 (As of 15th September 2022)	5-52
Table 5-21: Comparison Table of 4 TBMs Cases between Patna Junction Station and Case of in Japan..	5-
	71
Table 5-22: Comparison Table of Vertical 2 TBMs Case in Japan	5-72
Table 5-23 : Comparison Table for TBM sequence at Patana Junction Station	5-72
Table 5-24 : Points of attention for TBM Construction	5-78
Table 5-25: The number of Cross Passage for Corridor 1	5-79

Table 5-26: The Number of Cross Passage for Corridor 2	5-79
Table 5-27 : Inundation Countermeasures for Subways in Japan and Thailand.....	5-85
Table 5-28 : Seismic Design Method by PMRCL/DMRC for Civil Structures	5-87
Table 5-29 : Seismic Counter Measure Method for Civil structures	5-88
Table 5-30: Outline of Casting Yard	5-89
Table 6-1: Corridor-1 Stations.....	6-1
Table 6-2: Corridor-2 Stations.....	6-2
Table 6-3: Outline of Elevated Station Type	6-2
Table 6-4: Outline of Underground Station Type	6-2
Table 6-5: Outline of Station Design Criteria.....	6-3
Table 6-6: Patna Metro Station Facility Barrier-Free Design Criteria	6-6
Table 6-7: Patna Metro Station Facility Gender and Infant design consideration plan	6-8
Table 6-8: Outline of Interchange Station.....	6-10
Table 7-1: Measures to Strengthen Connectivity between Metro and Existing Transport System (proposed in DPR).....	7-2
Table 7-2: A Roadmap for Intermodal Integration Policies (proposed by JST)	7-4
Table 8-1: Future Operation Plan (Corridor 1).....	8-2
Table 8-2: Future Operation Plan (Corridor 2).....	8-2
Table 8-3: Revised PHPDT for Stations of Metro Corridor 1	8-3
Table 8-4: Revised PHPDT for Stations of Metro Corridor 2	8-3
Table 8-5: Number of Trains and Vehicles	8-7
Table 8-6: Hourly Train Operation Plan : Corridor 1 (Danapur – Khemni Chak).....	8-8
Table 8-7: Hourly Train Operation Plan : Corridor 2 (Patna Junction – New ISBT)	8-8
Table 8-8: Vehicle Kilometer : Corridor 1 (Danapur – Khemni Chak).....	8-9
Table 8-9: Vehicle Kilometer : Corridor 2 (Patna Junction – New ISBT)	8-9
Table 9-1: The main technical specifications of CBTC	9-1
Table 9-2: The main technical specifications of CBI and Other Signaling Facilities	9-2
Table 9-3: The Main Technical Specifications of Telecommunication Facilities	9-4
Table 9-4: International/Regional Standards adopted for PMRCL's signaling facilities	9-6
Table 9-5: International/Regional Standards adopted for Telecommunication facilities	9-13
Table 10-1: The Main Technical Specifications of AFC System Facilities	10-1
Table 10-2: International/Regional Standards adopted for PMRCL's AFC system facilities.....	10-2
Table 11-1: Rolling Stock Required.....	11-1
Table 11-2: Technical Details of Rolling Stock	11-2
Table 12-1: Sources of Power Supply.....	12-1
Table 12-2: Main Equipment of Possible Installation in RSS	12-2
Table 12-3: Power Demand Estimation	12-3
Table 12-4: Comparison of Power Requirement and Main Equipment Capacity.....	12-3
Table 12-5: Feature of Traction System	12-4
Table 12-6: Characteristics of Electric Contact Line System.....	12-5
Table 12-7: Main Equipment of Possible Installation in Traction Equipment	12-6
Table 12-8: Main Equipment of Possible Installation in Auxiliary Equipment.....	12-7

Table 12-9: Specifications of Auxiliary Loads	12-9
Table 12-10: VAC System Design Requirements	12-11
Table 13-1: NEW ISBT Depot Basic Specifications	13-1
Table 13-2: Lines, Buildings, and Facilities in Depot.....	13-5
Table 13-3: Plant and Machinery in Workshop	13-6
Table 14-1: Environmental Condition along Patna Metro	14-1
Table 14-2: Weather Condition in Patna	14-6
Table 14-3: Weather Condition in Patna	14-8
Table 14-4: Supervisory authority, Inspection authority for each category in India.....	14-9
Table 14-5: Gap between EIA Procedure in India and JICA guidelines	14-10
Table 14-6: Environment-related Permits	14-13
Table 14-7: Other environment-related Acts, Regulations	14-14
Table 14-8: Comparative Study Results of Alternatives	14-17
Table 14-9: Comparative study results of alternatives	14-24
Table 14-10: Comparative study results of Depot alternatives.....	14-29
Table 14-11 Scoping for the Project Facilities with Reasons Evaluated.....	14-34
Table 14-12 Scoping for the Related Facilities (Quarry, Borrow-Pit, and Construction Yard) with reasons for Evaluation	14-37
Table 14-13 Content and analysis method of baseline survey.....	14-39
Table 14-14 Survey Result in dry season	14-42
Table 14-15 Survey Result in rainy season	14-43
Table 14-16 Result of Ground water quality in dry season (1).....	14-46
Table 14-17 Result of Ground water quality in dry season (2).....	14-47
Table 14-18 Result of Ground water quality in rainy season	14-48
Table 14-19 Result of Surface water quality in rainy season	14-49
Table 14-20 Excavated Soil Transportation, and Reuse and Storage of Crushed Stones.....	14-52
Table 14-21 Result of Soil Quality in dry season	14-53
Table 14-22 Result of Soil Quality in rainy season	14-53
Table 14-23 Standard of India	14-54
Table 14-24 Result of Noise level in dry season	14-54
Table 14-25 Results of Noise Level in rainy season.....	14-54
Table 14-26 Results of Vibration Level in dry season	14-55
Table 14-27 Results of Vibration Level in rainy season	14-55
Table 14-28 List of sensitive receptors along Patna metro.....	14-56
Table 14-29: Standards for regulation of noise generated by specific construction work	14-57
Table 14-30: Noise and vibration generated by construction machines for pile-driving works.....	14-57
Table 14-31: Result of Noise Prediction.....	14-58
Table 14-32: Result of Vibration Prediction	14-59
Table 14-33 Prediction Condition for Patna Metro	14-62
Table 14-34: Result of Noise Prediction.....	14-63
Table 14-35 Protected Area in Bihar.....	14-66
Table 14-36 Entrance and Inside of SGB Park (Patna Zoo).....	14-67

Table 14-37 List of birds and mammals in enclosures/cages in Patna Zoo.....	14-67
Table 14-38 Identified species along the alignments (Natural Vegetation).....	14-71
Table 14-39 Identified species along the alignments (Mammals)	14-74
Table 14-40 Identified species along the alignments (Avifauna).....	14-74
Table 14-41 Identified species along the alignments (Butterflies)	14-75
Table 14-42 Identified species along the alignments (Reptilia)	14-75
Table 14-43 Key Species for KBA designation.....	14-76
Table 14-44: Categorization of Assessment Unit Based on Quantity	14-79
Table 14-45 List of Heritage Structure in Patna	14-82
Table 14-46: Traffic Accidents in Patna City.....	14-84
Table 14-47: Traffic Accidents in Patna City.....	14-84
Table 14-48: Results of Assessment for the Project	14-86
Table 14-49: Environmental Management Plan prepared by PMRCL.....	14-91
Table 14-50: Implementation status of Environment Management Plan	14-93
Table 14-51: Proposed Mitigation Measures against expected Impacts (Pre-Construction or Construction Phase)	14-96
Table 14-52: Proposed Mitigation Measures against expected Impacts (Operation Phase)	14-101
Table 14-53: Environmental Monitoring Plan prepared by PMRCL	14-104
Table 14-54: Example of air quality monitoring result	14-105
Table 14-55: Example of noise monitoring result	14-105
Table 14-56: Environmental Monitoring Plan (Pre-Construction and Construction Phase) proposed by the survey	14-107
Table 14-57: Environmental Monitoring Plan (Operation Phase)	14-115
Table 15-1: PER CAPITA NET STATE DOMESTIC PRODUCT AT CONSTANT PRICES; BASE YEAR 2011-12	15-1
Table 15-2: Population, Population Density and Households	15-2
Table 15-3: Circles and Wards in Patna Municipality Corporation	15-3
Table 15-4: Language in State of Bihar	15-3
Table 15-5: Religion and Caste in State of Bihar	15-3
Table 15-6: Final Education Level in Bihar and India.....	15-4
Table 15-7: Distribution of Household Members by Education Level	15-4
Table 15-8: Distribution of Households by Number of Earning Members	15-5
Table 15-9: Distribution of Household Members by Occupation.....	15-5
Table 15-10: Distribution of Households by Monthly Household Income	15-6
Table 15-11: Poverty Line of India and Bihar per Person per Month	15-7
Table 15-12: Calculated Poverty Line per Household per Month	15-7
Table 15-13: Contribution of Indicators to MPI Score	15-8
Table 15-14: Poverty Rate, Intensity, and MPI in Patna and India	15-9
Table 15-15: Poverty Rate of Patna, Bihar and India by Indicator.....	15-9
Table 15-16: Infant mortality rates in Bihar and India.....	15-10
Table 15-17: Life Expectancy and Patient Rates in Bihar.....	15-11
Table 15-18: Distribution of Households by Vehicle Ownership	15-11

Table 15-19: Distribution of Individuals by Average Monthly Expenditure on Transport.....	15-11
Table 15-20: Distribution of Vehicular and Walk Trips by Purpose	15-12
Table 15-21: Vehicles Registration in Patna.....	15-12
Table 15-22: Distribution of Road Length by Peak Hour Journey Speed	15-14
Table 15-23: Distribution of Road Length by Off-Peak Hour Journey Speed	15-14
Table 15-24: Road Accidents in Patna.....	15-15
Table 15-25: Due Process by the Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013 (Land Acquisition Act 2013).....	15-16
Table 15-26: System, Target, and Process of Compensation and Assistances Defined by Land Acquisition Act (2013).....	15-17
Table 15-27: Structure of the Bihar Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Rules, 2014.....	15-18
Table 15-28: Comparison of JICA Guidelines with Indian Acts and Rules	15-20
Table 15-29: Summary of Land Acquisition, Resettlement and Relocation	15-27
Table 15-30: Updated Land Requirement for Corridor 1 and Corridor 2 at July 2022 (in ha).....	15-29
Table 15-31: Progress of Land Acquisition	15-29
Table 15-32: Number of Affected Landowners Recognized in State SIA	15-31
Table 15-33: Social Class of Affected Landowners in State SIA	15-32
Table 15-34: Type of Family of Affected Landowners in State SIA.....	15-32
Table 15-35: Source of Drinking Water of Affected Landowners in State SIA.....	15-33
Table 15-36: Provision of Toilet Facility and Source of Sanitation in the Residential Premises of Affected Landowners in State SIA.....	15-33
Table 15-37: Annual Income of Affected Landowners in State SIA.....	15-34
Table 15-38: Occupation of Affected Landowners in State SIA	15-34
Table 15-39: Preferred Measure of Compensation of Affected Landowners in State SIA.....	15-35
Table 15-40: Possible Use of the Received Compensation	15-35
Table 15-41: Main Concern of Affected Landowners in State SIA	15-36
Table 15-42: Comparison of Land Prices: MVR, With Solatium, Claimed Value by Owners.....	15-36
Table 15-43: Perception about Impact of the Project: Economic Impact.....	15-37
Table 15-44: Perception about Impact of the Project: Impact on Transportation	15-38
Table 15-45: Perception about Impact of the Project: Social Impact.....	15-38
Table 15-46: Perception about Impact of the Project: Impact on Health	15-39
Table 15-47: Perception about Impact of the Project: Impact on Environment	15-39
Table 15-48: Number and Location of Affected Structures and PAHs in DPR SIA 2020	15-39
Table 15-49: Update of the Number and Location of Affected Structures.....	15-40
Table 15-50: Affected Structures	15-41
Table 15-51: Magnitude of Impacts on Structures.....	15-41
Table 15-52: Location-wise, Purpose-wise Number of Affected Structures	15-42
Table 15-53: PAHs for Resettlement in DPR SIA 2020.....	15-42
Table 15-54: Updated PAHs for Resettlement as of July 2022	15-44
Table 15-55: Affected Crops and Trees.....	15-44
Table 15-56: Vulnerable Families.....	15-45

Table 15-57: Religion-wise Distribution of PAHs.....	15-46
Table 15-58: Distribution of PAHs by Castes.....	15-47
Table 15-59: Distribution of PAPs According to Age	15-47
Table 15-60: Distribution of PAPs According to Education Level	15-48
Table 15-61: Marital Status of PAPs.....	15-48
Table 15-62: Occupation-wise Distribution of PAPs	15-49
Table 15-63: Distribution of Monthly Personal Income of Working PAPs	15-50
Table 15-64: Vulnerable Families.....	15-51
Table 15-65: Entitlement Matrix	15-53
Table 15-66: Institutions for Resettlement Activities	15-59
Table 15-67: Institutions for Resettlement Activities	15-60
Table 15-68: RAP Implementation Progress and Schedule.....	15-62
Table 15-69: Details of Cost of Land and Structure	15-63
Table 15-70: Details of Cost of Resettlement and Rehabilitation.....	15-64
Table 15-71: Indicators for Monitoring of RAP Progress	15-65
Table 15-72: Indicators for Project Outcome Evaluation.....	15-66
Table 15-73: Last Mile Connectivity Strategy by Delhi Metro	15-68
Table 15-74: Interview of Autorickshaw Drivers	15-70
Table 15-75: Interview of Institutions Related Bus Operation	15-71
Table 15-76: Gender Related Acts and Policies.....	15-73
Table 15-77: Gender Integration Efforts by Other Metro/Rail Projects in India	15-75
Table 15-78: Patna Metro Station Facility Gender and Infant Design Consideration Plan.....	15-76
Table 15-79: List of Gender Indicators for Monitoring of Gender Integration	15-77
Table 15-80: Patna Metro Station Facility Barrier-Free Design Criteria	15-79
Table 16-2: Summary of PC Results Conducted by PMRCL (2).....	16-2
Table 16-3: Summary of PC Results Conducted by PMRCL (3).....	16-2
Table 16-4: Summary of PC Results Conducted by PMRCL (4).....	16-3
Table 16-5: Summary of PC Results Conducted by PMRCL (5).....	16-3
Table 16-6: PC Photos Conducted by PMRCL	16-4
Table 16-7 Summary of the Result – 2 nd Public consultation.....	16-5
Table 16-8 Photos of 2 nd PC	16-6
Table 16-9: Locations, Date, Number of Attendants of the Public Hearing	16-8
Table 16-10: Photo Records of Public Hearing by District Administration.....	16-8
Table 16-11: Photo Records of Interview Survey and Focus Group Discussion	16-9
Table 16-12: Opinions Presented in the State Public Hearing: Depot Area (Report 1).....	16-12
Table 16-13: Opinions Presented in the State Public Hearing: New ISBT Sta. Area (Report 2)	16-12
Table 16-14: Opinions Presented in the State Public Hearing: University Sta. and Akashvani Sta. Area (Report 3)	16-13
Table 16-15: Opinions Presented in the State Public Hearing: Jagannpura Sta., Ramakrishnanagar Sta., and Mithapur Viaduct Area (Report 4)	16-13
Table 16-16: Opinions Presented in the State Public Hearing: Rukanpura Sta., Raja bazar Sta. and Patna Sta. Areas (Report 5).....	16-14

Table 16-17: Opinions Presented in the State Public Hearing: PMCH Station Area (Report 6).....	16-15
Table 18-1: Estimated Revenue from TOD (In Rs.Crore).....	18-1
Table 18-2: Development Status around Metro Stations (Corridor 1).....	18-1
Table 18-3: Development Status along Metro Stations (Corridor 2)	18-3
Table 18-4: Examples of Land Value Capture (LVC)	18-4
Table 18-5: Examples of Land Value Capture (LVC) in Japan.....	18-7
Table 18-6: Proposal of services to be implemented in this project (TOD)	18-8
Table 19-1: NCMC introduction status in metro companies.....	19-3
Table 19-2: Terms of tenders for AFC applied PPP scheme for metros in India	19-4
Table 19-3: Transportation apps widely used in Patna.....	19-4
Table 19-4: Proposal of services to be implemented in this project (DX)	19-10
Table 20-1: Rate for Non Fare Box Revenues.....	20-1
Table 20-2: Non-Fare Box Revenue	20-1
Table 20-3: Estimation of Non Fare Box Revenue for Patna Metro (Rs. In Crores)	20-2
Table 20-4: Ratio of Non Fare Box Revenue(Rs. In Crore).....	20-3
Table 20-5: Revenue Breakdown for Metro Operators (FY2020)	20-4
Table 20-6: Comparing Planned and Actual Passenger Rates for Metro Projects in India	20-4
Table 20-7: Trends in non-fare box business of Indian metro/railway companies	20-5
Table 20-8: Proposal of services to be implemented in this project (Non-Fare Box Business)	20-9
Table 21-1 Budget Allocation for the MoHUA	21-6
Table 21-2 Fund Arranged by MoHUA	21-7
Table 21-3 Budget Allocation for the GoB.....	21-7
Table 21-4 Fund Arranged by GoB.....	21-7
Table 21-5: Profit and Loss Statement of PMRCL (2019/20, 2020/21and 2021/22).....	21-9
Table 21-6: Equity Share Capital by GoI and GoB	21-9
Table 21-7: Balance Sheet of PMRCL (2019/20, 2020/21and 2021/22)	21-11
Table 21-8: Cash Flow Statement of PMRCL (2019/20, 2020/21and 2021/22)	21-12
Table 21-11: Qualitative Evaluation Indicators	21-13
Table 21-12: Benefit Items in Economic / Financial Analysis	21-15
Table 22-1 CDM conducted by DMRC	22-2
Table 22-2 Carbon Emission Reduced Units in 2020-2021	22-3
Table 22-3 Applicability of CDM Projects for Patna Metro	22-3
Table 22-4 Outline of IRFC Green Bond	22-4
Table 22-5 Sample Items of Information Disclosure on ESG Investment	22-5
Table 23-1: Permission Required for Construction	23-8
Table 23-2: PMRCL Organizational Structure Chart.....	23-10
Table 23-3: List of Board Members/Directors of PMRCL (24.05.2022).....	23-12
Table 24-2: Fields of training for executives.....	24-14
Table 24-3: Category and occupation	24-14
Table 24-4: Occupation Wise Training Duration.....	24-15
Table 24-5: Number of drivers required in horizon year.....	24-16
Table 24-6: Facilities of DMRA	24-16

Table 24-7: O&M Departments.....	24-19
Table 24-8: Administrative Units.....	24-19
Table 24-9: Worksites Reporting Structure	24-20
Table 24-10: Location of Non-rail Business Unit.....	24-20
Table 24-11: Number of personnel in DMRC's O&M department.....	24-21
Table 24-12: Number of personnel in BMRCL's O&M department	24-22
Table 24-13: Proposed Major Segregation of Duties in PMRCL's O&M.....	24-24
Table 24-14: Comparison of Personnel Composition between Japanese subway Operators and DMRC.24-	25
Table 24-15: Comparison of personnel composition between Japanese subway operators and DMRC in the maintenance sector	24-26
Table 24-16: Number and Percentage of Personnel by Department on worksite organizations of Japanese subway operators	24-26
Table 24-17: Estimated number of personnel needed by department in DMRC and PMRCL (2024)..24-27	
Table 24-18: Number of trains in operation by time of day as proposed by DPR and JICA study Team (Corridor-1)	24-27
Table 24-19: Number of trains in operation by time of day as proposed by DPR and JICA studyStudy Team (Corridor-2).....	24-28
Table 24-20: Number of rakes required in the horizon year (proposed by JST)	24-28
Table 24-21: Calculation of the Number of drivers required in horizon year	24-29

Abbreviations and Acronyms

AAGR	Annual Average Growth Rate
AC	Alternating Current
ACDB	AC Distribution Board
ADB	Asian Development Bank
AF	Audio Frequency
AFC	Automatic Fare Collection
AFG	Automatic Fare Gate
AHU	Air Handling Unit
AI	Artificial Intelligence
AMS	Auxiliary Main Substation
App	Application
ASI	Archaeological Survey of India
ASS	Auxiliary Substation
ATD	Auto-Tensioning Device
ATM	Automated Teller Machine
ATO	Automatic Train Operation
ATP	Automatic Train Protection
ATS	Automatic Train supervision
B/C	Benefit over Cost
BCC	Backup Control Center
BERC	Bihar Electricity Regulatory Commission
BSPTCL	Bihar State Power Transmission Company Limited
BT	Existing Bus Terminal
CBD	Central Business District
CBI	Computer-based Interlocking

CBM	Condition-Based Maintenance
CBTC	Continuous Automatic Train Control System
CCHS	Central Clearing House System
CCTV	Close Circuit TeleVision
CDAC	Centre for Development of Advanced Computing
CE	Conformité Européenne
CENELEC	Comité Européen de Normalisation ELECtrotechnique
CFRS	Central Fault Reporting System
CIBE	Commercial, industrial and business enterprise
CMP2018	Comprehensive Mobility Plan Patna in 2018
CP	Counterpart
CVC	Central Vigilance Commission
CVRS	Central Voice Recording System
DC	Direct Current
DCC	Depot Control Center
DF/R	Draft Final Report
DG	Diesel Generator
DISCOM	Distribution company
DMRC	Delhi Metro Rail Corporation
DoT	Department of Telecommunications
DPR	Updated Detailed Project Report for Metro Rail System in Patna
DTG	Distance To Go
DTO	Driverless Train Operation
DVRS	Digital Voice Recording System
DX	Digital Transformation
E&M	Electrical & Mechanical

EB	Emergency Break
EC	Environmental Clearance
EDC	External Development Charge
EFO	Excess Fare Office
EHV	Extra High Voltage
EIA	Environmental Impact Assessment
EIRR	Economic Internal Rate of Return
EMI	Electro Magnetic Interference
EMP	Environmental Management Plan
EMV	Europay Master Visa
EN	European Norm
ESIA	Environment and Social Impact Assessment
EV	Electric Vehicle
F/R	Final Report
FAR	Floor-Area Ratio
FCC	Federal Communications Commission
FCU	Fan Coil Unit
FGD	Focus Group Discussion
FIRR	Financial Internal Rate of Return
FOTS	Fiber Optics Transmission System
FRBM	Fiscal Responsibility and Budget Management
FS	Feasibility Study
FSB	Full Service Brake
GDP	Gross Domestic Product
GE	Gigabit Ethernet
GFCF	Gross Fixed Capital Formation

GHG	Greenhouse Gases
GNSS	Global Navigation Satellite System
GoB	Government of Bihar
GoI	Government of India
GPS	Global Positioning System
GSDP	Gross State Domestic Product
GSS	Grid Substation
HH	Household
HH rail	Head Hardened rail
HT	High voltage
IDA	International Development Association
IEC	International Electrotechnical Commission
IEEE	Institute of Electrical and Electronics Engineers
IETF	the Internet Engineering Task Force
IP	Internet Protocol
IPP	Indigenous Peoples Plan
IRR	Internal Rate of Return
IRS	Indian Railway Standard
ISM	Industrial, Scientific and Medical
ISO	International Organization for Standardization
IT/R	Interim Report
ITU-T	International Telecommunication Union Telecommunication
JST	JICA Study Team
LAP	Land Acquisition Plan
LARRA	Right to Fair Compensation and Transparency in Land Acquisition,
LCD	Liquid Crystal Display

LED	Light-Emitting Diode
LILO	Line In Line Out
LT	Low voltage
LVC	Land Value Capture
MaaS	Mobility as a Service
MCCB	Molded Case Circuit Breaker
MMI	Man Machine Interface
MoEFCC	Ministry of Environment, Forest and Climate Change
MoHUA	Ministry of Housing and Urban Affairs
MPI	Multidimensional Poverty Index
MPLS	Multi-Protocol Label Switching
NBC	National Building Code
NCMC	National Common Mobility Card
NFC	Near Field Communication
NFPA	National Fire Protection Association
NMS	Network Management System
NPCI	National Payment Corporation of India
O&M	Operation and Maintenance
OCC	Operation Control Center
OHE	Overhead Equipment
ONVIF	Open Network Video Interface Forum
PA	Passenger Address system
PAH	Project Affected Households
PAP	Project Affected Person
PBX	Private Branch eXchange
PCs	Public Consultations

PIDS	Passenger Information Display System
PMP2031	Patna Master Plan 2031
PMRCL	Patna Metro Rail Corporation Limited
POM	Passenger Operated Machine
PPP	Public Private Partnership
PSD	Platform Screen Door
PSTM	Procedure for Safety Certification and Technical Clearance of Metro
QOL	Quality of Life
QR	Quick Response
qSparc	Quick Specification for Payment Application of Rupay Chip
RAP	Resettlement Action Plan
RC	Return Conductor
RDSO	Research Designs & Standards Organisation
RFC	Request for Comments
ROCS	Rigid Overhead Conductor System
RPO	Renewable Purchase Obligation
RSS	Receiving Substation
SC	Scheduled Caste
SBPDCL	South Bihar Power Distribution Company Limited
SCR	Station Control Room
SD	Subordinate Debt
SGB Park	Sanjay Gandhi Botanical Park
SIA	Social Impact Assessment
SIL	Safety Integrity Level
SIP	Session Initiation Protocol
ST	Scheduled Tribe

STU	State Transmission Utility
SUICA	Super Urban Intelligent Card
TBM	Tunnel Boring Machine
TEC	Telecommunication Engineer Center
TES	Track Exhaust System
TETRA	TERrestrial Trunked RAdio
TOD	Transit Oriented Development
TOM	Ticket Office Machine
TR	Ticket Reader
TRAI	Telecom Regulatory Authority of India
TSS	Traction Substation
TTC	Travel Time Cost
TVM	Ticket Vending Machine
TVS	Tunnel Ventilation System
UL	Underwriters Laboratories (Limited Liability Company)
UPS	Uninterruptible Power Supply
UTO	Unattended Train Operation
VAC	Ventilation and Air Conditioning
VCF	Value Capture Finance
VOC	Vehicle Operating Cost
VRV	Variable Refrigerant Volume
VVVF	Variable Voltage Variable Frequency
WPC	Wireless Planning & Coordination wing
XLPE	Cross-linked Polyethylene
JSSS	JICA Standard Safety Specification
ROD	Revenue Operation Date

SBD	Standard Bidding Documents
ICB	International Competitive Bidding
LCB	Local Competitive Bidding
JPG	JICA Procurement Guideline
QCBS	Quality- and Cost-Based Selection
PQ	Prequalification
MPW	Manual for Procurement of Works
SPD	Standard Prequalification Document
LOA	Letter of Acceptance
GC	General Consultant
E/N	Exchange of Notes
CMRC	Commissioner of Railway Safety